



## **New Worcester North High School: Construction Management and Constructability Analysis**

A Major Qualifying Project  
Submitted to the faculty of Worcester Polytechnic Institute  
In partial fulfillment of the requirements for the  
**Degree of Bachelor of Science**

### **Submitted By:**

Scott MacDonald

Ryan Marques

Matthew Moreau

**Sponsoring Agency:** Gilbane Building Company

### **Submitted To:**

Project Advisors: Guillermo Salazar

Paramasivam Jayachandran

Date: March 15, 2010

## **Abstract**

This project presents three main deliverables concerning the construction of North High School in Worcester, Massachusetts. These are: a construction management analysis, a construction cost estimate developed by using a Building Information Model, and an alternative design of the retaining wall located near the corner of the auditorium and Building B. In addition, an earned value analysis of two steel oil tank replacements in South Portland, Maine was also conducted.

## Authorship Page

1.0 Introduction	Matt
2.0 Background	Matt, Ryan, & Scott
3.0 Scheduling & Safety	Ryan & Scott
4.0 Project Estimate Using Revit	Matt & Ryan
5.0 Earned Value Analysis	Scott
6.0 Retaining Wall Design	Matt
7.0 Results and Conclusions	Matt, Ryan, & Scott

## Acknowledgments

Our Major Qualifying Project team would like to thank all of the individuals that contributed to us during the duration of our project. Our team would especially like to thank our advisors, Professor Guillermo Salazar and Professor Paramasivam Jayachandran for their help and guidance to completing the project. Our team would also like to thank the Gilbane team that was working on the North High School project, including William Kearney Jr., Melissa Hinton and Don Venerus, for providing us valuable information, including the architect's drawings, and allowing us to attend owner meetings.

## Capstone Design Experience Statement

In order to complete the capstone design requirements for this Major Qualifying Project, the group conducted an alternative design for a retaining wall located near the corner of the Building B and the auditorium of the new Worcester North High School in Worcester, Massachusetts. The retaining wall performs load carrying capabilities during construction and at the same time protects lower lying houses from any potential soil falling off of the sixty foot cliff that the wall would be built into. The alternative design for the retaining wall included economic factors as well.

The alternative design of the retaining wall consisted of investigating the advantages and disadvantages different types of retaining walls, determining the vertical and horizontal pressures against the wall as well as the type of soil located on the construction site, and performing a structural analysis. The vertical surcharge of the wall was determined by using the live loads that are typically carried by fire lanes.

The proposed solution for the wall is a cantilever retaining wall with counterforts. Adding counterforts to the wall adds more strength without making the heel slab very long. Also, counterforts are typically added to embankments that are greater than eight meters in height. As some parts of the embankment at the construction site exceeds sixty feet, it was necessary to add counterforts to the retaining wall.

The economic aspects of the proposed solution for the retaining wall was compared with the one actually implemented in the site primarily in terms of the total amount of material and cost required to build both solutions. The economic issues surrounding this retaining wall are rather important as the type of wall was changed from a semi-gravity retaining wall to a smaller in size counterfort retaining wall, costing an estimated \$10,000 less.

The proposed design addressed the constructability aspects of the retaining wall and the safety aspects of the design process as well. We addressed safety and constructability issues that included wall overturning, base sliding, and soil bearing capacity failures. After investigating these different constructability issues and calculating factor of safety values, we found that our solution exhibits structurally sound qualities and is publically safe as well. The key to successful engineering is analyzing the situation from a public safety point of view, and determining whether a conservative or an aggressive approach should be used for that particular situation.

# Table of Contents

Abstract .....	I
Authorship Page.....	II
Acknowledgments.....	III
Capstone Design Experience Statement .....	IV
Table of Contents .....	VI
List of Figures.....	IX
List of Tables .....	XI
Chapter 1- Introduction.....	1
Chapter 2 - Background .....	3
2.1 Development of Previous Worcester North High Schools .....	3
2.2 Demand for a New High School.....	4
2.3 Development of the Worcester North High project.....	4
2.4 Project Organization .....	6
2.4.1 Gilbane Building Company .....	8
2.4.2 The Maguire Group.....	8
2.4.3 The City of Worcester-Architectural Services.....	9
2.5 Construction Manager at Risk .....	9
2.6 Project Objectives and Expectations.....	10
2.7 Prior Challenges.....	10
Chapter 3 - Project Scheduling and Safety .....	12
3.1 Safety .....	16
Chapter 4 – Using BIM (Building Information Modeling) .....	17
4.1 Getting Started .....	19

4.2 Foundation .....	20
4.3 Steel.....	21
4.4 Quantity Take-Off/Cost Estimate .....	21
4.5 Concrete and Steel Quantity Takeoff.....	22
4.6 Steel Estimate.....	24
4.7 Concrete Estimate .....	25
Chapter 5 - Earned Value Analysis.....	26
5.1 Earned Value Analysis.....	26
5.2 Project Background.....	29
5.3 Project Plan .....	29
5.4 Means/Methods.....	31
5.5 Project EVA Analysis .....	35
Chapter 6 – Design and Constructability Analysis of New Retaining Wall.....	41
6.1 Original Retaining Wall Design-Pre Construction Phase.....	41
6.2 Retaining Wall Changes- During Construction .....	43
6.3 New Cantilever Retaining Wall Design with Counterforts .....	47
6.4 Preliminary Design .....	48
6.4.1 General Pressures on the Wall .....	49
6.4.2 Further Investigation and Shear Calculations .....	51
6.5 Stability Investigation .....	51
6.6 Steel Reinforcement.....	52
6.7 Design of Counterforts.....	54
6.8 Analysis of Retaining Wall Cross Sections .....	55
Chapter 7 - Results and Conclusions .....	57
7.1 North High Estimate .....	57



7.2 Earned Value Analysis.....	58
7.3 Retaining Wall .....	58
7.4 Gilbane/Owner Architect Meetings .....	61
Works Cited .....	63
Appendix A: Project Schedule as of March, 2009.....	64
Appendix B: Schedule January 2010.....	86
Appendix C: Bid Package Cost vs. Budget Estimate .....	107
Appendix D: Retaining Wall Design .....	108
Appendix E: Cullinan’s Retaining Wall Design.....	141
Appendix F: Monthly Man Hour Totals .....	142
Appendix G: Capstone Design Proposal.....	143
Appendix H: Pictures – North High.....	147
Appendix I: Tank Replacement Project Pictures .....	156
Appendix J: Revit Takeoff Sheets .....	166
Appendix K: Development of the WPI Recreational Center.....	233

## List of Figures

Figure 1: Organizational Chart of the Worcester North High project .....	6
Figure 2: Construction Schedule Change Comparison .....	13
Figure 3: Floor Plan .....	14
Figure 4: March 2009 Milestone Schedule .....	15
Figure 5: North High 3-D Revit Model .....	18
Figure 6: Revit 3D Model Street View (North Elevation).....	19
Figure 7: Revit Model Elevation Levels (Cross section).....	20
Figure 8: 2D Ground Floor Plan .....	21
Figure 9: Foundation Detail .....	31
Figure 10: Concrete Pour .....	32
Figure 11: Concrete Footer Finish .....	33
Figure 12: Tank #2 Concrete Pour .....	34
Figure 13: Concrete Hose .....	34
Figure 14: Concrete Finishing .....	35
Figure 15: Tank 24 WH Analysis .....	37
Figure 16: Tank 24 Cost Analysis .....	37
Figure 17: Tank 23 WH Analysis .....	39
Figure 18: Tank 23 Cost Analysis .....	39
Figure 19: Approximate Area of Construction .....	42
Figure 20: Approximate Area of Cliff .....	42
Figure 21: Riprap .....	43
Figure 22: Plan View of New Retaining Wall .....	44
Figure 23: New Semi-Gravity Retaining Wall .....	44

Figure 24: Cross Sections of Different Retaining Walls .....	45
Figure 25: Cullinan's Retaining Wall Design .....	46
Figure 26: Typical Counterfort Wall .....	48
Figure 27: Preliminary Design of Retaining Wall (Cross section, in inches).....	49
Figure 28: Pressure on the Wall Due to the Surcharge.....	50
Figure 29: Plan View of Counterfort Wall .....	54

## List of Tables

Table 1: Comparison of Construction Schedules.....	12
Table 2: Steel Takeoff.....	23
Table 3: Concrete Takeoff .....	24
Table 4: Steel Estimate .....	25
Table 5: Concrete Estimate.....	25
Table 6: Budget Work Hours .....	35
Table 7: Tank 24 Actual Cost/Budget Cost .....	36
Table 8: Tank 23 Actual Cost/ Budget Cost .....	38
Table 9: Component Weights of Retaining Wall.....	52
Table 10: Vertical and Horizontal Bars .....	53
Table 11: Horizontal and Vertical Reinforcement.....	55
Table 12: Volume of Cross Sectional Area .....	55
Table 13: Cost of Steel Difference.....	57
Table 14: Concrete Estimate per CY .....	58
Table 15: Steel Reinforcement.....	60
Table 16: Counterfort Steel Reinforcement .....	60

## Chapter 1- Introduction

Anywhere in the United States, whether it is in the warm, tropical atmosphere of Florida or the frigid, arctic air of Alaska, structures have been a necessity of living for thousands of years and will continue to be in the future as well. The construction industry is one of the largest industries in the nation contributing to around 5% of the United States' gross domestic product in 2007(<http://www.bea.gov/>). Currently with a tight economy, it is more important than ever for management to keep construction projects on time and within budget.

In the construction industry, project management involves the organizing and working with people to identify problems and determine solutions to situations that eventually occurs within the work site. With more sustainable times ahead, many owners are looking to save money on energy, water, waste disposal, and also reducing their carbon footprint and these changes generally reflect on the engineer and designer's ability to stay within a project scope. Not only do managers need to solve problems, but they also need to be a good motivator and communicator in order for a project to become successful. Projects use methods and tools to perform traditional management functions such as earned value analysis, scheduling, estimating, and now there is an increasing use of virtual construction and Building Information Modeling (BIM) to assist the managers in meeting the time, cost, and quality objectives of the project.

In 1980, students and faculty of Worcester North High School moved from Salisbury Street in Worcester, Massachusetts to what was then called a temporary location at an old middle school building at 150 Harrington Way. This "temporary location" would serve as such for a period close to 30 years as plans for a new high school building were delayed several times due to lack of funding because the immediate need for a new school was not highly prioritized. Often seen during the last decade, the old middle school building was having trouble withstanding a

growing student population and could not keep up with the major changes in technology that have occurred over the years. Finally in 2003, the project was given the go ahead with the funding coming solely from the city of Worcester. The project for a new Worcester North High School broke ground in 2008 and has an estimated completion date for the fall of 2011. After the bidding process was completed, the city of Worcester selected The Gilbane Building Company as the professional construction manager, Maguire Group Inc. as the owner's project manager, and the city's own architect group, Worcester Architectural Services as the designer.

The 72 million dollar project includes 2 buildings, an auditorium, and gymnasium encompassing a total of 225,000 square feet. A project of this size in the heart of Worcester, Massachusetts requires efficient coordination between the owner, designer, general contractor, and subcontractors in order to be on time and on budget. Since construction started in 2008, there have been many issues with design and subcontractors which may have impacted the cost and schedule of the project

The focus of the report was to investigate and analyze the challenges of the construction of the new Worcester North High School. These are a construction management analysis, a construction cost estimate developed by using a Building Information Model, and an alternative design of the retaining wall located near the corner of the auditorium and building B

## **Chapter 2 - Background**

This chapter presents the general information that is associated with the project. The planning and development of a new high school demands a lot of time, coordination effort, and money. The first part of this chapter discusses some of the history of the old Worcester North High School and the reasons behind the need for building a new, state of the art high school. Also included in this chapter are the general concepts developed for the management of the project, including the parties involved and the type of contract agreed upon between the owner and general contractor.

### **2.1 Development of Previous Worcester North High Schools**

North High School is a four year public high school and is located on 150 Harrington Way in Worcester, Ma. North High is one of five public high schools that are in the city of Worcester and it is responsible for the education of 1,124 students as of October 1<sup>st</sup>, 2009. North High School is home to a diverse student population with 40.0% Hispanic, 31.7% White, 19.9% African American, 7.8% Asian or Pacific Islander, and 0.6% Native American. North High School also has a large percentage of its students, 22.2%, receiving special education services. All previous statistics are stated as of October 1<sup>st</sup>, 2009 by Principal Matthew Morse.

The building in which North High School currently inhabits was built in 1971 to be a Junior High School for the city; however in 1980 it became North High School. Prior to the move to the current site, North High School was located on Salisbury Street but after the move this building was closed and sold to a private developer. The move to Harrington Way was considered to be a temporary solution at the time. In 2000 the Worcester City Council agreed to the construction of a new North High School. The completion of the new North High School is

expected to be done by September 2011, in time for the 2011-2012 school year and finally finishing a 30 year period that was spent in the temporary building.

## **2.2 Demand for a New High School**

The community in the temporary building was long overdue for a new high school. In the year 2000 the Worcester City Council deemed the current building old and worn down, and they decided to go ahead with the plan to construct a new high school. Recent malfunctions of the current building were reported in the press (Worcester Telegram & Gazette, 2007). According to the article; Lauren E. Morocco, 17, and Kameran J. Perkins, 18, both seniors, said they're happy future generations won't be subjected to the conditions of the current building, with its broken floor tiles, moldy ceiling tiles, small lockers built into classrooms instead of hallways and lights occasionally sparking (<http://www.thefreelibrary.com>).

In 2008 Worcester North High School set out to develop an improvement plan for its students from 2008 to 2010. Part of this plan included the building of a new, modern high school that could supply all of its students the proper classrooms and equipment to succeed. As stated in North High School's improvement plan mission statement, "The design plans for a new North High School will provide a facility that thoroughly supports our conversion to smaller learning communities."

## **2.3 Development of the Worcester North High project**

Troubles for the building of a new North High School in Worcester started with the move to a temporary building meant for middle school students in 1980. This switch has lasted for almost 30 years because of lack of funding to build a new high school. Then in the year 2000, the Worcester City Council gave the go-ahead to the building of a new North High School, a project that was long overdue. The original estimated cost for the new Worcester high school was \$50



million in 2000. This project was slow to start and ran into delays. With the rising construction costs from 2000 to 2006 the estimated cost for this project jumped to roughly \$78 million.


Then in 2006 the Massachusetts School Building Authority took over the school building aid. The new authority made changes to the states reimbursement schedule for new school projects, changing a Massachusetts's city reimbursement for new schools from 90% to 70%. This new ruling left the city of Worcester with a \$23.6 million funding gap for the new North High School. The North High project seemed to be dormant again.

In October of 2006 the city manager of Worcester, Michael V. O'Brien, revived the new Worcester North High School project. He unveiled a new plan starting with the reduction of square footage in the school. The plan stated 40,000 square feet was to be removed from the design of the new North High School. This reduction left North High School with 190,000 square feet. Reductions were made in public rooms and classrooms in the building. The reduction shrunk parts of the atrium, reduced seating accommodation in the auditorium from 700 to 425 seats, and the gymnasium capacity to 1,295 people. The 16% shrinkage of the building lowered the overall projected cost from \$78 million to \$72.8 million. The redesign of the school delayed the project start date by 2 ½ months, town officials however were still confident they could make up this time and stay on schedule to finish in September of 2011 for the beginning of the school year.

The new arrangement set up a new financing plan which would have the state of Massachusetts contribute \$45 million to the new North High School's project cost. The plan had the city responsible for the remaining \$27 million. Out of the city's responsibility \$15 million of this would come from the state as part of a 2% interest loan. The other \$12 million the city is responsible for was to be borrowed at a higher undisclosed interest rate.

## 2.4 Project Organization

The City of Worcester is the owner of the new North High School in Worcester. The construction is being managed by Gilbane Building Company. The contractual arrangement between the owner and the contractor is Construction Management (CM) at risk. CM at-Risk is a delivery method which entails a commitment by the construction manager to deliver the project within a Guaranteed Maximum Price (GMP). The architect on the job is Architectural Services, an entity of the city. The Maguire Group is a consultant to the city of Worcester for the design of the project. There are also many subcontractors associated with the project. An organization chart is shown in Figure 1.



**Figure 1: Organizational Chart of the Worcester North High project**

The agreement between Gilbane Building Company and the City of Worcester for the construction of the new North High is divided into two phases. The first phase includes site work, concrete, and steel amendments worth roughly \$13 million dollars using a GMP contract. Major site work was completed by Marion Brothers, Inc. from 2008 to March of 2009. The cast-in-place concrete was completed in early spring 2009 by Francis Harvey & Sons, Inc., while the cast-in-place flat work was completed by October 2009 by JL Marshall and Sons. The structural steel was completed by United Steel, Inc., in November of 2009. The second phase will be a GMP contract negotiated between the two parties. At the time of the completion of this study a GMP had yet to be agreed upon between the two parties. The project is broken down into 2 phases because it is a fast track project, which means construction starts before the final design is complete. This allows the contractor, Gilbane to start construction on the early parts needed for the building, that is, site clearing and excavation, concrete, steel erection, rough-in plumbing and electrical.

The sub-contractors hired on this job are being selected through the filed sub-bid process. Massachusetts General Laws require what is known as the “filed sub-bid” system for selecting certain subcontractors on various public construction projects. The Law requires that contractors submit construction bids in two phases. First, subcontractors must submit their bids to the Awarding Authority, which will compile a list of all sub-bids received. The Awarding Authority will send the list to all interested general contractors. Interested contractors will then need to submit their bid including any filed sub-bidders that will be used on the work. It’s important to note that the general contractor is not obligated to use the lowest bidder. In the case of North High, Gilbane needs to get approval by the owner before contracting any sub-contractors.

### 2.4.1 Gilbane Building Company

Gilbane Building Company is a leading construction management firm, based in Providence RI, providing a full slate of facilities-related services for clients in the healthcare, education, government, convention/cultural, mission-critical, corporate, sports/recreation, life sciences, transportation, and criminal justice markets. Gilbane is a highly respected firm in the construction industry with annual revenues that top \$3.5 billion and is # 18 on the top contractors in the US according to ENR (<http://enr.construction.com/toplists/Contractors/001-100.asp>). The main individuals working on this project from Gilbane include:

- **Project Executive** – William Kearney
- **Project Manager** – Tony Iaccarino
- **Field Superintendent** – Al Abdella
- **Project Engineer** – Don Venerus
- **Project Engineer** – Melissa Hinton

### 2.4.2 The Maguire Group

The Maguire Group is one of the nation's leading Architectural, Engineering, Planning and Construction Management firms. They are assisting the owner in both the engineering and construction phases of the work. They mainly help the city of Worcester on major decisions when it comes to cost. Other projects they have worked on in the city of Worcester include WPI's new Gateway education facility and Union Station. Some of the main individuals working on this project from the Maguire group include:

- **Vice President of Project Management** – Tony DiLuzio
- **Project Manager** – Ted Fiffy

### 2.4.3 The City of Worcester-Architectural Services

The city of Worcester is the owner and architect for this project. It is unusual to come across a party assuming the responsibility of both the owner and the designer/architect, but the city of Worcester decided that this type situation would work best for this project. Architectural Services is a subdivision of the Department of Public Works of Worcester, meaning they are city employees. Architectural Services provides professional services for the design and construction of City of Worcester owned buildings. Since its creation in 1993, this group has completed over 150 assignments. Major individuals associated with this project from the city of Worcester include:

- **Designer/Architect** – Eric Twickler
- **Principal of Worcester North** – Matthew Morse
- **Assistant Commissioner of Public Works** – Paul Moosey

### 2.5 Construction Manager at Risk

As described briefly above, CM at-Risk is a delivery method which entails a commitment by the construction manager to deliver the project within a Guaranteed Maximum Price. The construction manager acts as construction consultant to the owner in the development and design phases. In addition to acting in the owner's interest, the construction manager must manage and control construction costs to not exceed the GMP, which would be a financial hit to the CM Company. If the contractor completes the job under the GMP, the savings goes back to the owner, or in many cases, shared among the owner and the contractor. This would be determined at the beginning of the project and stated in the contract between the two parties.

This type of project delivery system allows the Owner, Construction Manager and Architect/Engineer to work as a unified team. It is advantageous to include the Construction

Manager at the start of the project to gain the full benefits of their construction knowledge for the team. It is also important that all team members understand their duties and responsibilities required for a successful project. Before design of a project is completed the CM is involved with estimating costs of constructing a project based on hearing from the designer and Owner on what is going to be built.

## **2.6 Project Objectives and Expectations**

A major decision that parties involved with the project, especially the general contractor, is establishing a clear difference between the wants versus the needs. A meeting with Melissa Hinton, who is a project engineer for Gilbane, further discussed the importance of choosing between wants and needs. The types of decisions made in this area of the design process could be the difference between performing under budget or over budget (Hinton, 2009).

Major decisions that were discussed in the meeting were deciding on solar water heaters, smart boards, and a high powered air conditioning unit. The problem with choosing these commodities is that they are great to have in the near term but will not give a financial return until the long term. With a tight economy currently, there are hundreds of these decisions that the project team (contractor, architect, owner) have to make. All parties are involved because an architect will present an idea or concept, the contractor will review the financial impact it will have on the project and give input to the owner on what to do or present alternatives and then it is ultimately up to the owner to make the decision. (Hinton, 2009).

## **2.7 Prior Challenges**

Problems are a common in the construction industry. Ranging from the effects of the national economy on the budget of projects to faulty designs of the structure, poor workmanship

by the subcontractor and flawed materials arriving on-site. Delays are a common occurrence during construction and project managers must be diligent to keep the project on schedule. Every construction project has to deal with dilemmas whether they are long term or day to day and this was also a common theme for the Worcester North High Project.

## Chapter 3 - Project Scheduling and Safety


The activities that are necessary to build the project are interconnected in terms of their sequencing of execution so a schedule based on the order they can be completed in the most economically logical and physically logical procedure to achieve a fast completion time. Schedules are developed to determine the time and order of execution of each of the activities. Cash flow analysis is an extension of the use of the schedule in which the cost associated to each activity is projected over time.

The summary of the original North High School project schedule dated March 3, 2009, contained 15 main activities that last from the start date, March 2009, until the final estimated early completion date, May 11, 2011. The updated schedule as of September 18, 2009, had a changed estimated early completion date of September 8, 2011. This final date has since changed again to August 29, 2011. Changes to the schedule have been made again as of January 22, 2010. The chart below shows the 13 project milestones and their anticipated completion dates. Figure 2 is a chart displaying the information in Table 1.

<b>Item</b>	<b>Proposed Completion as of 3/12/2009</b>	<b>As of 9/18/2009</b>	<b>As of 1/22/2010</b>
Final GMP Submitted	6/8/2009	11/18/2009	3/11/2010
Final GMP Approved	8/7/2009	1/18/2010	5/10/2010
Interior Framing Complete	3/22/2010	4/28/2010	5/14/2010
MEP Rough-In Complete	8/11/2010	6/24/2010	7/19/2010
Exterior Skin Complete	7/14/2010	10/27/2010	11/30/2010
Elevators Complete	7/19/2010	11/24/2010	12/6/2010
Site-Work + Landscape Complete	8/11/2010	11/24/2010	12/29/2010
Roof Complete	1/28/2010	11/24/2010	12/29/2010
Finishes Complete	11/22/2010	1/6/2011	1/14/2010
General Punch List Complete	3/16/2011	3/17/2011	3/25/2011
Project Substantial Completion	3/16/2011	3/17/2011	7/21/2011
Certificate of Occupancy	3/16/2011	3/17/2011	7/21/2011
Project Final Completion	5/11/2011	9/8/2011	9/16/2011


**Table 1: Comparison of Construction Schedules**





**Figure 2: Construction Schedule Change Comparison**

The most up to date schedule as of January 22, 2010 now shows the final completion date to be September 16, 2011. Along with the final completion date of the project, other critical items have been delayed. A major reason for the delay of the project is the city architect, City of Worcester Architectural Services, who has been unable to answer request for information (RFI's) from subcontractors in a timely manner. In an attempt to pick up the pace of the project activities the Construction Manager Gilbane Building Company, accelerated the installation of gypsum board in building A and B instead of wrapping the building for the winter season. The reason wrapping the building, or closing the building in, is essential is because workers will not be able to work on interior installations during the cold New England winter months.



**Figure 3: Floor Plan**

The process used by Gilbane Building Company to deliver the North High School project was a fast track method. In the preconstruction phase of the North High School project, two main activities were performed. The architect/engineer designed North High School including Building A and B which is predominantly classrooms and Building C which includes an auditorium and gymnasium. The construction document phase began after development of the detailed design by the architect. Construction documents are extremely critical because these are needed in order to put out and receive bid from construction subcontractors. Since this project is based on the fast track method the procurement phase started upon completion of schematic designs. The construction phase of North High School contains 12 critical activities. Please refer to Appendix A for a schedule of the project. Site work included excavation and tree removal of the site to make room for the four-story high school, gymnasium and auditorium. The concrete foundations were poured and the structural steel was erected. Metal decking with cast in place concrete floors was used for the floors of the second, third and fourth floors. Following the

erection of the shell of the building, exterior studs were installed and the exterior skin and exterior roof followed. The summary of activities also included the installation of elevators, exterior metal panels and windows, interior framing, finishes and commissioning. The completion phase of the project is known as the close out phase. As you can see below this is the milestone summary as of March 2009.




Figure 4: March 2009 Milestone Schedule

### 3.1 Safety

Safety in the construction industry has changed drastically in the past 20 years. Very rarely do you see men climbing 15 stories above ground level on steel beams without harnesses or sites where construction workers aren't wearing hard hats. Regulations have been set at stricter standards and firms are taking it very seriously. To work for certain owners or even in certain industries, such as the petro-chemical industry, a superb safety record is a must to even be allowed to bid on projects. On a lot of sites, such as Gilbane's North High, new workers must go through a site safety orientation that covers all general safety rules and any site specific rules that may exist. If you are a visitor on site you must be accompanied by someone who has been orientated and familiar with the site. The safety regulations have led to the upbringing of "tool box" meetings and "activity plans" where the foreman goes over with the crew in the morning that activities of the day and the hazards that are accompanied with the tasks. These types of meetings and plans are nearly required on most any large jobsite.

Gilbane Building Company also has an organized monthly man hour report that includes deliveries, visitors and man hours. In this report drug tests are tracked with positive and negative results, incidents and the percentage rate of occurrences are followed, lost time is counted and the project schedule value analysis is calculated. Four workers have tested positive for a banned substance out of 163 since Decemeber 2008. The data has tracked 50,421 man hours as of December 2009 and has recorded only 2 incidents, both in the previous 5 months. It's important to note howeveere there have been no lost time incidents on the project. This information can be found in Appendix F.


## **Chapter 4 – Using BIM (Building Information Modeling)**

Estimating the cost of construction projects is an extremely important aspect of project management. An estimate of a single job can directly affect the profits made by a construction firm. When a project is awarded the budget is developed from the estimate and the owner expects the contractor to meet their budget. At the same time, if the estimator doesn't accurately estimate a job, the firm may not win that many competitive bidding jobs. There are many different ways to estimate jobs when finding the material quantities, from doing it by hand on smaller jobs to using software to do the take-offs. One the defined quantities are calculated a unit price for each of these quantities is assigned and a total cost estimate is developed. The type of project makes the difference whether you can do the take off by hand or are able to use some software. On civil engineering projects, take-offs are usually done by hand because civil engineering projects encompasses so many different structures. In estimating commercial work, it's easier to do the material take-off with Building Information Models because commercial work is all very similar in that they contain columns, girders, foundations, etc. This software uses an object orientated-parametric 3D technology that makes it possible to extract the quantities directly from the BIM.



**Figure 5: North High 3-D Revit Model**


The software program that was used by our MQP team to develop the building model of North High School is called Revit Structures. Revit Structures was developed by Autodesk in 2008 that was meant to be used as a program to extract quantities of work for the model that in turn becomes part of the components of a cost estimate. The development of the Revit model came in stages from the grid lines and elevation settings to the final elements and final review. North High School was broken into three main sections; buildings A, B and C. The first buildings developed were buildings A and B of North High School, which are predominately classrooms, because of their structural similarity. Then following the completion of buildings A and B, building C was developed. Building C houses the auditorium, locker rooms, weight room and gymnasium. This model is based on 2D drawings provided to us by Gilbane generated by the architect.



**Figure 6: Revit 3D Model Street View (North Elevation)**

## **4.1 Getting Started**

The first step in building the North High School model was to develop grid lines and establish elevation levels. The elevation levels were created in order to clarify a correlation between the architectural drawings developed by Architectural Services and our Revit model. The North High School Revit model has 12 elevation levels in all, ranging from the ground floor to the top of the auditorium parapet. After an element is added to a particular level it can be viewed from a 2D view options, the software is created to initially offer north, south, east and west views showing the vertical picture of the element.



**Figure 7: Revit Model Elevation Levels (Cross section)**


Other viewing options are the 3D views, different 3D views can be developed manually and the standard view is offered initially. The 3D views can be rotated at will using A navigation cube is located in the upper right hand portion of the screen; this cube can be used to change the 3D view to investigate and visualize different parts of the model.

## **4.2 Foundation**

Following the implementation of grid lines and elevation levels the next step of the BIM development process was to insert column footings. This function was very simple and completed by following the specifications and making sure each individual footing property matched the specified size. With the footings in place, there weren't any foundation walls to be



inserted for buildings A and B. The foundation wall for building C was implemented later in the process because it had complex elevation changes.



**Figure 8: 2D Ground Floor Plan**

### **4.3 Steel**

Once the foundation was completed, the steel columns were placed in REVIT in compliance with the specifications of the project. The columns in buildings A and B were predominately similar. Building C was more advanced in the difficulty of the design. Building C includes the auditorium and gymnasium. The auditorium included the stage, arena seating, and a parapet. Overall over 2500 steel beams were used in the construction of North High School.

### **4.4 Quantity Take-Off/Cost Estimate**

The cost estimate for North High School was developed by using the architectural plans and specifications. The drawings that were used to complete the take-off are comprised of the four floor levels of buildings A and B, the three levels of the auditorium and the gymnasium. The

materials that were quantified included concrete and steel. The cost estimate for North High School was created by using pricing from the 2010 version of R.S. Mean's method of Building Construction Cost Data. The R.S. Mean's Construction Cost Data book contained the average prices for different types of material that are used in construction, the book also contains a location factor that adjusts costs to the specified area the project is in. The location factor for Worcester is 109.5.

#### **4.5 Concrete and Steel Quantity Takeoff**

The concrete and steel takeoff was performed by Revit Structures using the Schedule function. Revit counted each individual piece of steel or concrete element and created a list of information containing the type of element, the volume and the length. From this all that needed to be calculated was collecting each element into groups of the same element. After the steel elements were properly grouped the tonnage had to be calculated. The tonnage of steel was found by following a few steps. The total length was found by adding up the lengths of each piece of steel with the other pieces of steel in their respective group. Then pounds were found by multiplying the pounds per linear foot with the total length. After each group had a total amount of pounds they were all added together and multiplied by 1.1 to take in account for the connections, this gave the overall weight of the steel in pounds. Tonnage was then found by dividing the weight in pounds by 2000. North High School ended up containing 944.16 tons of structural steel according to the Revit model. Table 2 shows the steel quantity take-off.

Type	Total Length	Lbs/Ft	Lbs
HSS5X5X5/16	2705.777	19.08	51626.22516
W8X10	27.458	10	274.58
W8X18	54.229	18	976.122
W10X12	2878.51	12	34542.12
W10X15	1380.083	15	20701.245
W10X22	555.458	22	12220.076
W12X14	1691.635	14	23682.89
W12X16	42.2	16	675.2
W12X19	200.281	19	3805.339
W12x26	2363.198	26	61443.148
W12X30	74.667	30	2240.01
W12X35	37.333	35	1306.655
W12X40	168	40	6720
W14X22	4335.01	22	95370.22
W14X30	2506.688	30	75200.64
W16X26	15749.27	26	409481.02
W16X31	205.927	31	6383.737
W16X36	325.416	36	11714.976
W18X35	2596.5	35	90877.5
W18X40	368	40	14720
W18X50	218.667	50	10933.35
W18X60	140	60	8400
W18X76	18.25	76	1387
W18X97	69.167	97	6709.199
W21X44	165.167	44	7267.348
W21X48	246.573	48	11835.504
W24X55	2518.083	55	138494.565
W24X62	540.833	62	33531.646
W24X68	82.583	68	5615.644
W24X76	346.667	76	26346.692
W27X84	322	84	27048
W30X99	4749.667	99	470217.033
W30X116	105	116	12180
W33X118	277.333	118	32725.294
*Multiply by 1.1 for connections		Lbs	1716652.978
		Lbs	1888318.276
		Tons	944.159

**Table 2: Steel Takeoff**

The concrete quantities were grouped into rectangular footings, wall foundations, and foundation slabs. The structural foundation schedule that was developed by Revit did not automatically group the concrete items into families, this was completed manually. Overall there was 113,385.03 cubic feet in the Revit model, the total cubic feet converted to cubic yards is 4200 cubic yards. This was found by dividing the cubic feet by 27.

<b>Structural Foundation Schedule</b>			
Family and Type	Quantity	Volume	Unit
Rectangular Footing	128	742	CY
Wall Foundation	9	28	CY
Foundation Slab	7	3430	CY
Subtotal		4200	CY

**Table 3: Concrete Takeoff**

#### **4.6 Steel Estimate**

The estimate of the structural steel for North High School, budgeted for by Gilbane Building Company, was \$2,890,000. The actual award amount was \$2,870,000 to United Steel, Inc. As of 10/28/2009 change orders had raised the total cost of the structural steel to \$3,163,901. The quantity developed by the Revit model found to have 944.159 tons of steel and using RS Means Building Construction Cost Data 2010 the average price for steel by ton for a high school was \$3,216 for bare costs. For the Revit estimate the location factor of Worcester, Ma factored into the cost was 109.5. Using the price given by RS Means costs, the overall Revit model estimate for structural steel came to \$3,324,875. The Revit estimate ended up being 4.84%, or \$160,974, higher than the actual cost Gilbane Building Company was required to pay. These numbers are considering that North High School falls directly in the middle of minimum and maximum sized high schools.

<b>Variable</b>	<b>Price</b>
Average \$ per Ton	\$ 3,216.00
Steel Tonnage	\$ 944.16
Location Factor	110%
Revit Estimate	\$ 3,324,875.00
Gilbane Cost (10/28/09)	\$ 3,163,901.00
Difference	\$ 160,974.00

**Table 4: Steel Estimate**

#### 4.7 Concrete Estimate

The concrete for North High School was grouped into three main families; rectangular footings, wall foundations, and foundation slabs. Using RS Means, prices were found for the cost per cubic yard of the specific concrete. The average price for 4000 PSI concrete with no additives was \$113 per cubic yard according to RS Means. Each of the three groups have different specifications in their mixes and require certain additives, this can be seen by the varying prices. The Revit model found that North High School had a volume of 4200 CY of concrete and breaking the total amount into three groups and assigning different prices to them the overall estimated cost was \$814,740. Table 5 displays the concrete estimate.

<b>Structural Foundation Schedule</b>				
Family and Type	Price Per CY	Volume	Unit	Cost
Rectangular Footing	\$ 277.70	742	CY	\$ 206,053.40
Wall Foundation	\$ 371.80	28	CY	\$ 10,410.40
Foundation Slab	\$ 152.83	3430	CY	\$ 524,206.90
	Location Factor		110%	\$ 74,067.07
		4200	CY	\$ 814,737.77

**Table 5: Concrete Estimate**

## Chapter 5 - Earned Value Analysis

This part of the report performs an earned value analysis that was not conducted on the new Worcester North High School construction project; however, it was performed on a steel tank bottom replacement job by Cianbro Corporation in South Portland, Maine. The main reason for this decision is based on the level of detail available to conduct the analysis. The North High School project is being managed by Gilbane Building Company who does not self-perform the construction work. Therefore, labor utilization reports are not detailed enough whereas in the case of the steel tank replacement project, Cianbro Corp. self-performs the work, and the detailed documentation needed for the analysis was readily available to one of the authors.

### 5.1 Earned Value Analysis

Earned Value Analysis (EVA) is a technique project manager's use on all types of construction projects. This analysis is used to determine more accurately if a given project is on schedule and within budget. (Professional Construction Management, Donald S. Barrie, Boyd C. Paulson) Earned Value analysis uses three fundamental factors:

- **Planned Value:** This consists of the planned work, along with the authorized budget, within the authorized time-frame, which in total forms the project baseline.
- **Earned Value:** This is the real work that has been completed in relation to the Planned Value. A budgeted amount is earned as a task is completed up to the total Planned Value.
- **Actual Costs:** These are the actual costs incurred in the project regardless of the Planned and Earned Value.

The analysis uses the concept of quantity to complete to perform the analysis and to tie all three values together. An estimate is completed at the beginning of the project which was discussed in a previous chapter. In the estimate quantities of work are put together and money is

allocated to the given quantity of work; such as cubic yards of concrete, square footage of brick, tons of steel etc. Throughout the project the management team has to update the quantity of work completed to determine the percent complete. The analysis is performed by looking at the time and money it took to complete the given quantity of work put in place (percent complete) and to forecast the time and money it will take to perform the “quantity to complete.” It’s important to use the correct units of measurement for work completed in each activity as this could lead to major errors in the budget forecast; for example if the budget is estimated in tons of steel; tons of steel needs to be entered in for the quantity completed, not pounds or kilograms.

From this analysis a project manager can tell if the job is over or under budget and behind or ahead of schedule on lump sum projects. Below is a simple example.

**From The Budget:**

Formwork estimated at 300 WH’s for 1200 SF (total quantity) or **.25 WH/SF**

**At a given time “x” the Planned Work was the following:**

**120 WH** to complete **480 SF**. Quantity to complete would equal 720 SF.

**The Actual Work at time “x”:**

**130 WH** to complete **600 SF** (quantity completed, 600 SF to complete; 50% complete)

**Earned WH** = .25 (from budget) X 600 (SF completed) or **150 WH’s**

**Cost Variance:** 150 WH (Earned) – 130WH (Actual) = **20 WH Under Budget**

**Schedule Variance:** 150 WH (Earned)–120 WH (Planned) = **30 WH Ahead of Schedule**

This type of analysis is extremely useful for large general contracting firms who self-perform all or most of their work. This analysis is useful in developing project projections for the end of the job. This analysis can be used for every portion of the job, from pouring concrete to

the amount of consumables used to overhead on the job. Not only does this analysis help out the current project but can also help estimate future work that is similar.

For pure construction management firms who do not self-perform any work, the technique is used a bit differently; as they are not so much concerned about budgetary numbers from activity to activity, as they usually contract out packages of work on a lump sum basis, as much so as the schedule. From looking at what a sub-contractor has completed versus what work he has left, the project manager can determine what the production rate of a certain activity is and from that project how much longer it will take the contractor to complete the work. This gives the project manager a leg up on any negotiations with the sub-contractor to bring more people on site if they are falling behind on their work.

The project manager is also concerned about how much more or less he is paying the sub-contractor to what it should be paying. At the beginning of the job, when a sub-contractor is brought in, they will usually give the CM what is called a schedule of values. This schedule of values allocates values for the various parts of the work. Mobilization, excavation, backfill and demobilization are typical activities you may find on an earthwork sub-contractors schedule of values. The sub-contractor will associate a cost to each of those different activities and use this as the basis for submitting and reviewing progress payments. It is up to the project management team to confirm the percent complete on the schedule of values by verifying in the field what has been done. This usually does not need to be an exact science but the project manager needs to make sure that the sub-contractor isn't asking for money for work that hasn't been completed at the time of payment.



## 5.2 Project Background

For the EVA analysis of this report, we looked at steel tank bottom replacement job being performed in South Portland, Maine. The project consisted of replacing the steel bottoms of two 150' diameter oil tanks and installing a foundation and a leak detection system. For this to be performed the old floor (bottom?) had to be cut away from the tank shell and the entire shell had to be jacked up 3' in the air with the use of twenty-four 70 ton air bags. Pictures can be found in Appendix H. This allowed for the excavation to take place for the concrete ring-wall. Inside the tank shell a center sump and leak detection piping was installed to detect if any leaks occurred. On top of the old steel floor an 80mm liner was installed to act as a diaper if a leak were to occur. On top of the liner, rings of cathodic protection were laid to prevent rusting of the new floor. One foot of sand was then installed over the liner and cathodic protection which the new floor was to lay on. The General Contractor (GC) self performed the jacking of the tanks, with the consulting of a professional tank-jacking sub-contractor, the leak detection piping and the concrete work. The GC crews were also needed to assist the sub-contractors on-site. The earthwork, liner, cathodic protection and steel floor work has all been sub-contracted out to various contractors. A "picture slideshow" of the project can be found in the Appendix H.

## 5.3 Project Plan

Although a smaller project, this type of self-performed lump sum work creates a lot more overlooking with the actual work of the job then than a pure CM job. Not only does the project manager have to manage the self performed work but also the work of the sub-contractors. Responsibilities such as deciding how many workers the job needs from month to month, what sort of hours they are going to work, the buyout of materials and management of equipment on-site make the job more a little more involved. These items need to be combed over with a

magnifying-glass weekly because any sort of mistake comes directly out of the contractor's pocket. While overseeing the work, the project manager has to make tough decisions regarding budget and schedule. For example, if an activity is falling behind schedule, is it worth to work the overtime and pay the extra money to get back on schedule?, or does he believe they'll be able to make it up somewhere else on the schedule and continue to work 40 hour weeks? Items like this arise all the time and have to be managed correctly, while also managing sub-contractors on-site.

To get a better understanding of both types of management we looked at activities that were self performed by the General Contractor which included all the concrete related work of the project. The concrete work included the buyout of all materials required on-site; the concrete itself (5000 psi and 2000 psi), the reinforcing steel and the formwork and all of its accessories. The estimate and schedule of these activities will be discussed in the analysis section.

For the GC's jobs, the project team develops a unit analysis report at the beginning of the job. This report includes what they call phases; these phases include work to be performed, OH costs, equipment costs, burdens, etc. In each phase they break the phase down into sub phases. These sub-phases include regular labor, overtime labor, materials, etc. In each phase there are a total number of units (yards of concrete, square footage of formwork, etc) and a budgeted amount for each sub phase they get from the estimate. Also in each phase are columns for costs to date and projected final costs. When entering the costs to date, the engineer/project manager also has to enter the quantity of work completed. Doing this the report will calculate the production rate and this will be used to determine the projected final costs based on the percentages. This will be elaborated on further on in this section. This report is extremely important to the management team as it tells them whether the job is over or under budget. The

project team however, has to do a good job of updating the quantities in each phase of the report because if not, this could yield false projections in the projected final column.

## 5.4 Means/Methods

The design of the ring-wall was a simple design, it contained a footing and the wall was to be 3' tall by 2' wide around the perimeter of the tank, approximately 472 feet. Where bedrock was encountered above the base of the footing elevation, the ring-wall or footing was to be constructed on the bedrock. The top of the wall contained a 3/4" chamfer that also contained a slope, special screeds had to be constructed to get this finish. The reinforcing steel in the foundation was relatively large rebar, #6 and #9 bars. Number 6 bar weighs 1.5 lbs/ft while number 9 bar weighs 3.5 lbs/ft. A drawing of the wall can be seen in Figure 7. Cianbro does a lot of concrete work but this was the first time doing one of these projects so there was an expected learning curve throughout the project. The good part of this job was that two tanks needed to be modified so whatever worked and didn't work on the first could be changed accordingly for the second tank.




Figure 9: Foundation Detail

Once the tank shell was jacked in the air and the excavation was complete, the Cianbro crews needed to pour the footing. Although the footing could have conformed to the excavated trench, it was decided that it would be more cost effective to have the crew spend a day forming up the footing then paying for much more concrete to fill the trench. The formwork was very rough and made out of plain pieces of plywood. Access around the tank was limited so the use of a pump truck was incorporated. The pour started at 7am, was finished by 10am and 86 yards of 2000psi concrete were used. The concrete crew consisted of a man on the end of the pump hose, 2 men on a vibrator and 2 men backfilling the form so they wouldn't blow out. A picture can be seen in Figure 8 below.



**Figure 10: Concrete Pour**



**Figure 11: Concrete Footer Finish**

Although the pour only lasted 3 hours, it was important for the management team to have planned other activities for the crews to do the rest of the day. If not, the crews would still get paid for 10 hours of work for that day in the pouring concrete phase which could really hurt the budget on a small project like this. In self-performed work, the planning of work from day to day is extremely crucial for a successful project.

Once the footing was cured, the formwork was removed and the formwork for the wall was put into place. To get the layout of the wall, a tape was pulled from the center of the tank to the inside of the wall every 18 feet. Once the marks were around the perimeter of the footing, a previously made cut-out of the radius was laid and the inside of the wall was marked out on the footing. The inside formwork was put up first and this took 2 days. The rebar was next to be installed and this took 3 days. The #9 bars came in 30' lengths and with a weight of 3.5 lb/ft; these pieces were quite heavy and needed four guys to put up and tie. The installation of the rebar took 3 days. Once the rebar was complete the outer formwork was put up and the crews

were ready to pour. For the first tank, 2 concrete pumps and two finishing crews were used. After completing this with no problem it was decided to only use one pump truck and one finishing crew on the second tank, see Figure 11. The first tank took less time out of the day but the second tank was more cost efficient as we used less work hours than the first tank and the job only had to pay for the use of one pump truck instead of two. Photos of the concrete pour can be seen below and more can be found in the Appendix H.



**Figure 12: Tank #2 Concrete Pour**



**Figure 13: Concrete Hose**



**Figure 14: Concrete Finishing**

## 5.5 Project EVA Analysis

Throughout the duration of the project each week the management team will updates its “unit analysis reports” better known as earned value reports. For each week the project manger or engineer will look at the number of hours used for a given activity and update the quantity completed for that week. Based on the quantity completed to that point and the WH’s used it will determine a new unit/hour number and apply that to the quantity to complete to get the estimated number of work hours to complete the job. By doing this every week the project management team can make sounder decisions on the project.

For this study the team looked at the concrete portion of the job in South Portland. Below is a breakdown of budgeted work hours for each tank and the total quantity of units for each activity. The duration of the concrete portion was estimated at 14 days; by the book this means we should have had 7 men on site to complete the work in that time period.

<b>Activity</b>	<b>Budget WH’s</b>	<b>Unit</b>	<b>Quantity</b>
Formwork	612	SF	2850
Rebar	166	Tons	7
Placing	230	Yards	360
Total	1008		

**Table 6: Budget Work Hours**

For the first tank, everything went accordingly to plan with the actual WH's used nearly identical to the budgeted work hours This doesn't tell the whole story though, not only does the management team need to look at the number of hours used but the wages rates as well. At first glance it will look good if your budgeted hours are the same as your actually WH's but if your actual wage rate is \$5.00 more than your budgeted wage rate, your budget will be shot. To keep confidentiality a wage rate of \$25.00 was used for the budgeted actual wage rate and the actually wage rate was used at \$26.25 (Note: the actual wage rates were 1.05% higher than the budgeted wage rates for the actual job and this is how the \$26.25 was determined.) As described above in the means and methods section the concrete portion of the first tank took 10 days. A spreadsheet giving a good synopsis of the first tank completed can be seen below.

<b>Day</b>	<b>Budgeted WH's</b>	<b>Actual WH's</b>	<b>Earned WH's</b>	<b>Actual Cost</b>	<b>Budgeted Cost</b>
<b>1</b>	72	101	101	\$2,662	\$1,800
<b>2</b>	144	203	202	\$5,324	\$3,600
<b>3</b>	216	304	303	\$7,985	\$5,400
<b>4</b>	288	406	404	\$10,647	\$7,200
<b>5</b>	360	507	505	\$13,309	\$9,000
<b>6</b>	432	608	606	\$15,971	\$10,800
<b>7</b>	504	710	707	\$18,632	\$12,600
<b>8</b>	576	811	808	\$21,294	\$14,400
<b>9</b>	648	913	909	\$23,956	\$16,200
<b>10</b>	720	1014	1008	\$26,618	\$18,000
<b>11</b>	792				\$19,800
<b>12</b>	864				\$21,600
<b>13</b>	936				\$23,400
<b>14</b>	1008				\$25,200
	Delta	-6		Delta	<b>(\$1,418)</b>

**Table 7: Tank 24 Actual Cost/Budget Cost**

Analyzing these data shows that the concrete activities were 4 days ahead of schedule, 6 hours over budget that equals out to \$1,418 over budget. On a project this size, 6 hours and



\$1,418 is not a bad loss; time is money and getting ahead of schedule by 4 days is economically more beneficial than \$1,418. A graph displaying these different items can be seen below.




Figure 15: Tank 24 WH Analysis





Figure 16: Tank 24 Cost Analysis

The second tank went a lot smoother than the first as there was a “learning curve” from the first tank; the craftspeople knew what to expect and what problems to look for on the second tank. Not only did the “learning curve” assist the craftspeople but also management team. The management team realized that the amount of work needed to be put in place didn’t require as much labor as estimated so the crew was cut down by 3 workers. Getting ahead of schedule on the first tank also made it easier to make this decision as there was some “float” in the schedule. The second tank took longer than the first tank to complete but saved a lot of WH’s and still finished on schedule. The spreadsheet can be seen below.


<b>Day</b>	<b>Budgeted WH's</b>	<b>Actual WH's</b>	<b>Earned WH's</b>	<b>Actual Cost</b>	<b>Budgeted Cost</b>
<b>1</b>	72	61	78	1531	1800
<b>2</b>	144	122	155	3050	3600
<b>3</b>	216	183	233	4575	5400
<b>4</b>	288	244	310	6100	7200
<b>5</b>	360	305	388	7625	9000
<b>6</b>	432	366	465	9150	10800
<b>7</b>	504	427	543	10675	12600
<b>8</b>	576	488	620	12200	14400
<b>9</b>	648	549	698	13725	16200
<b>10</b>	720	610	775	15250	18000
<b>11</b>	792	671	853	16775	19800
<b>12</b>	864	732	930	18300	21600
<b>13</b>	936	796	1008	19900	23400
<b>14</b>	1008				25200
	Delta	398		Delta	9950

**Table 8: Tank 23 Actual Cost/ Budget Cost**

Breaking this spreadsheet down shows that the concrete work on the second tank was 1 day ahead of schedule and 398 work hours under budget; equivalent to \$9,950. This means the schedule was done in 93% of the time estimated and used only 79% of the budget.



**Figure 17: Tank 23 WH Analysis**



**Figure 18: Tank 23 Cost Analysis**

Looking over the entire concrete portion of the job combining both tanks the activity ended up being 392 WH's ahead of budget, equivalent to \$8,532 and 5 days ahead of schedule. Please note that there is more to the budget that includes cost of materials which also is included

in the budget that was not included in this analysis. This analysis just shows a snapshot of a piece of work on a project. This analysis applies to every aspect of the job. It's important to quantify everything that will be billed to the job and is quantifies with a correct unit of measurement; this goes for equipment, small tools, consumables, fuel, etc. These items are usually designated in the OH area and should be quantified in weeks of the job as these items are usually spread out evenly across the duration of the project.

To understand the "time is money" concept we looked at the OH savings associated with beating the schedule. Analyzing the budget it was found that the OH budget was \$680,000 spread out over 180 days. This equals to \$3,778 per day. (The OH phase includes OH labor, equipment, burdens, small tools, consumables etc.) With the schedule being 5 days ahead of schedule this equals out to a savings of \$18,890. The total savings of this activity is the direct savings and the OH savings combined together which equaled out to \$27,422.

## **Chapter 6 – Design and Constructability Analysis of New Retaining Wall**

This chapter is dedicated to the analysis and design of an alternative retaining wall at the new Worcester North High School. During the design process, there were many different considerations on what type of retaining wall to use to stabilize the area around the 60 foot cliff that is located in around the back side of the construction site. Cullinan Engineering, an engineering firm located in Auburn, Massachusetts, designed the retaining wall that is currently in place at the construction site. The designers chose a semi-gravity retaining wall, which relies mostly on its' own weight to support compression forces, but has some steel reinforcement. The goal of this chapter is to determine the feasibility of choosing a cantilever retaining wall with counterforts instead of a semi-gravity wall and to compare the economic value of each type of retaining wall. The design process and equations were taken from Arthur Nilsen's textbook *Design of Concrete Structures*.

### **6.1 Original Retaining Wall Design-Pre Construction Phase**

The construction of the new high school was to be built alongside the old high school and a steep cliff shown in Figures 19 and 20. During the pre-construction phase of the design, the engineers at Architectural Services chose a design of riprap to protect the school and soil from the cliff, which at its highest point along the school is around 60 feet, shown in Figure 20. There is a need for some type of retaining wall against the cliff because there is a road that travels around the back of the school and along the cliff. To avoid the soil from sliding due to the live loads that travel along the road during construction and post-construction, retaining walls are placed for the safety of the site. Not knowing how close the road was to the cliff, the engineers suggested that major live loads were not to be included in the design and simple riprap would be a sufficient and cost effective solution to holding back the soil at the cliff.



Figure 19: Approximate Area of Construction




Figure 20: Approximate Area of Cliff

Riprap is a layer made of stones, as seen in the figure below, which is intended to protect the soil from erosion due to runoff from rain. Some limitations of riprap include that it is limited by steepness of slope that are greater than 2:1 because it has the potential of loss due to sliding. Riprap is extremely cost effective, with prices ranging anywhere from 35\$ to 60\$ per cubic yard. Again, the pre-construction thought of engineers was that the road behind the school was far enough away from the cliff to prohibit any more complicated designs than riprap.




**Figure 21: Riprap**

## **6.2 Retaining Wall Changes- During Construction**

During the site work and excavation for the new Worcester North High School, it was clearly evident that the riprap first designed would not be able to hold the construction loads that would be applied to the area during construction. Figure 22 shows that the corner of the building is only 21 feet from the cliff and that riprap would no longer be a valid solution to the 60 foot

drop-off. This would have been extremely dangerous for construction vehicle traveling around this corner.




**Figure 22: Plan View of New Retaining Wall**



**Figure 23: New Semi-Gravity Retaining Wall**




Since the new design for retention was to be more complicated than ordinary riprap, Cullinan Engineering was hired to design the new wall. There are many different options Cullinan could have chosen for the design of the wall. The three most common types used is a standard gravity retaining wall, and semi-gravity retaining wall, and a cantilever retaining wall. These options are displayed in Figure 24. Gravity walls are constructed with plain concrete or stone masonry and they depend on their own weight and soil resistance for stability. Typically this type of construction is not economically conducive to high wall design. In some cases, a small amount of steel is used for the construction of a gravity wall, thus making it a semi-gravity wall. Placing steel in the gravity wall will significantly reduce the size of the wall section because it strengthens the concrete in tension, thus saving money. A cantilever wall is made out of reinforced concrete that has a thin stem and base slab.



**Figure 24: Cross Sections of Different Retaining Walls**

Cullinan Engineering chose a semi-gravity wall for this design as seen in Figure 25. The wall is not the same height around the corner of the road, because the cliff is not the same height. The Cliff drops off drastically the further north it is. This means that the retaining wall does not have to be the same height, but in intervals of height instead. At its highest point, the wall is 14.5 feet and that is where the cliff is at its greatest length of around 60 to 65 feet. Moving northward along the road, the wall significantly drops to lengths of 10 feet and eventually 7 feet.



**Figure 25: Cullinan's Retaining Wall Design**

### 6.3 New Cantilever Retaining Wall Design with Counterforts

The proposed alternative solution for the retaining wall design is driven by several factors; ground water and soil conditions, cost and required wall height. The first step in designing the retaining was to obtain information on the earth's lateral pressure in the area. The basic soil parameters include:

- Soil unit weight
- Angle of internal friction (for sands)
- Cohesion and plasticity indices (for clays)
- The water table location.
- Ledge location

From here we were able to size the wall and check for stability; this will include checks for wall overturning, base sliding, and soil bearing capacity failures. After the wall is sized, each wall member was checked for adequate strength and steel reinforcing was determined.

A cantilever retaining wall with counterforts was the type of wall that was chosen for this design. A counterfort retaining wall is very similar to a cantilever wall, except that it has one additional feature. This wall has a triangular shaped cross section spaced at typically one foot which connects the top of the wall to the back of the footer. This added support wall is hidden within the earthen or gravel backfill of the wall. The footer, retaining wall and support wall must be tied to one another with reinforcing steel. The support walls add a great deal of strength to the retaining wall. The supports make it virtually impossible for the wall to become detached from the footer. Counterforts are usually used for high walls with heights greater than 24 to 26 feet. In

this case, the wall is only 10 feet high, but this type of design is also used for situations where high lateral pressures occur; where the backfill is heavily surcharged, in this case like North High where the area in close proximity to the wall will be used as a fire lane.




Figure 26: Typical Counterfort Wall

## 6.4 Preliminary Design

The first step in our design was to size the members, since we already had drawings of the current retaining wall it was relatively easy to realize what the height would need to be. We used the height of the current retaining wall to gather all of our dimensions, such as footing size, wall thickness and support sizes. These dimensions were based on a function of the retaining wall height from equations found in the foundation engineering handbook. Since the highest point of the current retaining wall at North High School is 14.5 feet, we estimated our height to

be a little lower than that at 10 feet. Once we had all of the dimensions of the wall we started the preliminary design on the wall.




Figure 27: Preliminary Design of Retaining Wall (Cross section, in inches)

### 6.4.1 General Pressures on the Wall

Implementing various equations found in *The Design of Concrete Structures* by Arthur Nilson, we started the calculation process. The first step in calculating the general pressures on the retaining wall is determining the dead loads and live loads using the equations:

$$U=1.4D+1.7L$$


Typically the equation above uses factored numbers to increase the safety of the design. Since there are no dead loads acting on the top of the wall, we only used the live loads for calculating the surcharge acting on the wall. The road running along the wall is intended for a fire lane which typically carries live loads of 225 psf (pounds per square foot, found in *The Design of*

Concrete Structures) to 250 psf. Using the above equation, we found the total surcharge of 425 psf.

After calculating surcharge, the next step was to determine the equivalent height of the surcharge,  $h'$ . The equivalent height of the surcharge acts as an increased height in the soil pressure on the back of the wall as seen in figure 28. The following equation was used for calculating the equivalent surcharge height:

$$h' = \text{Total Surcharge} / \text{Unit Weight of Soil}$$

The soil report indicated the underlying soil at the construction site as glacial till, we categorized the soil from soil reports as silty sand, sand and gravel with high clay content. Properties of this soil include 120 to 130 pounds per cubic foot for the unit weight, and 0.3 to 0.4 for the coefficient of friction. Inserting the appropriate values into the equation, we calculated a equivalent surcharge height of 3.27 feet for the new retaining wall.



**Figure 28: Pressure on the Wall Due to the Surcharge**

## 6.4.2 Further Investigation and Shear Calculations

Using the values calculated above, the earth pressure acting horizontally on the wall was then calculated using the following equation:

$$P = .5 * (C_{ah} * w * h * (h + 2h'))$$

$C_{ah}$  = soil coefficient

$w$  = unit weight of soil

$h$  = effective height

$h'$  = effective surcharge height

From there, the moment arm and total moment was calculated and finally the thickness of the arm. We calculated the arm thickness dimensions and shear values for both a 10 foot and a 12 foot wall. For the 10 foot wall we calculated an arm thickness of 10 inches and a shear value away from the base of 4,310 lbs, which is much lower than the factored shear value of the wall at 12,902 lbs. The 12 foot wall was much of the same. We calculated that an arm thickness of 10 inches would also be acceptable and that the shear force from the soil was 5594 lbs which is also lower than the factored shear value. Comparing each option, it was found more economical to choose the 10 foot wall over the 12 foot wall at that certain point in the design. Once the preliminary design was completed, the stability and reinforcement steel was determined.

## 6.5 Stability Investigation

With the wall now having dimensions for the height and arm thickness, it was time to investigate the external stability of the structure. According to Nilsen, a wall may fail in two different ways: (1) its individual parts may not be strong enough to resist the acting forces on it, and (2) the wall as a whole may be bodily displaced by the earth pressure, without breaking up

internally. Using the weights of the soil and retaining, a component weight table was formed with not only the component weight but resulting moment from each part as well. We split up the retaining wall and soil into 6 different sub-weights as seen below and in figure form in Appendix D.

	<b>Weight (lbs)</b>	<b>Moment Arm (ft)</b>	<b>Moment (ft-lbs)</b>
<b>W1</b>	1125	1.92	2160
<b>W2</b>	1175	3.92	4606
<b>W3</b>	104	1.92	199.68
<b>W4</b>	5940	5.083	30,193
<b>W5</b>	360	0.75	270
<b>W6</b>	3714	4.16	15,466
<b>Totals</b>	<b>12,417</b>		<b>52894.68</b>

**Table 9: Component Weights of Retaining Wall**

Using the calculated values of this table, the factor of safety against overturning was determined with the weights, moments and the bearing pressures. We found that the factor of safety against overturning was 3.99 which is adequate according to the theories of Nilsen's book, a value of 3 is an appropriate value for this. Following this procedure, we determined the total resistance due to sliding to be 4809 lbs using values calculated from the friction at the toe, heel, key and passive earth pressure. Dividing 4809 lbs by the total soil pressure of 3305 lbs, we found that the Factor of Safety against overturning was 1.45 which is also adequate.

## **6.6 Steel Reinforcement**

After completing the preliminary design and the stability checks throughout the retaining wall, the steel reinforcement could then be designed again using moments and equations from Nilsen. The bending moment in the arm decreases rapidly with increasing distance from the bottom. The first part of the retaining wall we design steel for was the arm and key. The moment at the bottom section of the arm was already determined in previous calculations and from there, we could use the following equation to receive a proportion of moment, height, and width:



$$M_u/\Phi*b*d^2$$

With this value, which was calculated to be 340.6, we turned to graph A.1b in Nilsen's book.

Graph A. 1b in Nilsen's book shows the relationship with the ratio above and the required steel ratio,  $\rho$ , for any given strength of steel. The graphs and tables are shown in Appendix D. Lastly, the area of steel was calculated with the following equation:

$$A_s = \rho*b*d$$

Having the same approach with the toe and heel slabs, steel reinforcement was successfully designed for the retaining wall.


One problem that was encountered during the design of the heel slab was that the shear force from the soil on the heel was greater than the factored shear force of the heel by about 900 lbs. In order to raise the factored shear of the heel slab, we had to increase the overall thickness of the slab to 13 inches instead of the original 12 inches. Increasing the height increased the factored shear by around 1,300 lbs, which in turn made the heel slab adequate against shear forces. The table below shows the calculated values for the steel reinforcement.

<b>Part of Retaining Wall</b>	<b>Vertical Bars</b>	<b>Horizontal Bars</b>
Arm and Key	#4 Bars @ 24" O.C. Outside Face	#4 Bars @ 20" O.C. Outside Face
	#7 Bars @ 24" O.C. Inside Face	#4 Bars @ 16" O.C. Inside Face
	#7 Bars @ 12" O.C. Starting 4.5' from top Inside Face	
Heel	#6 Bars @ 9" O.C.	#10 Bars @ 8" O.C.
Toe	#6 Bars 12" O.C.	#3 Bars @ 12" O.C

**Table 10: Vertical and Horizontal Bars**

## 6.7 Design of Counterforts

Counterforts are useful for cantilever retaining walls because they tie the slab and base together thus reducing shear moments and bending moments that are acting on the wall. Since the current retaining wall at the construction is around 84 feet long, we designed the cantilever wall with counterforts for only 42 feet which is half of the total length of the wall. We chose to design only half because the cliff height drops off from significantly from 60 to 65 feet to only around 30 feet towards the North. Since the cliff height is so low, a smaller wall could be designed to make the wall more economical. Figure 29 shows a plan view of our newly designed retaining wall with counterforts.



**Figure 29: Plan View of Counterfort Wall**

After determining the length of the wall and dimensions in between counterforts from previous projects and theories, which was 9.5 feet, we designed the horizontal and vertical reinforcement bars using the following equations:

$$M_u = P \cdot l^2 / 10$$

$$A_h = M_u / \Phi f_y \cdot (j d)$$

$$A_v = V_u / \Phi f_y d$$

Inserting values into the equations above, it was found that the horizontal reinforcement bars would have to be much larger than the vertical reinforcement bars. The placement and types of bars are seen in the table below.

<b>Horizontal Reinforcement</b>
#8 Bars @ 12" O.C. from 2' above top of heel to top wall
#9 Bars @ 12" O.C. from 2' above top of heel to top of heel
<b>Vertical Reinforcement</b>
#3 Bars @ 24" O.C. to 9' below top of wall
#3 Bars @ 30" O.C. from 9' below top of wall to bottom of heel

**Table 11: Horizontal and Vertical Reinforcement**

Cross sections of the cantilever wall and counterforts are shown on pages 131 and 135 respectively in the appendices.

## 6.8 Analysis of Retaining Wall Cross Sections

Now that all of the dimensions of the retaining wall were designed, it was necessary to analyze and compare the cross sections of the retaining wall designed by Cullinan Engineering and the wall designed above. By dividing each wall into sections to calculate the area and then multiplying the area by total length to get volume, we could compare the total volume of each wall to analyze cost. The table below details the cross sectional areas and volumes of each wall.

	<b>Cross Sectional Area</b>	<b>Total Length</b>	<b>Volume</b>
<b>Semi-Gravity Retaining Wall</b>	45.827 sq. ft	42 ft	<b>71.30 cubic yds</b>
<b>Cantilever Retaining Wall</b>	16.560 sq. ft	38.67 ft	640 cubic ft
<b>Counterforts</b>	41.03 sq. ft	3.34 ft	137 cubic ft
<b>Cantilever Retaining Wall With Counterforts</b>			<b>28.77 cubic yds</b>

**Table 12: Volume of Cross Sectional Area**

Comparing the total volume of each 42 foot wall, we found that the total volumes of the semi-gravity wall designed by Cullinan Engineering was almost 3 times more than the 42 foot

cantilever wall with counterforts. Although cantilever walls use much more steel than semi-gravity walls, the cost of steel would not come close to the amount of money saved with the reduction of concrete. Using a price of roughly \$200 per cubic yard, the choice of a cantilever retaining wall with counterforts would save almost \$10,000 for a 42 foot wall. By completing this analysis, we realized that there are so many different options in design and whichever option is chosen can severely impact the economic value of the project. All calculations and diagrams can be found in Appendix D.

## Chapter 7 - Results and Conclusions

### 7.1 North High Estimate

The North High School estimate developed by tracking quantities using BIM an accurate accumulation of information compared to the actual costs Gilbane Building Company was charged for. The Revit model, which was created by using the Architect's drawings that were obtained from Gilbane Building Company, calculated that 944.16 tons of steel were used in the structural framing of North High School. Using the information that was provided by R.S. Means Construction Cost Data on the current cost per ton of steel for a High School, an estimated cost for the steel was found to be \$3,324,875. As of October 28, 2009, Gilbane Building Company had already committed \$3,163,901 to United Steel Incorporated.

<b>Variable</b>	<b>Price</b>
Average \$ per Ton	\$ 3,216.00
Tonnage	\$ 944.16
Location Factor	110%
Revit Estimate	\$ 3,324,875.00
Gilbane Cost (10/28/09)	\$ 3,163,901.00
Difference	\$ 160,974.00

**Table 13: Cost of Steel Difference**

The concrete that was quantified by the Revit model came to be 4200 cubic yards that would be used in the foundation walls, rectangular footings and foundation slabs. Using R.S. Means Construction Cost Data, the price for the 4200 cubic yards of concrete came to be \$814,738. The cubic yards of concrete were broken into three groups when the estimated price was created. The groups footings, wall foundations, and slabs; each had varying prices.

<b>Structural Foundation Schedule</b>				
Family and Type	Price Per CY	Volume	Unit	Cost
Rectangular Footing	\$ 277.70	742	CY	\$ 206,053.40
Wall Foundation	\$ 371.80	28	CY	\$ 10,410.40
Foundation Slab	\$ 152.83	3430	CY	\$ 524,206.90
	Location Factor		110%	\$ 74,067.07
		4200	CY	\$ 814,737.77

**Table 14: Concrete Estimate per CY**

## **7.2 Earned Value Analysis**

The example of the steel tank replacement job in South Portland, Maine shows how critical it is to track work on a construction project, especially general contracted work. With the use of earned value analysis the management team can make important decisions during the duration of the job that will hopefully positively impact the budget and schedule. The job we analyzed shows how making decisions based on how the job is progressing can save quite a bit of money for the company, in this case, \$27,000 on just the concrete portion of the job. It's important to note that without the use of the earned value analysis these decisions wouldn't be able to be made, or at least made correctly.

## **7.3 Retaining Wall**

The capstone design project completed in this report investigated an alternative design of a retaining wall located near the corner of Building B and the auditorium of the new Worcester North High School. For the investigation, we discussed some of the advantages and disadvantages of each type of retaining wall considered, determined the soil properties and earth

pressures, performed a structural analysis of the wall, and addressed some economic aspects of each design.

The main reason for a retaining structure in this location is to protect the underlying houses from any sliding of soil due to live loads or precipitation. During the pre-construction design phase of the project, engineers did not know the proximity of the edge of the cliff to the corner of the building and the surrounding road. The engineers assumed the retaining structure would be far enough away from the road and the corner of the building that simple riprap would suffice the design. However, during construction it was seen that the road would be constructed only a few a feet from the retaining structure. Since riprap cannot hold the live loads traveling on the road, a sub-contractor was hired to redesign a retaining wall. As construction continued, it was of high priority of the engineers at Cullinan Engineering to design a retaining wall fast. The change order log that the new retaining wall would cost the project around \$250,000.

Having the economic aspect on high priority, we tried to not only design a retaining wall to withstand the appropriate loads, but to also try and decrease the overall cost of this part of the project. In order to try and save cost on concrete, we decided to design a cantilever wall with counterforts spaced 9.5 feet apart. The dimensions of our retaining wall include an arm that is 10 inches thick and 10 feet long, a toe that is 13 inches thick and 1.5 feet long, a key that is 10 inches thick and 10 inches long, and a heel that is 1.5 feet thick and 5.5 feet long. Also, we designed counterforts that would be 8 inches thick. Since cantilever walls require the use of steel reinforcement because of the wall's slenderness, we designed that aspect of the wall as well. The following tables include our design of steel reinforcement.

<b>Part of Retaining Wall</b>	<b>Vertical Bars</b>	<b>Horizontal Bars</b>
Arm and Key	#4 Bars @ 24" O.C. Outside Face	#4 Bars @ 20" O.C. Outside Face
	#7 Bars @ 24" O.C. Inside Face	#4 Bars @ 16" O.C. Inside Face
	#7 Bars @ 12" O.C. Starting 4.5' from top Inside Face	
Heel	#6 Bars @ 9" O.C.	#10 Bars @ 8" O.C.
Toe	#6 Bars 12" O.C.	#3 Bars @ 12" O.C

**Table 15: Steel Reinforcement**

<b>Horizontal Reinforcement</b>
#8 Bars @ 12" O.C. from 2' above top of heel to top wall
#9 Bars @ 12" O.C. from 2' above top of heel to top of heel
<b>Vertical Reinforcement</b>
#3 Bars @ 24" O.C. to 9' below top of wall
#3 Bars @ 30" O.C. from 9' below top of wall to bottom of heel

**Table 16: Counterfort Steel Reinforcement**

Since the cliff at the new Worcester North High School is not the same height, we could have designed the wall with smaller heights as the steepness of the cliff lowered. However, this was not feasible. In order to compare our design to Cullinan's design, we used an over length of 42 feet for the wall, using our maximum height and their maximum height over that entire span. It was found that the cantilever wall would save 30 square feet in cross sectional area and a



volume of around 42 cubic yards for the 42 feet of length as compared to the semi-gravity wall.

Although the cantilever wall would have much more reinforcing steel than the semi-gravity wall, it would be insignificant compared to the cost saved due to the decrease in the amount of concrete.

#### **7.4 Gilbane/Owner Architect Meetings**

Throughout the 6 months working on this project, we also attended weekly meetings to gain a perspective on how the construction management process really works. The firms that attended this meeting were Gilbane, the construction manager at risk, The Maguire Group, the owner's consultant, and Worcester Architectural Services, the owner architect. The main focus of these meetings was not only about the design of the building, but scheduling, request for information, and change orders. After attending these meetings, we found that the construction management process of North High was filled with headaches and conflicts.

Often times during the meeting, it seemed like Worcester Architectural Services was always behind schedule compared to Gilbane and The Maguire Group. At one of the meetings, it was stated that Worcester Architectural Services had 42 outstanding RFI's that were to be answered, which is generally high compared to a normal project. Throughout the project, The Maguire Group was usually the mediator between Gilbane and Worcester Architectural Services.


One example of a conflict throughout the 5 months we attended meetings was with Guaranteed Maximum Price or GMP. Generally the GMP cannot be decided until most of the building is designed in order for the construction manager to receive a fair price. Since Worcester Architectural Services was behind schedule on the design, the GMP contract deadline date was pushed back from mid November 2009 to mid March 2010.


Also, throughout the project there were many issues between Gilbane and Worcester Architectural Services that had to do with the drawings and plans being issued. One major issue with the plans that happened was with the some of the toilet designs in buildings A and B. Worcester Architectural Services had designed the piping of the toilets to come through the floor instead of the wall in the bathroom. After giving the incorrect plans to Gilbane, Gilbane awarded the job to a subcontractor, who then received the incorrect plans. These issues were two of many that we observed occurred throughout the project.

## Works Cited

- Coduto, Donald P. Foundation Design Principles and Practices. Prentice Hall Inc., 2001.*
- Eastman, Chuck. BIM Handbook: A Guide to BIM Modeling. John Wiley and Sons, 2008.*
- Hinton, Melissa. Personal interview. 7 September 2009.*
- Nilsen, Arthur H. Design of Reinforced Concrete Structure. McGraw Hill, 1991.*
- Oberlander, Garold D. Project Management for Engineering and Construction. McGraw Hill Company, 2000.*
- RS Means, (2010). Building Construction Cost Data. RS Means*
- Salmon, Charles G. Reinforced Concrete Design. John Wiley and Sons, 2007.*
- [http://www.thefreelibrary.com/First+step+for+new+North+High%3B+Long-stalled+\\$72M+school+breaks+ground.-a0168421746](http://www.thefreelibrary.com/First+step+for+new+North+High%3B+Long-stalled+$72M+school+breaks+ground.-a0168421746)*
- <http://enr.construction.com/toplists/Contractors/001-100.asp>*
- <http://www.stormwaterauthority.org/assets/Riprap.pdf>*
- <http://www.bea.gov/>*

# Appendix A: Project Schedule as of March, 2009















Activity ID	Activity Description	Rem Dur	Early Start	Early Finish	2009												2010												2011											
					F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J							
08C-512C	Prep/Sub SD+Smpis -08C-Frames/Doors/HrdwrBldg C	10	18JUN09	01JUL09	█ Prep/Sub SD+Smpis -08C-Frames/Doors/HrdwrBldg C																																			
08C-512B1	Rev/App SD's+Smpis -08C-Frames/Doors/HrdwrBldg B	10	18JUN09	01JUL09	█ Rev/App SD's+Smpis -08C-Frames/Doors/HrdwrBldg B																																			
15-514	Rev/App SD- Fire Protection	10	19JUN09	02JUL09	█ Rev/App SD- Fire Protection																																			
05B-516A	Fab/Del Materials+Equip 05B-Misc Metals Bldg A	10	26JUN09	10JUL09	█ Fab/Del Materials+Equip 05B-Misc Metals Bldg A																																			
08C-512C1	Rev/App SD's+Smpis -08C-Frames/Doors/HrdwrBldg C	10	02JUL09	16JUL09	█ Rev/App SD's+Smpis -08C-Frames/Doors/HrdwrBldg C																																			
08C-516B	Fab/Del Materials+Equip Bldg B	10	02JUL09	16JUL09	█ Fab/Del Materials+Equip Bldg B																																			
15-524	Rev/App Fire Protection	10	06JUL09	17JUL09	█ Rev/App Fire Protection																																			
15C-520	Fab/Del HVAC	40	06JUL09	28AUG09	█ Fab/Del HVAC																																			
15C-526	Fab/Del HVAC	60	06JUL09	28SEP09	█ Fab/Del HVAC																																			
08C-516C	Fab/Del Materials+Equip Bldg C	10	17JUL09	30JUL09	█ Fab/Del Materials+Equip Bldg C																																			
08D-506	Rec. Award-08D-Special Doors	3	03AUG09	05AUG09	█ Rec. Award-08D-Special Doors																																			
09B-506	Rec. Award-	3	03AUG09	05AUG09	█ Rec. Award-																																			
09C-506	Rec. Award-Pkg 09A ACT Ceilings	3	03AUG09	05AUG09	█ Rec. Award-Pkg 09A ACT Ceilings																																			
09D-506	Rec. Award-	3	03AUG09	05AUG09	█ Rec. Award-																																			
09E-506	Rec. Award-	3	03AUG09	05AUG09	█ Rec. Award-																																			
09G-506	Rec. Award-	3	03AUG09	05AUG09	█ Rec. Award-																																			
10A-506	Rec. Award-	3	03AUG09	05AUG09	█ Rec. Award-																																			
10B-506	Rec. Award-	3	03AUG09	05AUG09	█ Rec. Award-																																			
12A-506	Rec. Award-Pkg 12A Theater Seating	3	03AUG09	05AUG09	█ Rec. Award-Pkg 12A Theater Seating																																			
09H-506	Rec. Award-	3	03AUG09	05AUG09	█ Rec. Award-																																			
06A-506	Rec. Award-06A-Millwork	3	03AUG09	05AUG09	█ Rec. Award-06A-Millwork																																			
09F-506	Rec. Award-Pkg 09F Wood Athletic Flooring	3	03AUG09	05AUG09	█ Rec. Award-Pkg 09F Wood Athletic Flooring																																			
08B-516A	Fab/Del Materials-Pkg 08B-Glass+Glazing-Bldg A	10	03AUG09	14AUG09	█ Fab/Del Materials-Pkg 08B-Glass+Glazing-Bldg A																																			
02B-504	Rec. Award-Pkg 02B Landscaping	10	03AUG09	14AUG09	█ Rec. Award-Pkg 02B Landscaping																																			
08D-508	Rev/App Award-08D-Special Doors	3	06AUG09	10AUG09	█ Rev/App Award-08D-Special Doors																																			
09B-508	Rev/App Award-	3	06AUG09	10AUG09	█ Rev/App Award-																																			
09C-508	Rev/App Award-Pkg 09A ACT Ceilings	3	06AUG09	10AUG09	█ Rev/App Award-Pkg 09A ACT Ceilings																																			
09D-508	Rev/App Award-	3	06AUG09	10AUG09	█ Rev/App Award-																																			
09E-508	Rev/App Award-	3	06AUG09	10AUG09	█ Rev/App Award-																																			
09G-508	Rev/App Award-	3	06AUG09	10AUG09	█ Rev/App Award-																																			
10A-508	Rev/App Award-	3	06AUG09	10AUG09	█ Rev/App Award-																																			
10B-508	Rev/App Award-	3	06AUG09	10AUG09	█ Rev/App Award-																																			
12A-508	Rev/App Award-Pkg 12A Theater Seating	3	06AUG09	10AUG09	█ Rev/App Award-Pkg 12A Theater Seating																																			
09H-508	Rev/App Award-	3	06AUG09	10AUG09	█ Rev/App Award-																																			
06A-508	Rev/App Award-06A-Millwork	3	06AUG09	10AUG09	█ Rev/App Award-06A-Millwork																																			
09F-508	Rev/App Award-Pkg 09F Wood Athletic Flooring	3	06AUG09	10AUG09	█ Rev/App Award-Pkg 09F Wood Athletic Flooring																																			
08D-510	Award Contract-08D-Special Doors	3	11AUG09	13AUG09	█ Award Contract-08D-Special Doors																																			
09B-510	Award Contract-	3	11AUG09	13AUG09	█ Award Contract-																																			

Start Date	25A/PROJ
Finish Date	11MAY11
Date Date	15MAR09
Run Date	12MAR09 12:19



WN07  
**GILBANE BUILDING COMPANY**  
**WORCESTER NORTH HIGH SCHOOL (WN07)**  
**REMAINING BY BUILDING/PHASE/LEVEL**



DRAFT			
Date	Revision	Checked	Approved
12MAR09	PRELIMINARY FOR REV		



Activity ID	Activity Description	Rem Dur	Early Start	Early Finish	2009												2010												2011											
					F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	
05C-500	Date Required for CD's-Pkg 05C-Metal Panels+Lou	0		02APR09*	◆ Date Required for CD's-Pkg 05C-Metal Panels+Lou																																			
07C-500	Date Required for CD's-Pkg 07C Wtrprf+Sealants	0		02APR09*	◆ Date Required for CD's-Pkg 07C Wtrprf+Sealants																																			
08C-500	Date Required for CD's-Pkg 08C Frames, Doors, Hrdwr	0		02APR09*	◆ Date Required for CD's-Pkg 08C Frames, Doors, Hrdwr																																			
07B-502	Prep Scope-07B - Roofing	0*	03APR09	02APR09	◆ Prep Scope-07B - Roofing																																			
05C-502	Prep Scope-05C Metal Panels + Louvers	5	03APR09	09APR09	■ Prep Scope-05C Metal Panels + Louvers																																			
08A-502	Prep. Scope-Pkg 08A Mt Windows+StoreFronts	8	03APR09	14APR09	■ Prep. Scope-Pkg 08A Mt Windows+StoreFronts																																			
04A-502	Prep Scope-Masonry	8	03APR09	14APR09	■ Prep Scope-Masonry																																			
07C-502	Prep Scope-Waterproofing/Jt Sealants	8	03APR09*	14APR09	■ Prep Scope-Waterproofing/Jt Sealants																																			
08C-503	Prep Scope-08C Frames, Doors+Hardware	9	03APR09	15APR09	■ Prep Scope-08C Frames, Doors+Hardware																																			
16A-500	Date Required for CD's-Pkg 16A-Electrical	0		15APR09*	◆ Date Required for CD's-Pkg 16A-Electrical																																			
09A-500	Date Required for CD's-Pkg 09A Drywall	0		15APR09*	◆ Date Required for CD's-Pkg 09A Drywall																																			
11A-500	Date Required for CD's-Pkg 11A Kitchen Equipment	0		15APR09*	◆ Date Required for CD's-Pkg 11A Kitchen Equipment																																			
15B-500	Date Required for CD's-Pkg 15B-Plumbing	0		15APR09*	◆ Date Required for CD's-Pkg 15B-Plumbing																																			
11B-500	Date Required for CD's-Pkg 11B Lab Equipment	0		15APR09*	◆ Date Required for CD's-Pkg 11B Lab Equipment																																			
15C-500	Date Required for CD's-Pkg 15C-HVAC	0		15APR09*	◆ Date Required for CD's-Pkg 15C-HVAC																																			
15A-500	Date Required for CD's-Pkg 15A-Fire Protection	0		15APR09*	◆ Date Required for CD's-Pkg 15A-Fire Protection																																			
14A-500	Date Required for C-Pkg 14A Elevators (1/15/09)	0		15APR09*	◆ Date Required for C-Pkg 14A Elevators (1/15/09)																																			
05B-500	Date Required for CD's-Pkg 05B-Misc Metals	0		15APR09*	◆ Date Required for CD's-Pkg 05B-Misc Metals																																			
241	A/E Issue 100% CD's	0		15APR09	◆ A/E Issue 100% CD's																																			
15D-501	A/E Issue - Pkg 15D Foundation Drainage	1	16APR09	16APR09	■ A/E Issue - Pkg 15D Foundation Drainage																																			
05B-502	Prep Scope-05B-Misc Metals	5	16APR09	22APR09	■ Prep Scope-05B-Misc Metals																																			
09A-502	Prep Scope - Pkg 09A Drywall	9	16APR09	28APR09	■ Prep Scope - Pkg 09A Drywall																																			
11A-503	Prep Scope-Pkg 11A Kitchen Equipment	9	16APR09	28APR09	■ Prep Scope-Pkg 11A Kitchen Equipment																																			
15A-502	Prep. Scope-Plumbing	9	16APR09	28APR09	■ Prep. Scope-Plumbing																																			
16A-502	Prep. Scope-Electrical	9*	16APR09	28APR09	■ Prep. Scope-Electrical																																			
15C-502	Prep. Scope-HVAC	9*	16APR09	28APR09	■ Prep. Scope-HVAC																																			
14A-503	Prep Scope-Elevators	9	16APR09	28APR09	■ Prep Scope-Elevators																																			
15-502	Prep. Scope-Fire Protection	9	16APR09	28APR09	■ Prep. Scope-Fire Protection																																			
11B-503	Prep Scope-Pkg 11B Lab Equipment	9	16APR09	28APR09	■ Prep Scope-Pkg 11B Lab Equipment																																			
251	Obtain Building Permit	20	16APR09	13MAY09	■ Obtain Building Permit																																			
402	GBC Prepare GMP	15	07MAY09	28MAY09	■ GBC Prepare GMP																																			
08D-500	Date Required for CD's-Pkg 08D-Special Doors	0		15MAY09*	◆ Date Required for CD's-Pkg 08D-Special Doors																																			
09B-500	Date Required for CD's-Pkg 09B Ceramic Tile	0		15MAY09*	◆ Date Required for CD's-Pkg 09B Ceramic Tile																																			
09C-500	Date Required for CD's-Pkg 09C ACT Ceilings	0		15MAY09*	◆ Date Required for CD's-Pkg 09C ACT Ceilings																																			
09D-500	Date Required for CD's-Pkg 09D Carpeting	0		15MAY09*	◆ Date Required for CD's-Pkg 09D Carpeting																																			
09E-500	Date Required for CD's-Pkg 09E Resilient Floors	0		15MAY09*	◆ Date Required for CD's-Pkg 09E Resilient Floors																																			
09G-500	Date Required for CD's-Pkg 09G Epoxy Floors	0		15MAY09*	◆ Date Required for CD's-Pkg 09G Epoxy Floors																																			
10A-500	Date Required for CD's-Pkg 10A Specialties	0		15MAY09*	◆ Date Required for CD's-Pkg 10A Specialties																																			

Start Date 25APR08  
 Finish Date 11MAY11  
 Date Date 16MAR09  
 Run Date 12MAR09 12:19



WN07  
**GILBANE BUILDING COMPANY**  
**WORCESTER NORTH HIGH SCHOOL (WN07)**  
**REMAINING BY BUILDING/PHASE/LEVEL**



DRAFT			
Date	Revision	Checked	Approved
12MAR09	PRELIMINARY FOR REV		



Activity ID	Activity Description	Rem Dur	Early Start	Early Finish	2009												2010												2011											
					F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J							
<b>GENERAL</b>																																								
11A-504	Bld Period -Pkg11A Kitchen Equipment	16	29APR09	20MAY09	■ Bld Period -Pkg11A Kitchen Equipment																																			
11B-504	Bld Period -Pkg 11B Lab Equipment	16	29APR09*	20MAY09	■ Bld Period -Pkg 11B Lab Equipment																																			
11A-506	Rec. Award-Pkg11A Kitchen Equipment	3	21MAY09	26MAY09	■ Rec. Award-Pkg11A Kitchen Equipment																																			
11B-506	Rec. Award-Pkg 11B Lab Equipment	3	21MAY09	26MAY09	■ Rec. Award-Pkg 11B Lab Equipment																																			
11A-508	Rev/App Award-Pkg11A Kitchen Equipment	3	27MAY09	29MAY09	■ Rev/App Award-Pkg11A Kitchen Equipment																																			
11B-508	Rev/App Award-Pkg 11B Lab Equipment	3	27MAY09	29MAY09	■ Rev/App Award-Pkg 11B Lab Equipment																																			
11A-510	Award Contract-Pkg11A Kitchen Equipment	3	01JUN09	03JUN09	■ Award Contract-Pkg11A Kitchen Equipment																																			
11B-510	Award Contract-Pkg 11B Lab Equipment	3	01JUN09	03JUN09	■ Award Contract-Pkg 11B Lab Equipment																																			
08B-504	Bld Period -Pkg 08B-Glass+Glazing	15	01JUN09*	19JUN09	■ Bld Period -Pkg 08B-Glass+Glazing																																			
11A-512A	Prep/Sub SD+Data-Pkg11A Kitchen Eq Bldg A	10	04JUN09	17JUN09	■ Prep/Sub SD+Data-Pkg11A Kitchen Eq Bldg A																																			
11B-512A	Prep/Sub SD+Data-Pkg 11B Lab Equip.-Bldg A	10	04JUN09	17JUN09	■ Prep/Sub SD+Data-Pkg 11B Lab Equip.-Bldg A																																			
08B-506	Rec. Award-Pkg 08B-Glass+Glazing	3	22JUN09	24JUN09	■ Rec. Award-Pkg 08B-Glass+Glazing																																			
08B-508	Rev/App Award-Pkg 08B-Glass+Glazing	3	25JUN09	29JUN09	■ Rev/App Award-Pkg 08B-Glass+Glazing																																			
08B-510	Award Contract-Pkg 08B-Glass+Glazing	3	30JUN09	02JUL09	■ Award Contract-Pkg 08B-Glass+Glazing																																			
08B-512A	Prep/Sub SD+Data-Pkg 08B-Glass+Glazing-Bldg A	10	06JUL09	17JUL09	■ Prep/Sub SD+Data-Pkg 08B-Glass+Glazing-Bldg A																																			
11B-516A	Fab/Del Materials+Pkg 11B Lab Equip Bldg A	10	31JUL09	13AUG09	■ Fab/Del Materials+Pkg 11B Lab Equip Bldg A																																			
11B-516B	Fab/Del Materials+Pkg 11B Lab Equip Bldg B	10	14AUG09	27AUG09	■ Fab/Del Materials+Pkg 11B Lab Equip Bldg B																																			
08B-516B	Fab/Del Materials-Pkg 08B-Glass+Glazing-Bldg B	10	17AUG09	28AUG09	■ Fab/Del Materials-Pkg 08B-Glass+Glazing-Bldg B																																			
11B-516C	Fab/Del Materials+Pkg 11B Lab Equip Bldg C	10	28AUG09	11SEP09	■ Fab/Del Materials+Pkg 11B Lab Equip Bldg C																																			
08B-516C	Fab/Del Materials-Pkg 08B-Glass+Glazing-Bldg C	10	31AUG09	14SEP09	■ Fab/Del Materials-Pkg 08B-Glass+Glazing-Bldg C																																			
<b>CONSTRUCTION PHASE</b>																																								
<b>PRECONSTRUCTION + PROCUREMENT</b>																																								
<b>GENERAL</b>																																								
03AF516C	Fab/Delv-Rebar for Flatwork Bldg C	5	18JUN09	24JUN09	■ Fab/Delv-Rebar for Flatwork Bldg C																																			
1564	Rev/App/SD-Mtl Windows+StoreFronts	10	18JUN09	01JUL09	■ Rev/App/SD-Mtl Windows+StoreFronts																																			
1574	Rev/App Calc's Mtl Windows+StoreFronts	10	18JUN09	01JUL09	■ Rev/App Calc's Mtl Windows+StoreFronts																																			
04A-516A	Fab/Del Masonry + Accessories Bldg A	10	18JUN09	01JUL09	■ Fab/Del Masonry + Accessories Bldg A																																			
04A-516C	Fab/Del Masonry + Accessories Bldg C	10	18JUN09	01JUL09	■ Fab/Del Masonry + Accessories Bldg C																																			
04A-516B	Fab/Del Masonry + Accessories Bldg B	10	18JUN09	01JUL09	■ Fab/Del Masonry + Accessories Bldg B																																			
16A-514	Rev/App/SD- Electrical	10	18JUN09	01JUL09	■ Rev/App/SD- Electrical																																			
16A-524	Rev/App Electrical Samples	10	18JUN09	01JUL09	■ Rev/App Electrical Samples																																			
05C-514B	Rev/AppSD's Submittals-05C Metal Panels+LouversB	10	18JUN09	01JUL09	■ Rev/AppSD's Submittals-05C Metal Panels+LouversB																																			
05C-512C	Submit SD's Submittals-05C Metal Panels+LouversC	10	18JUN09	01JUL09	■ Submit SD's Submittals-05C Metal Panels+LouversC																																			
07B-512C	Prep/Submit Shop Drawings+Calcs-Roof Bldg C	10	18JUN09	01JUL09	■ Prep/Submit Shop Drawings+Calcs-Roof Bldg C																																			
07B-514B	Rev/App Shop Drawings+Calcs-Roof Bldg B	10	18JUN09	01JUL09	■ Rev/App Shop Drawings+Calcs-Roof Bldg B																																			

Start Date 25APR09  
 Finish Date 11MAY11  
 Date Date 16MAR09  
 Run Date 12MAR09 12:19



WN07  
**GILBANE BUILDING COMPANY**  
**WORCESTER NORTH HIGH SCHOOL (WN07)**  
**REMAINING BY BUILDING/PHASE/LEVEL**



DRAFT			
Date	Revision	Checked	Approved
12MAR09	PRELIMINARY FOR REV		

















Activity ID	Activity Description	Rem Dur	Early Start	Early Finish	2009												2010												2011											
					F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J							
C-4167B	Install Understab Electrical-Bldg B	8	28MAY09	08JUN09	█ Install Understab Electrical-Bldg B																																			
C-4090B	Install Under Slab Redon Gas Removal System-B	5	03JUN09	09JUN09	█ Install Under Slab Redon Gas Removal System-B																																			
C-4125B	Test/Backfill Utilities Bldg B	2	10JUN09	11JUN09	█ Test/Backfill Utilities Bldg B																																			
C-4105B	Fine Grade For S.O.G. - Bldg B	2	12JUN09	15JUN09	█ Fine Grade For S.O.G. - Bldg B																																			
C-4110B	Prep & Place S.O.G. Bldg B	9	12JUN09	24JUN09	█ Prep & Place S.O.G. Bldg B																																			
C-4001A	Fireproof Exterior Perimeter 1st-2nd Fir Bldg A	3	28SEP09	30SEP09	█ Fireproof Exterior Perimeter 1st-2nd Fir Bldg A																																			
1-5315	R.I.O.H. Sprinkler 1st Fir	10	20OCT09	02NOV09	█ R.I.O.H. Sprinkler 1st Fir																																			
1-9305	R.I.O.H. Ductmains / Branches - 1st Fir	15	20OCT09	09NOV09	█ R.I.O.H. Ductmains / Branches - 1st Fir																																			
1-5325	R.I.O.H. Plumbing 1st Fir	20	20OCT09	16NOV09	█ R.I.O.H. Plumbing 1st Fir																																			
1-9320	R.I.O.H. Mechanical Piping - 1st Fir	15	03NOV09	23NOV09	█ R.I.O.H. Mechanical Piping - 1st Fir																																			
C-4001B	Fireproof Exterior Perimeter 1st-2nd Fir Bldg B	3	10NOV09	12NOV09	█ Fireproof Exterior Perimeter 1st-2nd Fir Bldg B																																			
1-9304	Test Ductmains / Branches - 1st Fir	3	10NOV09	12NOV09	█ Test Ductmains / Branches - 1st Fir																																			
1-9309	Insulate Ductmains / Branches - 1st Fir	5	13NOV09	19NOV09	█ Insulate Ductmains / Branches - 1st Fir																																			
1-9306	Install VAV's / FCU's / CUH - 1st Fir	5	17NOV09	23NOV09	█ Install VAV's / FCU's / CUH - 1st Fir																																			
1-9308	Duct Tie In To VAV's - 1st Fir	3	24NOV09	27NOV09	█ Duct Tie In To VAV's - 1st Fir																																			
1-9321	Flush/Test Signoff Mechanical Piping - 1st Fir	3	24NOV09	27NOV09	█ Flush/Test Signoff Mechanical Piping - 1st Fir																																			
1-9322	Insulate O.H. Mechanical Piping - 1st Fir	5	24NOV09	01DEC09	█ Insulate O.H. Mechanical Piping - 1st Fir																																			
1-9307	Piping Tie In To VAV's - 1st Fir	15	24NOV09	15DEC09	█ Piping Tie In To VAV's - 1st Fir																																			
1-5330	Stud Frame Walls 1st Fir	10	23FEB10	08MAR10	█ Stud Frame Walls 1st Fir																																			
1-5332	Install Door Frames 1st Fir	5	09MAR10	15MAR10	█ Install Door Frames 1st Fir																																			
1-5310	R.I.O.H. Electric, Fire Alarm + AV 1st Fir	10	09MAR10	22MAR10	█ R.I.O.H. Electric, Fire Alarm + AV 1st Fir																																			
1-5335	R.I.Plumb In Walls - 1st Fir	10	09MAR10	22MAR10	█ R.I.Plumb In Walls - 1st Fir																																			
1-5320	R.I.O.H. Controls 1st Fir	10	23MAR10	05APR10	█ R.I.O.H. Controls 1st Fir																																			
1-5340	R.I. Electric In Walls - 1st Fir	10	04MAY10	17MAY10	█ R.I. Electric In Walls - 1st Fir																																			
1-5350	Test & Insulate In Wall MEP -1st Fir	5	18MAY10	24MAY10	█ Test & Insulate In Wall MEP -1st Fir																																			
1-5355	Sheetrock Walls - 1st Fir	10	25MAY10	08JUN10	█ Sheetrock Walls - 1st Fir																																			
1-9415	Firestop Duct Penetrations - 1st Fir	5	09JUN10	15JUN10	█ Firestop Duct Penetrations - 1st Fir																																			
1-5360	Tape Sheetrock Walls - 1st Fir	10	09JUN10	22JUN10	█ Tape Sheetrock Walls - 1st Fir																																			
1-5365	Prime Paint + First Coat Paint - 1st Fir	10	23JUN10	07JUL10	█ Prime Paint + First Coat Paint - 1st Fir																																			
1-5385	Ceiling Grid - 1st Fir	10	12AUG10	25AUG10	█ Ceiling Grid - 1st Fir																																			
1-5395	Splk Heads - 1st Fir	5	26AUG10	01SEP10	█ Splk Heads - 1st Fir																																			
1-5390	Lighting - 1st Fir	10	26AUG10	09SEP10	█ Lighting - 1st Fir																																			
1-5400	Install RGD - 1st Fir	10	07SEP10	20SEP10	█ Install RGD - 1st Fir																																			
1-5402	Ceiling Tile - 1st Fir	9	22OCT10	03NOV10	█ Ceiling Tile - 1st Fir																																			
1-5410A	Complete Millwork - 1st Fir - Bldg A	3	29OCT10	02NOV10	█ Complete Millwork - 1st Fir - Bldg A																																			
1-5405	Install Doors / Hardware - 1st Fir	10	29OCT10	11NOV10	█ Install Doors / Hardware - 1st Fir																																			
1-5410B	Complete Millwork - 1st Fir - Bldg B	1	03NOV10	03NOV10	█ Complete Millwork - 1st Fir - Bldg B																																			
1-5415	Complete Pimg @ Millwork - 1st Fir	10	04NOV10	17NOV10	█ Complete Pimg @ Millwork - 1st Fir																																			

Start Date: 25APR08 Finish Date: 11MAY11 Date Date: 16MAR09 Run Date: 12MAR09 12:19		WV07 <b>GILBANE BUILDING COMPANY</b> <b>WORCESTER NORTH HIGH SCHOOL (WN07)</b> <b>REMAINING BY BUILDING/PHASE/LEVEL</b>	Sheet 18 of 26 	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th colspan="4">DRAFT</th> </tr> <tr> <th>Date</th> <th>Revision</th> <th>Checked</th> <th>Approved</th> </tr> </thead> <tbody> <tr> <td>12MAR09</td> <td>PRELIMINARY FOR REV</td> <td></td> <td></td> </tr> <tr> <td> </td> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>	DRAFT				Date	Revision	Checked	Approved	12MAR09	PRELIMINARY FOR REV										
DRAFT																								
Date	Revision	Checked	Approved																					
12MAR09	PRELIMINARY FOR REV																							

© Primavera Systems, Inc.

















Activity ID	Activity Description	Rem Dur	Early Start	Early Finish	2009												2010												2011											
					F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	
11A-S16A	Fab/Del Materials+Kitchen Equip-Bldg A	80	02JUL09	23OCT09	<div style="display: flex; justify-content: space-between;"> <div style="width: 100%;"> <div style="display: flex; align-items: center;"> <div style="width: 15px; height: 10px; background-color: green; margin-right: 5px;"></div> <span>Fab/Del Materials+Kitchen Equip-Bldg A</span> </div> <div style="display: flex; align-items: center; margin-top: 5px;"> <div style="width: 15px; height: 10px; background-color: green; margin-right: 5px;"></div> <span>Submit SD/Samples-Pkg 08B-Glass+Glazing-Bldg B</span> </div> <div style="display: flex; align-items: center; margin-top: 5px;"> <div style="width: 15px; height: 10px; background-color: green; margin-right: 5px;"></div> <span>Submit SD/Samples-Pkg 08B-Glass+Glazing-Bldg C</span> </div> </div> </div>																																			
08B-S12B	Submit SD/Samples-Pkg 08B-Glass+Glazing-Bldg B	10	20JUL09	31JUL09																																				
08B-S12C	Submit SD/Samples-Pkg 08B-Glass+Glazing-Bldg C	10	03AUG09	14AUG09																																				
11A-S18	Mobilize-Pkg11A Kitchen Equipment	0	09JUN10		<div style="display: flex; align-items: center; justify-content: center;"> <div style="width: 15px; height: 10px; background-color: red; border: 1px solid black; margin-right: 5px;"></div> <span>Mobilize-Pkg11A Kitchen Equipment</span> </div>																																			
11A-S12A1	Rev/App SD's Submittals-Pkg11A Kitchen Eq Bldg A	10	18JUN09	01JUL09	<div style="display: flex; align-items: center;"> <div style="width: 15px; height: 10px; background-color: green; margin-right: 5px;"></div> <span>Rev/App SD's Submittals-Pkg11A Kitchen Eq Bldg A</span> </div>																																			
11B-S14A	Rev/App SDs Submittals-Pkg 11B Lab Equip.-Bldg A	10	18JUN09	01JUL09	<div style="display: flex; align-items: center;"> <div style="width: 15px; height: 10px; background-color: green; margin-right: 5px;"></div> <span>Rev/App SDs Submittals-Pkg 11B Lab Equip.-Bldg A</span> </div>																																			
11B-S14B	Rev/App SDs Submittals-Pkg 11B Lab Equip.-Bldg B	10	02JUL09	16JUL09	<div style="display: flex; align-items: center;"> <div style="width: 15px; height: 10px; background-color: green; margin-right: 5px;"></div> <span>Rev/App SDs Submittals-Pkg 11B Lab Equip.-Bldg B</span> </div>																																			
11B-S14C	Rev/App SDs Submittals-Pkg 11B Lab Equip.-Bldg C	10	17JUL09	30JUL09	<div style="display: flex; align-items: center;"> <div style="width: 15px; height: 10px; background-color: green; margin-right: 5px;"></div> <span>Rev/App SDs Submittals-Pkg 11B Lab Equip.-Bldg C</span> </div>																																			
08B-S12A1	Rev/App SD/Samples-Pkg 08B-Glass+Glazing-Bldg A	10	20JUL09	31JUL09	<div style="display: flex; align-items: center;"> <div style="width: 15px; height: 10px; background-color: green; margin-right: 5px;"></div> <span>Rev/App SD/Samples-Pkg 08B-Glass+Glazing-Bldg A</span> </div>																																			
08B-S12B1	Rev/App SD/Samples-Pkg 08B-Glass+Glazing-Bldg B	10	03AUG09	14AUG09	<div style="display: flex; align-items: center;"> <div style="width: 15px; height: 10px; background-color: green; margin-right: 5px;"></div> <span>Rev/App SD/Samples-Pkg 08B-Glass+Glazing-Bldg B</span> </div>																																			
08B-S12C1	Rev/App SD/Samples-Pkg 08B-Glass+Glazing-Bldg C	10	17AUG09	28AUG09	<div style="display: flex; align-items: center;"> <div style="width: 15px; height: 10px; background-color: green; margin-right: 5px;"></div> <span>Rev/App SD/Samples-Pkg 08B-Glass+Glazing-Bldg C</span> </div>																																			

Start Date 25A/PR04  
Finish Date 11MAY11  
Date Date 16MAR09  
Run Date 12MAR09 12:20



WN07 Sheet 26 of 26  
**GILBANE BUILDING COMPANY**  
**WORCESTER NORTH HIGH SCHOOL (WN07)**  
**REMAINING BY BUILDING/PHASE/LEVEL**



DRAFT			
Date	Revision	Checked	Approved
12MAR09	PRELIMINARY FOR REV		

**Appendix B: Schedule January 2010**

Activity	Start	Finish	Duration	Early Start	Early Finish	LS	LF	ES	EF
<b>WORCESTER NORTH HIGH SCHOOL (W116)</b>									
<b>PROJECT MILESTONES</b>									
4788K Area Complete - Kitchen/Cafeteria	0	0		11JAN11	18	-17	88A		
4499K Auditorium Complete	0	0		25JAN11	3	-19	99A		
MS-021 Buyout Complete	0	0		11MAR10	364	-52	99A		
MS-022 Submittals	0	0		11MAR10	367	-52	99A		
MS-200 GMP Approved - GMP Period Complete	0	0		10MAY10	345	-51	99A		
MS-031 Water Framing Complete	0	0		14MAY10	219	-44	99A		
MS-032 Start Finishes	0	0	25JUN10		312	-17	99A		
MS-035 MEP Rough-In Complete	0	0		16JUL10	175	-33	99A		
MS-041 Permanent Power Available	0	0	01SEP10*		44	0	99A		
MS-029 Start Elevators	0	0	10SEP10		259	-7	99A		
MS-035 Start Commissioning	0	0	29SEP10		247	-33	99A		
MS-034 Exterior Skin Complete	0	0		30NOV10	31	-22	99A		
MS-038 Commissioning Complete	0	0		06DEC10	161	-33	99A		
MS-033 Elevators Complete	0	0		06DEC10	150	-7	99A		
MS-057 Final Sitework + Landscape Complete	0	0		26DEC10	61	-22	99A		
MS-028 Roof Complete	0	0		26DEC10	183	-22	99A		
MS-041 Finishes Complete	0	0		14JAN11	50	-17	99A		
MS-039 General Punchlist Complete	0	0		29MAR11	0	-17	99A		
MS-099 Pre-Design Impact Substantial Completion	0	0		29MAR11	0	-17	99A		
9999 Design Impact	92	92	28MAR11		21JUN11	0	-17	99A	
MS-114 Pre-Design Impact Project Final Completion	0	0		20MAY11	62	-17	99A		
MS-100 Project Substantial Completion	0	0		21JUL11	0	-17	99A		
MS-105 Certificate Of Occupancy	0	0		21JUL11	0	-17	99A		
MS-110 Close-Out	40	40	22JUL11		16SEP11	0	-17	99A	
MS-043 Final Completion - Close-Out Complete	0	0		16SEP11	0	-17	99A		
MS-115 Project Final Completion	0	0		16SEP11	0	-17	99A		
SS-010 Procurement Phase	451*	40*	03JUN08A		11MAR10	344	-62	99A	
SS-021 Sitework + Landscape	593*	244*	01DEC08A		29DEC10	61	-22	99A	
SS-071 Metal Roof	325*	244*	21SEP08A		29DEC10	183	-22	99A	
SS-015 MEP Rough-In	185*	133*	15OCT08A		15JUL10	175	-33	99A	
SS-072 Install Exterior Studs, Demoglass + Massing	272*	214*	22OCT08A		15NOV10	8*	-22	99A	
SS-070 Install Exterior Skin (Summarizes SS-072+SS-073)	267*	224*	22OCT08A		30NOV10	0*	-22	99A	
SS-000 Install Interior Framing	118*	78*	30NOV08A		14MAY10	213	-44	99A	
SS-073 Install Exterior Metal Panels/Windows	224*	224*	15JAN10		30NOV10	8*	-22	99A	
SS-091 Install Finishes	140*	169*	28JUN10		14JAN11	172	-17	99A	


Site Date: 234 Pcs  
 Finish Date: 198 Pcs  
 Close Date: 21 JAN 10  
 Run Date: 23 JAN 10 14:25

Early Bar  
 Progress Bar  
 Critical Activity

W116  
**GILBANE BUILDING COMPANY**  
**WORCESTER NORTH HIGH SCHOOL (W116)**  
**BID PACKAGE - CURRENT WDK**



Activity	Start	Finish	Duration	Early Start	Early Finish	LS	LF	ES	EF





A-CAST IN PLACE CONCRETE FLAT WORK						
425062	Place Conc Inflr - Stair 4 (L)	2	2	07APR10	08APR10	105 25 031
425062	Place Conc Inflr - Stair 2 (SW)	2	2	08MAY10	08MAY10	100 28 051
4606C	Place Conc Inflr - Stair 5 (N)	2	2	19MAY10	20MAY10	10 0 031
425061	Place Conc Inflr - Stair 3 (SE)	2	2	17JUN10	18JUN10	86 19 081
4250A1	Place Conc Inflr - Stair 1 (W)	2	2	16JUL10	19JUL10	80 13 031
32A-036T	Coel Summary: CIP Conc Flatwork 03A	273	273	23JUN06A	19JUL10	80 19 021
CONCRETE SLABS ON GRADE - STRUCTURAL LEVEL 03A						
4746K	Place Conc Slab in Coolers - Kitchen/Caf	2	2	15JUN10	17JUN10	25 -91 03B
4746K	Cure/Dehumid Conc Slab in Coolers - Kitchen/Caf	40	40	18JUN10	18JUN10	86 -31 03D
2444C	Prep & Place Slab @ Stage - Auditorium	20	20	24SEP10	21OCT10	3 -19 03B
C-MASONRY (75B)						
04A-605	Rev Award-Masonry	3	3	15JAN10	19JAN10	23 -35 04A
04A-508	RevApp Award-Masonry	3	1	20JAN10	23JAN10	23 -35 04A
04A-510	Award Contract-04A-Masonry	3	3	21JAN10	25JAN10	23 -35 04A
04A-512	Prep/Sub SD+ Samples+ Access - Masonry	16	16	25JAN10	19FEB10	23 -26 04A
05B-62C	Prep/Sub Seismic CIP Data	16	16	25JAN10	19FEB10	49 -36 04A
04A-532	Prep/Sub SD+ Samples+ Access - Precast	15	15	28JAN10	19FEB10	340 0 04A
04A-547	Prep/Sub SD+ Samples+ Access - Brick	15	15	25JAN10	19FEB10	340 0 04A
04A-514	RevApp SDs + Access - Masonry	15	15	16FEB10	08MAR10	93 -29 04A
05B-527	RevApp Seismic CIP Data	15	15	10FEB10	08MAR10	89 -35 04A
04A-534	RevApp SDs + Access - Precast	16	16	18FEB10	08MAR10	340 0 04A
04A-544	RevApp SDs + Access - Brick	15	15	16FEB10	08MAR10	340 0 04A
04A-619	Fab/Del Masonry + Accessories - Masonry	70	20	05MAR10	05APR10	23 -45 04A
42R2	Fab/Del Install Seismic Clips	20	20	05MAR10	05APR10	88 -35 04A
04A-539	Fab/Del Masonry + Accessories - Precast	60	60	05MAR10	17MAY10	340 0 04A
04A-605	Fab/Del Masonry + Accessories - Brick	50	50	05MAR10	17MAY10	340 0 04A
04A-619	Mobilize - Masonry	9	0	06APR10		23 -45 04A
4256C	Build Elev C Shaft & Staging - Bldg C Masonry	15	15	06APR10	28APR10	28 -45 04A
4256B	Stair 4 (E) Shaft & Staging - Masonry Bldg B	25	25	07APR10	11MAY10	47 -45 04A
4256A	Masonry + Precast Lintels - Bldg A/B W,S,+E (1-4)	18	45	06APR10	17JUN10	16 -22 04A
4256A	Stair 2 (SW) Shaft & Staging - Masonry Bldg A	25	25	06MAY10	06JUN10	47 -18 04A
45B2C	CMU Interior Walls Col 17-22 - Locker Area	15	15	21MAY10	11JUN10	10 -33 04A
4256B	Masonry + Precast Lintels - Bldg A/B North (2-4)	30	30	04JUN10	15JUL10	16 -22 04A
4512C	CMU Interior Walls Col 22-28 - Locker Area	20	20	11JUN10	12JUL10	10 33 04A
4257R	Stair 3 (SE) Shaft & Staging - Masonry Bldg B	25	25	17JUN10	22JUL10	27 -28 04A
4258C	Masonry + Precast Lintels - Bldg C South + East (1)	30	30	12JUL10	20AUG10	16 -22 04A
4257A	Stair 1 (W) Shaft & Staging - Masonry Bldg A	25	25	15JUL10	19AUG10	27 -26 04A


Place Conc Inflr - Stair 4 (E)	Place Conc Inflr - Stair 2 (SW)	Place Conc Inflr - Stair 5 (N)	Place Conc Inflr - Stair 3 (SE)	Place Conc Inflr - Stair 1 (W)	Coel Summary: CIP Conc Flatwork 03A
Place Conc Slab in Coolers - Kitchen/Caf	Cure/Dehumid Conc Slab in Coolers - Kitchen/Caf	Prep & Place Slab @ Stage - Auditorium	Rev Award-Masonry	RevApp Award-Masonry	Award Contract-04A-Masonry
Prep/Sub SD+ Samples+ Access - Masonry	Prep/Sub Seismic CIP Data	Prep/Sub SD+ Samples+ Access - Precast	Prep/Sub SD+ Samples+ Access - Brick	RevApp SDs + Access - Masonry	RevApp Seismic CIP Data
RevApp SDs + Access - Precast	RevApp SDs + Access - Brick	Fab/Del Masonry + Accessories - Masonry	Fab/Del Install Seismic Clips	Fab/Del Masonry + Accessories - Precast	Fab/Del Masonry + Accessories - Brick
Mobilize - Masonry	Build Elev C Shaft & Staging - Bldg C Masonry	Stair 4 (E) Shaft & Staging - Masonry Bldg B	Masonry + Precast Lintels - Bldg A/B W,S,+E (1-4)	Stair 2 (SW) Shaft & Staging - Masonry Bldg A	CMU Interior Walls Col 17-22 - Locker Area
Masonry + Precast Lintels - Bldg A/B North (2-4)	CMU Interior Walls Col 22-28 - Locker Area	Stair 3 (SE) Shaft & Staging - Masonry Bldg B	Masonry + Precast Lintels - Bldg C South + East (1)	Stair 1 (W) Shaft & Staging - Masonry Bldg A	

Start Date	25APR08	25APR08	Early Bar
Finish Date	16SEP11	16SEP11	Progress Bar
Date Code	15MAY10	15MAY10	Critical Activity
Run Date	22JUN10 14:28		

GILBANE BUILDING COMPANY		Sheet 3 of 31
WORCESTER NORTH HIGH SCHOOL (W116)		
BID PACKAGE - CURRENT WORK		
<b>Gilbane</b>		

4295A	Build Elev A Shaft & Staging - Bldg A Masonry	20	20	13AUG10	16SEP10	37	-25	04A	Build Elev A Shaft & Staging - Bldg A Masonry
4292C	Masonry + Precast Lintels - Bldg C NW, -S (Gym Aud	25	25	16AUG10	04OCT10	16	-22	04A	Masonry + Precast Lintels - Bldg C N, W, -S (Gym
4256C	Masonry + Precast Lintels - Bldg A/B/C - W, L+R (1)	30	30	28SEP10	09NOV10	18	-22	04A	Masonry + Precast Lintels - Bldg A/B/C W
4254C	Masonry + Precast Lintels - Bldg A/B/C - Fill Ins	10	10	02NOV10	15NOV10	51	-22	04A	Masonry + Precast Lintels - Bldg A/B/C F
04A-006T	Cost Summary: Masonry 04A	158*	158*	07APR10	15NOV10	51	-22	04A	Cost Summary: Masonry 04A
<b>STRUCTURAL STEEL DECK</b>									
06A-676	Fab/Del Tube Steel - K Line Library 2nd Flr	10	10	16JAN10A	26JAN10	95	0	06A	Fab/Del Tube Steel - K Line Library 2nd Flr
2-534Z	Instal Tube Steel Rein Wall - K Line Library	5	5	25JAN10	04FEB10	6E	0	06A	Instal Tube Steel Rein Wall - K Line Library
<b>C-MISCELLANEOUS METALS - FSB</b>									
05B-652	Prep/Sub SD Aud Ladders - 05B - Bldg A	39	6	06NOV09A	22JAN10	99E	-14	05B	Prep/Sub SD Aud Ladders - 05B - Bldg A
05B-622	Prep/Sub SD Lintels - 05B - Bldg A	15	11	06NOV09A	20JAN10	12	-41	05B	Prep/Sub SD Lintels - 05B - Bldg A
05B-642	Prep/Sub SD Elev hoist beam - 05B - Bldg A	18	11	09NOV09A	23JAN10	38*	-41	05B	Prep/Sub SD Elev hoist beam - 05B - Bldg A
06B-611A1	RevApp Re-sub SD's Stairs (E, SE, SW, W)	40*	18*	14DEC09A	09FEB10	10	0	05B	RevApp Re-sub SD's Stairs (E, SE, SW, W)
05B-634	RevApp SD's Aud Ladders - Misc Met Bldg A	10	10	25JAN10	06FEB10	39E	14	05B	RevApp SD's Aud Ladders - Misc Met Bldg A
05B-634	RevApp SD's Lintels - 05B-Misc Met Bldg A	10	10	01FEB10	27FEB10	12	-44	05B	RevApp SD's Lintels - 05B-Misc Met Bldg A
05B-644	RevApp SD's Elev Hoist Beam-Misc Met Bldg A	10	10	01FEB10	12FEB10	301	-41	05B	RevApp SD's Elev Hoist Beam-Misc Met Bldg A
05B-655	Fab/Del Aud Ladders - 05B-Misc Metals Bldg A	15	15	06FEB10	26FEB10	29E	-14	05B	Fab/Del Aud Ladders - 05B-Misc Metals Bldg A
05B-6165Z	Fab/Del Stair 4 (E) - 05B-Misc Metals Bldg B	20	20	10FEB10*	09MAR10	10	-36	05B	Fab/Del Stair 4 (E) - 05B-Misc Metals Bldg B
05B-616A2	Fab/Del Stair 2 (SW) - 05B-Misc Metals Bldg A	20	20	10FEB10*	09MAR10	30	-36	05B	Fab/Del Stair 2 (SW) - 05B-Misc Metals Bldg A
06B-639	Fab/Del Lintels - 05B-Misc Metals Bldg A	15	15	15FEB10	05MAR10	12	44	05B	Fab/Del Lintels - 05B-Misc Metals Bldg A
06B-646	Fab/Del Elev Hoist Beam - 05B-Misc Metals Bldg A	15	15	16FEB10	05MAR10	301	-41	05B	Fab/Del Elev Hoist Beam - 05B-Misc Metals Bldg A
05B-616B1	Fab/Del Stair 3 (SE) - 05B-Misc Metals Bldg B	22	22	03MAR10*	01APR10	70	-4E	05B	Fab/Del Stair 3 (SE) - 05B-Misc Metals Bldg B
05B-616A1	Fab/Del Stair 1 (W) - 05B-Misc Metals Bldg A	22	22	03MAR10*	01APR10	60	-26	05B	Fab/Del Stair 1 (W) - 05B-Misc Metals Bldg A
05B-616C1	Fab/Del Stair 5 (N) - 05B-Misc Metals Bldg C	10	10	05APR10*	16APR10	361	24	05B	Fab/Del Stair 5 (N) - 05B-Misc Metals Bldg C
05B-619	Mod/In Pkg 05B Miscellaneous metals	0	0	10MAR10		10	25	05B	Mod/In Pkg 05B Miscellaneous metals
428064	Instal Metal Pan Stair 4 (E)	20	20	10MAR10	06APR10	10	70	05B	Instal Metal Pan Stair 4 (E)
4280A2	Instal Metal Pan Stair 2 (SW)	20	20	07APR10	04MAY10	10	28	05B	Instal Metal Pan Stair 2 (SW)
4503C	Instal Metal Pan Stair 3 (N) Basement to 1st	10	10	06MAY10	18MAY10	10	3	05B	Instal Metal Pan Stair 3 (N) Basement to 1st
4280A3	Instal Metal Pan Stair 3 (SE)	20	20	16MAY10	16JUN10	27	19	05B	Instal Metal Pan Stair 3 (SE)
4280A*	Instal Metal Pan Stair 1 (W)	20	20	17JUN10	15JUL10	37	19	05B	Instal Metal Pan Stair 1 (W)
4522C	Instal Seismic Clips - Locker Area	10	10	05JUL10	19JUL10	5E	93	05B	Instal Seismic Clips - Locker Area
05B-036T	Cost Summary: Misc Metals 05B	390*	389*	10MAR10	16SEP11	6	-293	05B	Cost Summary: Misc Metals 05B
<b>E-MILLWORK</b>									
06A-606	Rec Award-06A-Millwork	7	7	24NOV09A	25JAN10	12	-38	06A	Rec Award-06A-Millwork
06A-606	RevApp Award-06A-Millwork	3	3	25JAN10	28JAN10	102	-38	06A	RevApp Award-06A-Millwork
06A-610	Award Contract-06A-Millwork	3	3	28JAN10	02FEB10	102	-38	06A	Award Contract-06A-Millwork
06A-612AB	Submit SD's Submittals 06A-Millwork- Bldg A/B	20	20	05FEB10	02MAR10	132	-32	06A	Submit SD's Submittals 06A-Millwork- Bldg A/B
06A-612C	Submit SD's Submittals 06A-Millwork- Bldg C	20	20	05FEB10	02MAR10	132	-32	06A	Submit SD's Submittals 06A-Millwork- Bldg C
Start Date	25/PROG	25/PROG	25/PROG	25/PROG	25/PROG	25/PROG	25/PROG	25/PROG	25/PROG
End Date	15SEP11	15SEP11	15SEP11	15SEP11	15SEP11	15SEP11	15SEP11	15SEP11	15SEP11
Estimate	06A-01	06A-01	06A-01	06A-01	06A-01	06A-01	06A-01	06A-01	06A-01
Rev Date	06A-01	06A-01	06A-01	06A-01	06A-01	06A-01	06A-01	06A-01	06A-01
<p style="text-align: center;"><b>GILBANE BUILDING COMPANY</b></p> <p style="text-align: center;"><b>WORCESTER NORTH HIGH SCHOOL (W116)</b></p> <p style="text-align: center;"><b>BID PACKAGE - CURRENT WORK</b></p>									
									
<p style="text-align: center;">© Piraveera Systems, Inc.</p>									

Activity	Description	Start	End	Duration	Start	End	Duration	Start	End	Duration	Start	End	Duration																									
05A-014A	Rev/App SD's Submittals -05A-Millwork Bldg A/B	15	16	03MAR10	23MAR10	102	-38	08A																														
05A-014B	Rev/App SD's Submittals 05A-Millwork Bldg C	15	16	03MAR10	23MAR10	102	-38	08A																														
05A-015A	Fab/Del Materials 05A-Millwork Bldg A/B	30	30	24MAR10	04MAY10	102	-38	08A																														
05A-015B	Fab/Del Materials 05A-Millwork Bldg C	30	30	24MAR10	04MAY10	102	-38	08A																														
05A-016	Mobilize 05A-Millwork	0	0	22SEP10		0	-17	06A																														
4-04-04B	Complete Millwork - 4th Flr - Bldg A-B	20	20	22SEP10	19OCT10	5	-17	06A																														
2-04-04B	Complete Millwork - 2nd Flr - Bldg A-B	20	20	20OCT10	19NOV10	5	-17	06A																														
1-04-04B	Complete Millwork - 1st Flr - Bldg A-B	30	30	09DEC10	21JAN11	5	-17	06A																														
5410C	Complete Millwork - Bldg C	20	20	03JAN11	28JAN11	5	-17	06A																														
05A-COST	Cost Summary: Millwork 05A	90	90	22SEP10	28JAN11	5	-17	06A																														
<b>C-ROOFING (RSB)</b>																																						
4215A	Roofing Details Bldg A	20	20	01DEC10	20DEC10	31	-22	07B																														
4216B	Roofing Details Bldg B	20	20	01DEC10	20DEC10	31	-22	07B																														
<b>C-WATERPROOFING+JOINT SEALANTS (RSB)</b>																																						
07C-012	Prep/Sub Samples & Data - Air Barrier/Waterproof	15	15	16JAN10	04FEB10	28	-47	07C																														
07C-015	Prep/Sub Samples & Data - Joint Sealants	15	15	16JAN10	04FEB10	28	-47	07C																														
07C-022	Rev/App Samples & Data Air Barrier/Waterproof	15	15	05FEB10	25FEB10	28	-47	07C																														
07C-025	Rev/App Samples & Data - Joint Sealants	15	15	05FEB10	25FEB10	28	-47	07C																														
07C-032	Fab/Del - Air Barrier/Waterproof	12	12	26FEB10	15MAR10	28	-41	07C																														
07C-035	Fab/Del - Joint Sealants	12	12	26FEB10	15MAR10	28	-41	07C																														
07C-018	Mobilize Waterproofing+Joint Sealants	0	0	01APR10		10	-23	07C																														
4260A	AVB pre-Masonry - Bldg A/B W,S,+E (1-4)	45	45	01APR10	03JUN10	16	-23	07C																														
4310A	AVB pre-Windows - Bldg A/B W,S,+E (1-4)	15	15	13MAY10	15JUL10	16	-29	07C																														
4280D	AVD pre-Masonry - Bldg A/B North (2-4)	30	30	20MAY10	01JUL10	16	-23	07C																														
4330A	Window Sealants - Bldg A/B W,S,+E (1-4)	48	48	16JUN10	20AUG10	10	-22	07C																														
4290C	AVB pre-Masonry - Bldg C South +East (1)	30	30	25JUN10	08AUG10	16	-28	07C																														
4310B	AVB pre-Windows - Bldg A/B North (2-4)	30	30	02JUL10	15AUG10	16	-22	07C																														
4262C	AVB pre-Masonry - Bldg C N,W,+S (Gym-Aud)	35	35	02AUG10	20SEP10	16	-25	07C																														
4210C	AVB pre-Windows - Bldg C South +East (1)	30	30	08AUG10	20SEP10	16	-29	07C																														
4330B	Window Sealants - Bldg A/B North (2-4)	30	30	08AUG10	20SEP10	16	-22	07C																														
4263C	AVB pre-Masonry - Bldg A/B/C W,F+N (1)	30	30	14SEP10	25OCT10	10	-23	07C																														
4300C	Window Sealants - Bldg C South +East (1)	30	30	14SEP10	25OCT10	16	-22	07C																														
4212C	AVD pre-Windows - Bldg C N,W,+S (Gym-Aud)	35	35	14SEP10	01NOV10	16	-22	07C																														
4284C	AVD pre-Masonry - Bldg A/B/C Fill-ins	10	10	19OCT10	01NOV10	5	-23	07C																														
4332C	Window Sealants - Bldg C N,W,+S (Gym-Aud)	35	35	19OCT10	07DEC10	18	-22	07C																														
4313C	AVB pre-Windows - Bldg A/B/C W,E+N (1)	30	30	29OCT10	07DEC10	18	-22	07C																														
4314C	AVB pre-Windows - Bldg A/B/C Fill-ins	10	10	01DEC10	14DEC10	31	-22	07C																														
<div style="display: flex; justify-content: space-between;"> <div style="width: 20%;"> <p>Start Date: 25APR08 Finish Date: 19SEP11 13th Date: 15MAY10 Mer Date: 22JUN10 14:28</p> </div> <div style="width: 40%; text-align: center;"> <p>W415</p> <p><b>GILBANE BUILDING COMPANY</b></p> <p><b>WORCESTER NORTH HIGH SCHOOL (W415)</b></p> <p><b>BID PACKAGE - CURRENT WORK</b></p> </div> <div style="width: 20%; text-align: right;"> <p>3/24/11 of 21</p> </div> <div style="width: 20%; border: 1px solid black;"> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>File</th> <th>Created</th> <th>Public</th> <th>View</th> <th>Print</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table> </div> </div>														File	Created	Public	View	Print																				
File	Created	Public	View	Print																																		

Item No.	Description	QTY	UNIT	START DATE	END DATE	EST. COST	ACT. COST
4335C	Window Sealants - Bldg A/B/C W/E+N (1)	30	30	01DEC10	13JAN11	18	-22.070
4334C	Window Sealants - Bldg A/B/C R/Hs	10	10	07JAN11	20JAN11	18	-22.070
070-008T	Cost Summary: Waterproofing & Sealants 070	208*	208*	01APR10	20JAN11	18	-22.070
<b>A-SPRAY ON FIREPROOFING</b>							
42100C	Fireproof Interior Perimeter 1st Flr Bldg C Aud	57'	0'	11OCT09A	22JAN10	22	21.070
4200C	Fireproof Exterior Perimeter Bldg C (Gym)	7	7	01APR10*	05APR10	24	-31.070
4416C	Fireproof Patching @ Ceiling - Auditorium	6	5	21MAY10	27MAY10	72	0.070
4624C	Fireproof Patching - Locker Area	3	3	20JUL10	22JUL10	50	-33.070
070-009T	Cost Summary: Spray Fireproofing 070	141*	01*	22SEP08A	06APR10	24	-76.070
<b>B-METAL SIDING &amp; LOUVERS</b>							
050-500	100% CD's Issued for -Pkg 07E-Metal Panels+Lou	0	0		06FEB10*	124	-67.07E
050-500	Rec Award-07E Metal Panels	7	7	15JAN10	25JAN10	127	-30.07E
050-500	RevApp Award-07E Metal Panels	3	3	26JAN10	26JAN10	177	-30.07E
050-510	Award Contract-07E Metal Panels	13	3	26JAN10	02FEB10	127	-30.07E
050-512AS	Prep/Sub SD & Data-07E Metal Panels Bldg A/B	23	23	08FEB10	03MAR10	124	-33.07E
350-512C	Prep/Sub SD & Data-07E Metal Panels Bldg C	23	20	09FEB10	06MAR10	144	-33.07E
050-514AS	RevAppSD's Submittals-07E Metal Panels Bldg A/B	15	15	08MAR10	08MAR10	174	-33.07E
350-514C	RevAppSD's Submittals-07E Metal Panels Bldg C	18	15	08MAR10	08MAR10	141	-33.07E
050-516AS	Fab/Del Materials-07E Metal Panels Bldg A/B	53	50	29MAR10	07JUN10	124	-33.07E
050-516C	Fab/Del Materials-07E Metal Panels C	33	33	29MAR10	07JUN10	144	-33.07E
050-518	Met/Ins-Pkg 07E Metal Panels	3	0	05OCT10		41	-22.07E
-1261C	Instal Metal Panels Bldg C	30	30	05OCT10	15NOV10	61	22.07E
42B1AB	Instal Metal Panels Bldg A/B @ Slr's only	30	30	18OCT10	30NOV10	31	-22.07E
350-005T	Cost Summary: Metal Panels 07E	40*	40*	05OCT10	30NOV10	51	-22.07E
<b>C-METAL WINDOWS/ROOF EFFORTS (RSB)</b>							
08A-5151	Fab/Del-Mtl Storefronts Bldg A/B	40	40	21DEC09A	11MAR10	70	-30.05A
08A-5152	Fab/Del-Mtl Storefronts Bldg C	10	40	21DEC09A	11MAR10	205	-30.05A
08A-5151	Fab/Del-Mtl Windows / Receptors Bldg A	60	60	21DEC09A	09APR10	55	-30.05A
08A-5152	Fab/Del-Mtl Windows / Receptors Bldg B	60	60	21DEC09A	09APR10	55	-30.05A
08A-5153	Fab/Del-Mtl Windows / Receptors Bldg C	60	60	21DEC09A	09APR10	115	-30.05A
08A-519	Met/Ins On Site-Metal Window Receptors	0	0	04JUN10		16	22.05A
4320A	Windows - Bldg A/B W,S,+E (1-4)	45	45	04JUN10	05AUG10	16	-22.05A
4320B	Windows - Bldg A/D North (2-4)	30	30	26JUL10	06SEP10	16	-22.05A
4320C	Windows - Bldg C South +East (1)	30	30	30AUG10	11OCT10	16	-22.05A
4250C	Instal Storefront-Bldg C	30	30	06OCT10	16NOV10	61	-22.05A
4322C	Windows - Bldg C W,N,+S (Gym-Aud)	35	35	05OCT10	22NOV10	16	-22.05A
4250A	Instal Storefronts-Bldg A/B	30	30	19OCT10	30NOV10	31	-22.05A
4322C	Windows - Bldg A/B/C W,E+N (1)	30	30	18NOV10	29DEC10	16	-22.05A

Start Date: 01/01/2009  
Finish Date: 12/31/11  
Cost Data: 01/01/10  
Run Type: Primavera 6.10.02

Legend:  
 Early Bar  
 Progress Bar  
 Critical Activity

**GILBANE BUILDING COMPANY**  
**WORCESTER NORTH HIGH SCHOOL (W116)**  
**BID PACKAGE - CURRENT WORK**

Sheet 6 of 24

CD#	Description	QTY	UNIT	START DATE	END DATE	EST. COST	ACT. COST	STATUS
08B-COST	Cost Summary: Metal Windows/Storefront GSA	148'	148'	04JUN10	26DEC10	18	-22.00A	
<b>F-GLASS + GLAZING (10R)</b>								
08B-300	100% CD's Issued for -Pkg 08B-Glass+Glazing	0	0		01FEB10	115	-53.08B	◆100% CD's Issued for -Pkg 08B-Glass+Glazing
08B-304	Bid Period -Pkg 08B-Glass+Glazing	15	15	02FEB10	22FEB10	116	-52.08B	■ Bid Period -Pkg 08B-Glass+Glazing
08B-306	Rec. Award-Pkg 08B-Glass+Glazing	7	7	23FEB10	03MAR10	116	-52.08B	■ Rec. Award-Pkg 08B-Glass+Glazing
08B-308	Rev/App Award Pkg 08B-Glass+Glazing	3	3	04MAR10	05MAR10	115	-52.08B	■ Rev/App Award-Pkg 08B-Glass+Glazing
08B-310	Award Contract-Pkg 08B-Glass+Glazing	3	3	09MAR10	11MAR10	115	-52.08B	■ Award Contract-Pkg 08B-Glass+Glazing
08B-312	Prep/Sub SD+Data-Pkg 08B-Glass & Glazing	15	15	17MAR10	31APR10	115	-52.08B	■ Prep/Sub SD+Data-Pkg 08B-Glass & Glazing
08B-314	Rev/App SD+Samples-Pkg 08B-Glass & Glazing	15	15	02APR10	22APR10	116	-52.08B	■ Rev/App SD+Samples-Pkg 08B-Glass & Glazing
08B-316A	Fab/Del Materials-Pkg 08B-Glass+Glazing-Bldg A/B	16	16	23APR10	13MAY10	115	-52.08B	■ Fab/Del Materials-Pkg 08B-Glass+Glazing-Bldg A/B
08B-316B	Fab/Del Materials-Pkg 08B-Glass+Glazing-Bldg C	15	15	23APR10	13MAY10	115	-52.08B	■ Fab/Del Materials-Pkg 08B-Glass+Glazing-Bldg C
08B-316	Mobilize-Pkg 08B-Glass+Glazing	3	0	06OCT10		15	-17.08B	◆ Mobilize-Pkg 08B-Glass+Glazing
4-4500AB	Interior Glass & Glazing - Bldg A/B Flr. 4	10	10	09OCT10	18OCT10	15	-17.08B	■ Interior Glass & Glazing - Bldg A/B Flr. 4
3-4500AB	Interior Glass & Glazing - Bldg A/B Flr. 3	10	10	27OCT10	09NOV10	0	-17.08B	■ Interior Glass & Glazing - Bldg A/B Flr. 3
2-4500AB	Interior Glass & Glazing - Bldg A/B Flr. 2	10	10	17NOV10	01DEC10	0	-17.08B	■ Interior Glass & Glazing - Bldg A/B Flr. 2
1-4500AB	Interior Glass & Glazing - Bldg A/B Flr. 1	10	10	09DEC10	22DEC10	0	-17.08B	■ Interior Glass & Glazing - Bldg A/B Flr. 1
4500C	Interior Glass & Glazing - Bldg C	10	10	22DEC10	07JAN11	0	-17.08B	■ Interior Glass & Glazing - Bldg C
08B-COST	Cost Summary: Glass & Glazing 08B	65'	65'	06OCT10	07JAN11	0	-17.08B	◆ Cost Summary: Glass & Glazing 08B
<b>C-DOORS, FRAMES + HARDWARE</b>								
08C-515A	Fab/Del Door Frames Bldg A/B	41'	40'	14JAN10A	11MAR10	3	41.08C	■ Fab/Del Door Frames Bldg A/B
08C-516C	Fab/Del Door Frames/Bldg C	41'	40'	14JAN10A	11MAR10	85	21.08C	■ Fab/Del Door Frames/Bldg C
08C-516B	Fab/Del Doors/Hdw/Bldg A/B	60	60	14JAN10A	25MAR10	130	-41.08C	■ Fab/Del Doors/Hdw/Bldg A/B
08C-516C	Fab/Del Doors/Hdw - Bldg C	60	60	14JAN10A	25MAR10	185	0.08C	■ Fab/Del Doors/Hdw - Bldg C
08C-518	Mobilize-08C Frames, Doors+Hdw	0	0	26MAR10		40	-24.08C	◆ Mobilize-08C Frames, Doors+Hdw
08C-COST	Cost Summary: Doors+Frames+Hardware 08C	188'	188'	26MAR10	20DEC10	0	-17.08C	◆ Cost Summary: Doors+Frames+Hardware
<b>E-SPECIAL DOORS</b>								
08D-500	100% CD's Issued for -Pkg 08D-Special Doors	0	0		01FEB10	91	-65.08D	◆100% CD's Issued for -Pkg 08D-Special Doors
08D-504	Bid Period -08D-Special Doors	20'	211'	15NOV09A	25NOV09	91	-259.08D	■ Bid Period -08D-Special Doors
08D-505	Rec. Award-08D-Special Doors	7	7	30NOV10	03DEC10	91	-252.08D	■ Rec. Award-08D-Special Doors
08D-508	Rev/App Award-08D-Special Doors	3	3	09DEC10	13DEC10	91	-252.08D	■ Rev/App Award-08D-Special Doors
08D-510	Award Contract-08D-Special Doors	3	3	14DEC10	16DEC10	91	-252.08D	■ Award Contract-08D-Special Doors
08D-512A	Submit SD's Submittals-Special Doors Bldg A/B/C	16	15	17DEC10	17JAN11	91	-252.08D	■ Submit SD's Submittals-Special Doors
08D-514A	Rev/App SD's Submittals-Special Doors Bldg A/B/C	15	15	11JAN11	31JAN11	91	-252.08D	■ Rev/App SD's Submittals-Special Doors
08D-516A	Fab/Del Materials-Special Doors Bldg A/B/C	60	60	01FEB11	11APR11	91	-252.08D	■ Fab/Del Materials-Special Doors Bldg A/B/C
08D-518	Mobilize-08D-Special Doors	0	0	12APR11		91	-24.08D	◆ Mobilize-08D-Special Doors
4750	Install Special Doors - Bldgs A/B/C	20	20	12APR11	06MAY11	91	-24.08D	■ Install Special Doors - Bldgs A/B/C
08D-COST	Cost Summary: Special Doors 08D	20'	20'	12APR11	06MAY11	91	-24.08D	◆ Cost Summary: Special Doors 08D

Start Date	20APR08
Inter-Date	16SEP08
End Date	15MAY09
Run Time	22AM10 14:28

Legend	Bar	Color	Activity
■	Early Bar	Yellow	Early Bar
■	Progress Bar	Green	Progress Bar
■	Critical Activity	Red	Critical Activity

**GILBANE BUILDING COMPANY**  
**WORCESTER NORTH HIGH SCHOOL (W16)**  
**BID PACKAGE - CURRENT WORK**




Activity	Start	End	Duration	Start	End	Duration	Activity
1-5380	25JAN10	26JAN10	1	25	26	1	Stud Frame Walls - 1st Flr (Interior)
2-5330	25JAN10	24JAN10	-1	24	23	-1	Stud Frame Walls 2nd Flr
2-5332	15JAN10	21JAN10	6	15	21	6	Install Door Frames 2nd Flr
4400C	25JAN10	28MAR10	63	25	22	-23	Install LGMF & GVB @ Aud + Stage Walls - Auditorium
4700K	27JAN10	32FEB10	35	27	16	-11	Stud Frame Walls - Kitchen/Caf
4700K	03FEB10	20FEB10	17	03	16	-1	Door Frames / Mngr Critia HRP Frames - Kitchen/Ca
2-5544	05FEB10	11FEB10	6	05	0	-5	Studs / Deck K Line Library Wall -
3-5320	05FEB10	25FEB10	20	05	25	20	Stud Frame Walls 3rd Flr
1-5322	12MAR10	18MAR10	6	12	0	-12	Install Door Frames - 1st Flr
4-5320	12MAR10	07APR10	25	12	24	12	Stud Frame Walls 4th Flr
3-5327	15MAR10	25MAR10	10	15	25	10	Install Door Frames 3rd Flr
1-5355	19MAR10	07APR10	19	19	0	-19	Sheetrock Walls - 1st Flr
4-5312	26MAR10	07APR10	12	26	10	-16	Install Door Frames 3th Flr
4400C	28MAR10	07APR10	10	28	22	0	Erect Work Platform - Auditorium
1-5380	02APR10	07APR10	5	02	10	8	Tape Sheetrock Walls - 1st Flr
4-700K	02APR10	11APR10	9	02	17	15	Sheetrock Walls - Kitchen/Caf
4414C	02APR10	27APR10	25	02	0	-25	Tape + Sand Walls - Auditorium
2-5355	02APR10	28APR10	26	02	0	-26	Sheetrock Walls - 2nd Flr
4702K	10APR10	25APR10	15	10	18	8	Tape Sheetrock Walls - Kitchen/Caf
2-5350	16APR10	18MAY10	32	16	17	-19	Tape Sheetrock Walls - 2nd Flr
5350C	25APR10	17MAY10	22	25	14	-11	Stud Frame Walls - Bldg C
3-5355	30APR10	27MAY10	27	30	3	-27	Sheetrock Walls - 3rd Flr
5357C	10MAY10	17MAY10	7	10	14	4	Install Door Frames - Bldg C
3-5350	14MAY10	11JUN10	28	14	17	-11	Tape Sheetrock Walls - 3rd Flr
4-5355	28MAY10	25JUN10	28	28	17	-11	Sheetrock Walls - 4th Flr
4-5350	14JUN10	12JUL10	29	14	17	-17	Tape Sheetrock Walls - 4th Flr
5450C	20JUN10	06JUL10	16	20	54	34	Stage Areas in Gym
5450C	07JUL10	20JUL10	13	07	18	11	Frame Inside High Area - Gym
5355C	20JUL10	18AUG10	29	20	10	-10	Sheetrock Walls - Bldg C
4526C	23JUL10	06AUG10	14	23	59	36	Frame/ Board GYP Ceilings - Locker Area
5350C	03AUG10	30AUG10	27	03	33	30	Tape Sheetrock Walls - Bldg C
4420C	23AUG10	25AUG10	2	23	10	17	Dismantle Work Platform - Auditorium
4420C	28AUG10	23SEP10	25	28	3	-19	LGMF & Deck @ Stage - Auditorium
5500C	16SEP10	21SEP10	5	16	60	44	Remove Staging From Gymnasium
4-5405	22SEP10	19OCT10	27	22	17	-15	Install Doors / Hardware - 4th Flr
3-5405	13OCT10	09NOV10	26	13	17	-16	Install Doors / Hardware - 3rd Flr
2-5405	03NOV10	01DEC10	29	03	17	-16	Install Doors / Hardware - 2nd Flr

Start Date: 25APR08  
 Finish Date: 18SEP11  
 Data Date: 15MAR10  
 User: 22/03/10 14:28

Empty Bar  
 Progress Bar  
 Critical Activity

W118  
**GILBANE BUILDING COMPANY**  
 WORCESTER NORTH HIGH SCHOOL (W118)  
 BID PACKAGE - CURRENT WORK



Activity	Start	End	Start	End	Start	End	Start	End	Start	End	Start	End
4442C Interior Systems & Finishes - Auditorium	40	40	02NOV10	04JAN11	31	-13	06A	Interior Systems & Finishes - Aud				
1-540b Instal Doors / Hardware - 1st Flr	18	18	24NOV10	20DEC10	0	17	06A	Instal Doors / Hardware - 1st Flr				
54C3C Instal Doors / Hardware - Bldg C	50	10	02DEC10	19DEC10	10	-33	06A	Instal Doors / Hardware - Bldg C				
4764K Instal Doors / Hardware - Kitchen/Caf	2	2	10JAN11	11JAN11	15	-7	06A	Instal Doors / Hardware - Kitchen/Caf				
08A-00ST Cost Summary Drywall 08A	308*	282*	09NOV09A	25JAN11	6	-18	06A	Cost Summary: Drywall 08A				
<b>00B CERAMIC TILE (P.38)</b>												
06B-500 100% CD's Issued for-Pkg 06B Ceramic Tile	0	0		01FEB10	55	-53	06B	100% CD's Issued for-Pkg 06B Ceramic Tile				
06B-504 Bid Period - Ceramic Tile	15	15	02FEB10	22FEB10	56	52	06B	Bid Period - Ceramic Tile				
06B-506 Rec. Award - Ceramic Tile	7	7	23FEB10	03MAR10	95	-52	06B	Rec. Award - Ceramic Tile				
06B-508 Rev/App Award - Ceramic Tile	3	3	04MAR10	05MAR10	05	-52	06B	Rev/App Award - Ceramic Tile				
06B-510 Award Contract - Ceramic Tile	3	3	09MAR10	11MAR10	95	-52	06B	Award Contract - Ceramic Tile				
06B-512 Prep/Sub Submittals - Ceramic Tile	16	15	12MAR10	01APR10	56	52	06B	Prep/Sub Submittals - Ceramic Tile				
06B-514 Rev/App Submittals - Ceramic Tile Submittals	15	15	02APR10	22APR10	95	52	06B	Rev/App Submittals - Ceramic Tile Submittals				
06B-518 Fabric/Materials - Ceramic Tile	30	30	25APR10	04JUN10	05	-52	06B	Fabric/Materials - Ceramic Tile				
06B-518 Mobilize-06B Ceramic Tile	0	0	20JUL10		65	-17	06B	Mobilize-06B Ceramic Tile				
4-5540 Instal Ceramic Tile Wall Base - 4th Flr	10	10	20JUL10	02AUG10	65	-17	06B	Instal Ceramic Tile Wall Base - 4th Flr				
3-5540 Instal Ceramic Tile Wall Base - 3rd Flr	10	10	03AUG10	16AUG10	70	-17	06B	Instal Ceramic Tile Wall Base - 3rd Flr				
2-5540 Instal Ceramic Tile Wall Base - 2nd Flr	10	10	17AUG10	30AUG10	76	17	06B	Instal Ceramic Tile Wall Base - 2nd Flr				
1-5540 Instal Ceramic Tile - 1st Flr	10	10	31AUG10	14SEP10	80	-17	06B	Instal Ceramic Tile - 1st Flr				
5540C Instal Gymnasium Ceramic Tile In Locker Rooms	15	15	15SEP10	09OCT10	50	-33	06B	Instal Gymnasium Ceramic Tile In Locker Rooms				
06B-00ST Cost Summary Ceramic Tile 06B	55*	55*	20JUL10	09OCT10	65	-32	06B	Cost Summary: Ceramic Tile 06B				
<b>00C ACTUATOR CEILING (P.39)</b>												
05C-500 100% CD's Issued for-Pkg 05C ACT Ceilings	0	0		01FEB10	20	-63	05C	100% CD's Issued for-Pkg 05C ACT Ceilings				
05C-504 Bid Period - Pkg 05A ACT Ceilings	15	15	02FEB10	22FEB10	20	-82	05C	Bid Period - Pkg 05A ACT Ceilings				
05C-506 Rec. Award-Pkg 05A ACT Ceilings	7	7	25FEB10	03MAR10	70	-52	05C	Rec. Award-Pkg 05A ACT Ceilings				
05C-508 Rev/App Award-Pkg 05C ACT Ceilings	5	5	04MAR10	05MAR10	20	-52	05C	Rev/App Award-Pkg 05C ACT Ceilings				
05C-510 Award Contract-Pkg 05A ACT Ceilings	5	5	09MAR10	11MAR10	20	-52	05C	Award Contract-Pkg 05A ACT Ceilings				
09C-512A Submit SDs Submittals-Pkg05A ACT Ceilings Bldg A	15	15	12MAR10	01APR10	20	-52	05C	Submit SDs Submittals-Pkg05A ACT Ceilings Bldg A				
09C-512B Submit SDs Submittals-Pkg05A ACT Ceilings Bldg B	15	15	02APR10	22APR10	20	-52	05C	Submit SDs Submittals-Pkg05A ACT Ceilings Bldg B				
09C-514A Rev/App SDs Submittals-Pkg05A ACT Ceilings Bldg A	15	15	02APR10	22APR10	20	02	05C	Rev/App SDs Submittals-Pkg05A ACT Ceilings Bldg A				
09C-514B Rev/App SDs Submittals-Pkg05A ACT Ceilings Bldg B	15	15	23APR10	13MAY10	20	-82	05C	Rev/App SDs Submittals-Pkg05A ACT Ceilings Bldg B				
09C-512C Submit SDs Submittals-Pkg05A ACT Ceilings Bldg C	10	10	23APR10	13MAY10	55	-52	05C	Submit SDs Submittals-Pkg05A ACT Ceilings Bldg C				
09C-516A Fabric/Matls+EquipPkg 05A ACT Ceilings Bldg A	20	20	23APR10	20MAY10	61	-52	05C	Fabric/Matls+EquipPkg 05A ACT Ceilings Bldg A				
09C-514C Rev/App SDs Submittals-Pkg05A ACT Ceilings Bldg C	15	15	14MAY10	04JUN10	55	-52	05C	Rev/App SDs Submittals-Pkg05A ACT Ceilings Bldg C				
09C-519B Fabric/Matls+EquipPkg 05A ACT Ceilings Bldg B	20	20	14MAY10	11JUN10	20	-52	05C	Fabric/Matls+EquipPkg 05A ACT Ceilings Bldg B				
09C-518C Fabric/Matls+EquipPkg 05A ACT Ceilings Bldg C	20	20	14JUN10	12JUL10	50	-52	05C	Fabric/Matls+EquipPkg 05A ACT Ceilings Bldg C				
2 6345 Ceiling Grid - 2nd Flr	15	15	14MAY10	04JUN10	70	-17	05C	Ceiling Grid - 2nd Flr				
05C-518 Mobilize-Pkg 05A ACT Ceilings	0	0	21MAY10		61	-32	05C	Mobilize-Pkg 05A ACT Ceilings				

Interior Systems & Finishes - Aud	Instal Doors / Hardware - 1st Flr	Instal Doors / Hardware - Bldg C	Cost Summary: Drywall 08A	100% CD's Issued for-Pkg 06B Ceramic Tile	Bid Period - Ceramic Tile	Rec. Award - Ceramic Tile	Rev/App Award - Ceramic Tile	Award Contract - Ceramic Tile	Prep/Sub Submittals - Ceramic Tile	Rev/App Submittals - Ceramic Tile Submittals	Fabric/Materials - Ceramic Tile	Mobilize-06B Ceramic Tile	Instal Ceramic Tile Wall Base - 4th Flr	Instal Ceramic Tile Wall Base - 3rd Flr	Instal Ceramic Tile Wall Base - 2nd Flr	Instal Ceramic Tile - 1st Flr	Instal Gymnasium Ceramic Tile In Locker Rooms	Cost Summary: Ceramic Tile 06B	100% CD's Issued for-Pkg 05C ACT Ceilings	Bid Period - Pkg 05A ACT Ceilings	Rec. Award-Pkg 05A ACT Ceilings	Rev/App Award-Pkg 05C ACT Ceilings	Award Contract-Pkg 05A ACT Ceilings	Submit SDs Submittals-Pkg05A ACT Ceilings Bldg A	Submit SDs Submittals-Pkg05A ACT Ceilings Bldg B	Rev/App SDs Submittals-Pkg05A ACT Ceilings Bldg A	Rev/App SDs Submittals-Pkg05A ACT Ceilings Bldg B	Submit SDs Submittals-Pkg05A ACT Ceilings Bldg C	Fabric/Matls+EquipPkg 05A ACT Ceilings Bldg A	Rev/App SDs Submittals-Pkg05A ACT Ceilings Bldg C	Fabric/Matls+EquipPkg 05A ACT Ceilings Bldg B	Fabric/Matls+EquipPkg 05A ACT Ceilings Bldg C	Ceiling Grid - 2nd Flr	Mobilize-Pkg 05A ACT Ceilings
-----------------------------------	-----------------------------------	----------------------------------	---------------------------	---	---------------------------	---------------------------	------------------------------	-------------------------------	------------------------------------	--	---------------------------------	---------------------------	---	---	---	-------------------------------	---	--------------------------------	---	-----------------------------------	---------------------------------	------------------------------------	-------------------------------------	--	--	---	---	--	---	---	---	---	------------------------	-------------------------------

Blk: 100%	25APR10
Finch Color	15SEP11
Dist: 100%	15JAN10
Room Color	22JUN10 16285

	Early Bar
	Progress Bar
	Critical Activity

GILBANE BUILDING COMPANY  
WORCESTER NORTH HIGH SCHOOL (W116)  
BID PACKAGE - CURRENT WORK



© Primavera Systems, Inc.

Activity ID	Description	Start	End	Start Date	End Date	Duration	Early Start	Early End	Early Duration	Activity Type	Notes
1-5385	Ceiling Grid - 1st Flr	10	10	21MAY10	04JUN10	14	-32	09C			■ Ceiling Grid - 1st Flr
4732K	Ceiling Grid - Kitchen/Caf	10	10	07JUN10	18JUN10	11	-32	09C			■ Ceiling Grid - Kitchen/Caf
3-5385	Ceiling Grid - 3rd Flr	15	15	14JUN10	02JUL10	18	-17	09C			■ Ceiling Grid - 3rd Flr
1-5402	Ceiling Tile - 1st Flr	5	6	29JUN10	05JUL10	6	-32	09C			■ Ceiling Tile - 1st Flr
4424C	Hang Ceiling Panels - Auditorium	10	10	18JUN10	29JUN10	11	-19	09C			■ Hang Ceiling Panels - Auditorium
2-5402	Ceiling Tile - 2nd Flr	10	10	19JUL10	28JUL10	9	-17	09C			■ Ceiling Tile - 2nd Flr
4-5385	Ceiling Grid - 4th Flr	15	15	13JUL10	02AUG10	19	-17	09C			■ Ceiling Grid - 4th Flr
3-5402	Ceiling Tile - 3rd Flr	10	10	10AUG10	23AUG10	13	-17	09C			■ Ceiling Tile - 3rd Flr
4530C	Ceiling Grid - Locker Area	7	7	20AUG10	30AUG10	10	33	09C			■ Ceiling Grid - Locker Area
4-5402	Ceiling Tile - 4th Flr	10	10	06SEP10	21SEP10	15	-17	09C			■ Ceiling Tile - 4th Flr
5385C	Ceiling Grid - Bldg C	15	15	06SEP10	28SEP10	13	-33	09C			■ Ceiling Grid - Bldg C
4530C	Ceiling Tiles - Locker Area	3	3	10SEP10	14SEP10	4	-33	09C			■ Ceiling Tiles - Locker Area
4446C	Wall Panels - Auditorium	10	10	22OCT10	06NOV10	15	-19	09C			■ Wall Panels - Auditorium
5402C	Ceiling Tile - Bldg C	10	10	08NOV10	18NOV10	9	-34	09C			■ Ceiling Tile - Bldg C
4782K	Ceiling Tile - Kitchen/Caf	7	7	22DEC10	03JAN11	6	-17	09C			■ Ceiling Tile - Kitchen/Caf
09D-COST	Cost Summary: Acoustical Ceilings 09D	125*	125*	21MAY10	16NOV10	255	-33	09C			■ Cost Summary: Acoustical Ceilings 09D
<b>E-CARPETING</b>											
09D-500	100% CD's issued for -Pkg 09D Carpeting	0	0		01FEB10	182	-83	09D			◆ 100% CD's issued for -Pkg 09D Carpeting
09D-506	Reprc on final A Rec Award-Carpeting	10	10	02FEB10	16FEB10	14	-35	09D			■ Reprc on final A Rec Award-Carpeting
09D-508	RevApp Award-Carpeting	3	3	10FEB10	18FEB10	8	-35	09D			■ RevApp Award-Carpeting
09D-510	Award Contract-Carpeting	3	3	19FEB10	28FEB10	9	-35	09D			■ Award Contract-Carpeting
09D-512	Submit SD's Carpet Submittals - Bldg	15	15	24FEB10	16MAR10	21	-35	09D			■ Submit SD's Carpet Submittals - Bldg
09D-514	RevApp SD's Carpet Submittals - Bldg	15	15	17MAR10	06APR10	20	-35	09D			■ RevApp SD's Carpet Submittals - Bldg
09D-516	Fab/Del Carpet Materials-Equip-Bldg	20	20	07APR10	04MAY10	27	-35	09D			■ Fab/Del Carpet Materials-Equip-Bldg
09D-518	Mobilize-09D Carpeting	0	0	23DEC10		23	17	09D			◆ Mobilize-09D Carpeting
4903AB	Instal Carpeting - Bldg A/B	10	10	23DEC10	07JAN11	14	-17	09D			■ Instal Carpeting - Bldg A/B
4800C	Instal Carpeting - Bldg C	10	10	17JAN11	28JAN11	11	-17	09D			■ Instal Carpeting - Bldg C
09D-COST	Cost Summary: Carpeting 09D	25*	25*	23DEC10	28JAN11	6	-17	09D			■ Cost Summary: Carpeting 09D
<b>E-RESILIENT FLOORING (ESE)</b>											
09E-500	100% CD's issued for -Pkg 09E Resilient Floors	0	0		01FEB10	75	-83	09E			◆ 100% CD's issued for -Pkg 09E Resilient Floors
09E-504	Bid Period - Resilient Flooring	15	15	02FEB10	22FEB10	19	-52	09E			■ Bid Period - Resilient Flooring
09E-506	Rec. Award - Resilient Flooring	7	7	23FEB10	06MAR10	13	-52	09E			■ Rec. Award - Resilient Flooring
09E-508	RevApp Award - Resilient Flooring	3	3	04MAR10	08MAR10	4	-52	09E			■ RevApp Award - Resilient Flooring
09E-510	Award Contract - Resilient Flooring	3	3	09MAR10	11MAR10	2	-52	09E			■ Award Contract - Resilient Flooring
09E-512	Submit SD's Submittals - Resilient Flooring	15	15	12MAR10	01APR10	19	-52	09E			■ Submit SD's Submittals - Resilient Flooring
09E-514	RevApp SD's Submittals - Resilient Flooring	15	15	02APR10	22APR10	20	-52	09E			■ RevApp SD's Submittals - Resilient Flooring
09E-516	Fab/Del Materials & Equip - Resilient Flooring	20	20	23APR10	20MAY10	27	-52	09E			■ Fab/Del Materials & Equip - Resilient Flooring
09E-518	Mobilize-09E Resilient Flooring	0	0	08SEP10		8	-17	09E			◆ Mobilize-09E Resilient Flooring
Start Date	25APR10	Early Bar	WHS	Sheet 00121			<b>GILBANE BUILDING COMPANY</b> <b>WORCESTER NORTH HIGH SCHOOL (WHS)</b> <b>BID PACKAGE - CURRENT WORK</b>				File 09E-518.rvt 11/17/10 11:47 AM 11/17/10 11:47 AM



Activity	Start	End	Duration	Start	End	Duration	Start	End	Duration	Start	End	Duration
4-6420	Flooring - 4th Flr	15	15	08SEP10	20SEP10	0	-17	08E				
3-6420	Flooring - 3rd Flr	16	16	28SEP10	18OCT10	0	-17	08E				
2-6420	Flooring - 2nd Flr	15	15	20OCT10	09NOV10	0	-17	08E				
54900	Flooring - Bldg C	20	20	03NOV10	01DEC10	10	+33	08E				
1-6420	Flooring - 1st Flr	10	10	10NOV10	23NOV10	0	-17	08E				
4762K	Flooring - Kitchen/Caf	0	10	24NOV10	08DEC10	18	-17	08E				
09E-COST	Cost Summary: Res Ident Flooring 08E	65	65	08SEP10	08DEC10	18	11	08E				
<b>E-WOOD ATHLETIC FLOORING</b>												
02F-530	100% CD's Issued for Pkg 09F Wood Athletic Floors	0	0		01FEB10	135	-63	09F				
09F-533	Prep Scope-Pkg 09F Wood Athletic Flooring	18	2	20NOV08A	18JAN10	145	-37	09F				
09F-534	3rd Period -Pkg 09F Wood Athletic Flooring	18	18	02FEB10	22FEB10	135	-47	09F				
09F-538	Rec. Award-Pkg 09F Wood Athletic Flooring	7	7	23FEB10	03MAR10	135	-47	09F				
09F-538	RawApp Award-Pkg 09F Wood Athletic Flooring	3	3	04MAR10	08MAR10	135	-47	09F				
09F-540	Award Contract-Pkg 09F Wood Athletic Flooring	3	3	09MAR10	11MAR10	135	-47	09F				
09F-512C	Submit SD's Submittals Pkg 09F Wood Ath - Bldg C	15	15	12MAR10	01APR10	135	-47	09F				
09F-514C	RawApp SD's Submittals Pkg 09F Wood Ath - Bldg C	15	16	02APR10	02APR10	135	-47	09F				
09F-516C	Fab/Del Materials Pkg 09F Wood Athletic Fl Bldg C	30	30	23APR10	04JUN10	135	-47	09F				
09F-516	Mobilize-Pkg 09F Wood Athletic Flooring	0	0	22SEP10			62	-33	09F			
54400	Instal Gymnasium Flooring	20	20	22SEP10	15OCT10		93	09F				
09F-COST	Cost Summary: Wood Athletic Flooring 09F	20	20	22SEP10	15OCT10		93	09F				
<b>E-EPOXY FLOORING</b>												
09G-500	100% CD's Issued for Pkg 09G Epoxy Floors	0	0		01FEB10	150	-63	09G				
09G-504	Re-Bid Period - Epoxy Flooring	15	15	02FEB10	22FEB10	150	-47	09G				
09G-506	Rec. Award-Epoxy Flooring	7	7	23FEB10	03MAR10	150	-47	09G				
09G-508	RawApp Award-Epoxy Flooring	3	3	04MAR10	08MAR10	150	-47	09G				
09G-510	Award Contract-Epoxy Flooring	3	3	09MAR10	11MAR10	150	-47	09G				
09G-512A	Submit SD's Epoxy Floor Submittals - Bldg A	15	15	12MAR10	01APR10	150	-47	09G				
09G-514A	RawApp SD's Epoxy Floor Submittals - Bldg A	15	16	02APR10	02APR10	150	-47	09G				
09G-516A	Fab/Del Epoxy Floor Materials+Equip Bldg A	20	20	23APR10	24JUN10	150	-47	09G				
09G-518	Mobilize-Epoxy Flooring	0	0	26JUN10			104	-32	09G			
4760	Epoxy Flooring - Bldg A Flr 1	10	10	25JUN10	13JUL10	301	32	09G				
4750K	Instal Epoxy Floor - Kitchen/Caf	10	10	15AUG10	27AUG10		83	-31	09G			
45400	Epoxy Flooring - Locker Area	20	20	18SEP10	12OCT10		53	-58	09G			
09G-COST	Cost Summary: Epoxy Flooring 09G	74	74	23JUN10	12OCT10		237	-58	09G			
<b>E-PAINT - WALLCOVERING (P&amp;P)</b>												
09H-500	100% CD's Issued for Pkg 09H Paint-Wall Coverings	0	0		01FEB10	42	-63	09H				
09H-504	Re-Bid Period - Paint	15	15	15JAN10	08FEB10	42	-42	09H				
09H-506	Rec. Award - Paint	10	10	08FEB10	22FEB10	42	-43	09H				
<div style="display: flex; justify-content: space-between;"> <div style="width: 20%;"> <p>Start Date: 25MRF00</p> <p>Finish Date: 10SEP10</p> <p>Start Date: 15JAN10</p> <p>Finish Date: 25JAN10 14:28</p> </div> <div style="width: 20%;"> <p>Early Bar</p> <p>Progress Bar</p> <p>Critical Activity</p> </div> <div style="width: 40%; text-align: center;"> <p>GILBANE BUILDING COMPANY</p> <p><b>WORCESTER NORTH HIGH SCHOOL (W18)</b></p> <p>BID PACKAGE - CURRENT WORK</p> </div> <div style="width: 20%; text-align: right;"> <p>Sheet: 1 of 21</p> </div> </div>												

Activity	Start	End	Duration	Early Start	Early Finish	Duration	Early Start	Early Finish	Duration	Activity
09H-508 Rev/App Award - Paint	3	3	23-E810	26-E810	42	-4E	09H			Rev/App Award - Paint
09H-510 Award Contract - Paint	3	3	23-FEB10	02-MAR10	42	-4E	09H			Award Contract - Paint
09H-512 Prep/Sub Submittals - Paint	15	15	02-MAR10	23-MAR10	42	-4E	09H			Prep/Sub Submittals - Paint
09H-514 Rev/App Submittals - Paint	15	15	24-MAR10	13-APR10	42	-4E	09H			Rev/App Submittals - Paint
09H-516A Fin/Del Materials - Paint	10	10	14-APR10	27-APR10	42	-4E	09H			Fin/Del Materials - Paint
2-5365 Prime Paint + First Coat Paint - 2nd Flr	6	16	30-APR10	20-MAY10	70	-17	09H			Prime Paint + First Coat Paint - 2nd Flr
09H-518 Mobilize-Painter	0	0	03-MAY10*		0	-4	09H			Mobilize-Painter
1-6263 Prime Paint + First Coat Paint - 1st Flr	8	8	03-MAY10	12-MAY10	99	28	09H			Prime Paint + First Coat Paint - 1st Flr
4736R Prime Paint + First Coat Paint - Kitchen/Caf	7	7	13-MAY10	21-MAY10	151	-24	09H			Prime Paint + First Coat Paint - Kitchen/Caf
4418C Paint Ceiling/MEPs - Auditorium	10	10	26-MAY10	04-JUN10	22	0	09H			Paint Ceiling/MEPs - Auditorium
3-5365 Prime Paint + First Coat Paint - 3rd Flr	6	15	28-MAY10	18-JUN10	35	-17	09H			Prime Paint + First Coat Paint - 3rd Flr
4810C Paint CMU Interior Walls Col 17-22 - Locker Area	8	8	14-JUN10	18-JUN10	90	23	09H			Paint CMU Interior Walls Col.17-22 - Locker Area
4-936A Prime Paint + First Coat Paint - 4th Flr	15	15	28-JUN10	18-JUL10	0	-17	09H			Prime Paint + First Coat Paint - 4th Flr
5-548D Paint Steel Trusses And Ceiling @ High Area	10	10	04-AUG10	17-AUG10	79	-14	09H			Paint Steel Trusses And Ceiling @ High Area
4528C Paint CMU Walls + GYP Ceilings - Locker Area	10	10	08-AUG10	19-ALG10	50	-23	09H			Paint CMU Walls + GYP Ceilings - Locker Area
5365C Prime Paint + First Coat Paint - Bldg C	15	15	24-AUG10	14-SEP10	10	-35	09H			Prime Paint + First Coat Paint - Bldg C
4-5425 Finish Paint - 4th Flr	10	10	08-OCT10	19-OCT10	20	37	09H			Finish Paint - 4th Flr
3-5425 Finish Paint - 3rd Flr	10	10	27-OCT10	08-NOV10	20	37	09H			Finish Paint - 3rd Flr
2-5426 Finish Paint - 2nd Flr	10	10	17-NOV10	01-DEC10	20	-17	09H			Finish Paint - 2nd Flr
1-5425 Finish Paint - 1st Flr	10	10	08-DEC10	22-DEC10	20	-17	09H			Finish Paint - 1st Flr
5425C Finish Paint - Bldg C	5	5	13-JAN11	14-JAN11	0	-17	09H			Finish Paint - Bldg C
09H-COST Cost Summary: Painting 09H	179*	179*	03-MAY10	14-JAN11	0	37	09H			Cost Summary: Painting 09H
<b>5- GEN'L TRADES OPER PART/TOILET PART/ACCESS FTL</b>										
09J-500 100% CDs Issued for Pkg 05J Gen'l Trades	0	0		01-FEB10	107	-E5	09J			100% CDs Issued for Pkg 05J Gen'l Trades
09J-506 Re-Price & Rec. Award - Gen'l Trades	10	10	02-FEB10	15-FEB10	107	-40	09J			Re-Price & Rec. Award - Gen'l Trades
09J-508 Rev/App Award - Gen'l Trades	3	3	18-FEB10	18-FEB10	107	-40	09J			Rev/App Award - Gen'l Trades
09J-510 Award Contract - Gen'l Trades	3	3	19-E810	23-E810	107	-40	09J			Award Contract - Gen'l Trades
10A-512 Submit SD's Specialties Submittals - Lockers	16	15	24-FEB10	03-MAR10	107	35	09J			Submit SD's Specialties Submittals - Lockers
05J-512D Submit SD's Submittals - White/Task Boards + Acc	15	15	24-FEB10	03-MAR10	142	-40	09J			Submit SD's Submittals - White/Task Boards + Acc
09J-512E Submit SD's Specialties Submittals - Toilet Part	15	15	24-FEB10	03-MAR10	142	-40	09J			Submit SD's Specialties Submittals - Toilet Part
10A-512C Submit SD's Submittals - Bleachers	15	15	24-FEB10	03-MAR10	147	-26	09J			Submit SD's Submittals - Bleachers
09J-512 Prep/Sub Submittals - Operable Partitions	16	15	24-FEB10	03-MAR10	329	-40	09J			Prep/Sub Submittals - Operable Partitions
09J-512B Prep/Sub Submittals - Skyfold Partitions	16	15	24-E810	03-MAR10	329	-40	09J			Prep/Sub Submittals - Skyfold Partitions
09J-512I Prep/Sub Submittals - Gym Divider Curtains	16	15	24-FEB10	03-MAR10	373	-40	09J			Prep/Sub Submittals - Gym Divider Curtains
05J-512G Prep/Sub Submittals - Blinds and Drapes	15	15	24-FEB10	03-MAR10	328	-40	09J			Prep/Sub Submittals - Blinds and Drapes
09J-512J Prep/Sub Submittals - Toile Access	15	15	24-FEB10	03-MAR10	339	-40	09J			Prep/Sub Submittals - Toilet Access
09J-512H Prep/Sub Submittals - Appliances	15	15	24-FEB10	03-MAR10	349	-40	09J			Prep/Sub Submittals - Appliances
12B-512C Submit SD's+Sample Pkg 12B Athletic Equipment	20	20	24-FEB10	22-MAR10	142	21	09J			Submit SD's+Sample Pkg 12B Athletic Equipment

Blk. Date	25/1/09
Finish Date	18/E/11
Close Date	15/4/10
Plan Date	22/M/10/1429

09H	09J	09K	09L	09M	09N	09O	09P	09Q	09R	09S	09T	09U	09V	09W	09X	09Y	09Z
█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█
█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█	█

W115 21st 12 of 21

**GILBANE BUILDING COMPANY**

**WORCESTER NORTH HIGH SCHOOL (W115)**

**BID PACKAGE - CURRENT WORK**



REV	NO	DATE	BY	CHKD

Activity	Start Date	End Date	Duration	Start Time	End Time	Activity	Start Date	End Date	Duration	Start Time	End Time
10A-514 RevApp SD's Specialties Submittals - Lockers	15	15	17MAR10	06APR10	107	-35	OSJ				
09J-514B RevApp SD's Submittals - White/Tack Boards + Acc	15	15	17MAR10	06APR10	142	-40	OSJ				
05J-514B RevApp SD's Specialties Submittals - Toilet Par	15	15	17MAR10	06APR10	142	-40	OSJ				
10A-514C RevApp SD's S/Lyn Itals - Bleachers	15	15	17MAR10	06APR10	147	-35	OSJ				
09J-514 RevApp Submittals - Operable Partitions	15	15	17MAR10	06APR10	329	-40	OSJ				
05J-514E RevApp Submittals - Skylold Partitions	15	15	17MAR10	06APR10	529	-40	OSJ				
09J-514F RevApp Submittals - Gym Divider Curtain	15	15	17MAR10	06APR10	529	-40	OSJ				
09J-514G RevApp Submittals - Blinds and Drapes	15	15	17MAR10	06APR10	529	-40	OSJ				
09J-514 RevApp Submittals - Toilet Access	15	15	17MAR10	06APR10	529	-40	OSJ				
05J-514H RevApp Submittals - Appliances	15	15	17MAR10	06APR10	529	-40	OSJ				
12B-514C RevApp SD's Sample Pkg 12B Athletic Equipment	20	23	24MAR10	23APR10	142	-31	OSJ				
09J-516 Fab/Del Materials - Operable Partitions Supports	20	20	07APR10	04MAY10	349	-40	OSJ				
09J-516B Fab/Del Materials - Skylold Partitions Supports	20	20	07APR10	04MAY10	349	-40	OSJ				
09J-516H Fab/Del Materials - Appliances	20	20	07APR10	04MAY10	349	-40	OSJ				
09J-516 Rev/Del Materials - Toilet Access	20	20	07APR10	04MAY10	349	-40	OSJ				
08J-516A Fab/Del Materials - Operable Partitions	40	40	07APR10	02JUN10	323	-40	OSJ				
09J-516C Fab/Del Materials - Skylold Partitions	40	40	07APR10	02JUN10	323	-40	OSJ				
09J-516F Fab/Del Materials - Gym Divider Curtain	40	40	07APR10	02JUN10	323	-40	OSJ				
05J-516B Rev/Del Materials - Blinds and Drapes	40	40	07APR10	02JUN10	323	-40	OSJ				
10A-516A Fab/Del Specialties - Lockers	50	50	07APR10	16JUN10	107	-35	OSJ				
09J-516D Fab/Del Specialties - White/Tack Boards + Acc	50	50	07APR10	16JUN10	142	-40	OSJ				
09J-516E Fab/Del Specialties - Toilet Partitions	50	50	07APR10	16JUN10	142	-40	OSJ				
10A-516C Fab/Del Specialties - Bleachers	50	50	07APR10	16JUN10	147	-35	OSJ				
12B-516C Fab/Del Materials Pkg 12B Athletic Equipment	60	60	21APR10	16JUL10	142	-31	OSJ				
10A-516 Mobilize - Specialties	0	0	15SEP10		00	-33	OSJ				
12B-516 Mobilize - Pkg 12B Athletic Equipment	0	0	15SEP10		00	-240	OSJ				
5376C Install Gym Equipment, Back Board, Score Board	5	5	15SEP10	21SEP10	00	-30	OSJ				
4-545D White Boards, Tack Boards + Accessories 4th Flr	5	5	20OCT10	26OCT10	65	-17	OSJ				
5466C Install Bleacher Seating - Gym	10	10	23OCT10	02NOV10	80	-33	OSJ				
4-544U Install Lockers - 4th Floor	15	15	23OCT10	09NOV10	20	-17	OSJ				
4544C Toilet Partitions + Accessories - Locker Area	10	10	27OCT10	06NOV10	50	-33	OSJ				
3-545D White Boards, Tack Boards + Accessories 3rd Flr	5	5	09NOV10	19NOV10	45	-17	OSJ				
4646C Lockers - Locker Area	5	5	10NOV10	18NOV10	50	-33	OSJ				
3-544U Install Lockers - 3rd Floor	15	15	10NOV10	01DEC10	20	-17	OSJ				
4595C Locker Area Complete	5	0		16NOV10	30	-33	OSJ				
2-545D White Boards, Tack Boards + Accessories 2nd Flr	5	5	22DEC10	06DEC10	35	-17	OSJ				
2-544U Install Lockers - 2nd Floor	15	15	30DEC10	20DEC10	20	-17	OSJ				
1-546D White Boards, Tack Boards + Accessories 1st Flr	5	5	28DEC10	30DEC10	25	-17	OSJ				

Start Date: 16SEP10  
 End Date: 16JAN11  
 Duration: 222DAYS 42H

Activity Per  
 Progress Bar  
 Critical Activity

**GILBANE BUILDING COMPANY**  
**WORCESTER NORTH HIGH SCHOOL (WNHS)**  
**BID PACKAGE - CURRENT WORK**




Activity	Start Date	End Date	Duration	Start Time	End Time

Item	Description	QTY	UNIT	START DATE	END DATE	START TIME	END TIME	Notes
1-540	Install Lockers - Basement Locker Rm	10	LC	20DEC10	07JAN11	20	17:09J	Install Lockers - Basement Locker Rm
<b>F-LOCKERS</b>								
10A-COST	Cost Summary: Specialbas 10A	55*	55*	20OCT10	07JAN11	20	-17	10A
<b>G-SIGNAGE</b>								
10B-500	100% CD's Issued for Pkg 10B Signage	0	0		07FEB10	126	-63	10B
10B-503	Prep Scope-Pkg 10B Signage	9	9	02FEB10*	12FEB10	126	-21	10B
10B-504	Bid Period - Signage	20	20	16FEB10	23MAR10	126	-21	10B
10B-506	Rec Award - Signage	7	7	16MAR10	23MAR10	126	-21	10B
10B-508	Rev/App Award - Signage	3	3	24MAR10	25MAR10	126	-21	10B
10B-510	Award Contract - Signage	3	3	23MAR10	31MAR10	126	-21	10B
10B-512	Submit SD's Submittals - Signage	15	5	01APR10	21APR10	126	-21	10B
10B-514	Rev/App SD's Submittals - Signage	25	25	22APR10	20MAY10	126	-21	10B
10B-516A	Fab/Del Materials - Signage Bldg A/B	30	30	27MAY10	06JUL10	126	-21	10B
10B-516C	Fab/Del Materials - Signage Bldg C	20	20	27MAY10	03JUL10	131	-21	10B
10B-518	Mobilize-Pkg 10B Signage	0	0	20OCT10		55	-17	10B
4-4550AB	Install Signage - Flr 4	5	5	20OCT10	26OCT10	58	-17	10B
3-4550AB	Install Signage - Flr 3	5	5	10NOV10	16NOV10	44	-17	10B
2-4550AB	Install Signage - Flr 2	5	5	02DEC10	08DEC10	35	-17	10B
1-4550AB	Install Signage - Flr 1	5	5	22DEC10	30DEC10	25	-17	10B
4550C	Install Signage - Bldg C	10	10	17JAN11	23JAN11	0	-17	10B
10B-COST	Cost Summary: Signage 10B	70*	70*	20OCT10	23JAN11	0	-17	10B
<b>H-KITCHEN EQUIPMENT</b>								
11A-516A	Inst/Del Materials-Kitchen Equip-Bldg A	80	80	15JAN10	06MAY10	89	-21	11A
11A-518	Mobilize Pkg 11A Kitchen Equipment	0	0	07MAY10		99	-21	11A
4718K	Install Coolers/Freezers - Kitchen/Caf	27	27	07MAY10	16JUN10	89	-21	11A
4720	Install Kitchen Equipment - Kitchen/Caf	20	20	09DEC10	07JAN11	18	-17	11A
11A-COST	Cost Summary: Kitchen Equipment 11A	20*	20*	09DEC10	07JAN11	18	-17	11A
<b>I-LABORATORY EQUIPMENT</b>								
11B-512A	Prep/Sub SD-Data Lab Equip-Bldg A/B	15	5	15JAN10	04FEB10	35	-48	11B
11B-514A	Rev/App SD's Submittals-Lab Equip-Bldg A/B	20	20	01LUB10	04MAR10	35	-48	11B
11B-516A	Fab/Del Materials - Lab Equip Bldg A/B	46	46	06MAR10	06MAY10	145	-48	11B
11B-518	Mobilize-Pkg 11B Lab Equipment	0	0	13NOV10		15	-17	11B
4720	Install Lab Equipment	20	20	13NOV10	30DEC10	15	-17	11B
11B-COST	Cost Summary: Lab Equipment 11B	20*	20*	13NOV10	30DEC10	15	-17	11B
<b>J-Stage Equipment / Rigging</b>								
11C-500	100% CD's Issued for Pkg 11C Stage Equip / Rig	0	0		01FEB10	16	-63	11C
11C-502	Prep Scope-Pkg 11C Stage Equipment / Rigging	0	5	30NOV10A	22JAN10	16	0	11C


Start Date	2014/03/25	Legend	Early Bar	Scale	1:100
Finish Date	10/01/11	Progress Bar			
Print Date	10/01/11	Critical Activity			
Run Date	10/01/11				

<b>GILBANE BUILDING COMPANY</b> <b>WORCESTER NORTH HIGH SCHOOL (WNHS)</b> <b>BID PACKAGE - CURRENT WORK</b>		
J/C 10/01/11 A/P: L/S		

© Primavera Systems, Inc.

110-504	Bid Period - 110 Stage Equip / Rigging	17	17	02FEB10	24FEB10	10	-44	110	■ Bid Period - 110 Stage Equip / Rigging																																								
110-506	Rec. Award - 110 Stage Equip / Rigging	7	7	25FEB10	05MAR10	10	-44	110	■ Rec. Award - 110 Stage Equip / Rigging																																								
110-508	RevApp Award - 110 Stage Equip / Rigging	3	3	09MAR10	13MAR10	10	-44	110	■ RevApp Award - 110 Stage Equip / Rigging																																								
110-510	Award Contract - 110 Stage Equip / Rigging	3	3	11MAR10	15MAR10	10	-44	110	■ Award Contract - 110 Stage Equip / Rigging																																								
110-512	Submit SD's Submittals - Stage Equip / Rigging	15	15	16MAR10	05APR10	10	-44	110	■ Submit SD's Submittals - Stage Equip / Rigging																																								
110-514	RevApp SD's Submittals - Stage Equip / Rigging	25	25	06APR10	10MAY10	10	-44	110	■ RevApp SD's Submittals - Stage Equip / Rigging																																								
110-516	Fab/Del Materials - Stage Equip / Rigging	30	30	11MAY10	22JUN10	10	-44	110	■ Fab/Del Materials - Stage Equip / Rigging																																								
110-518	Mobilize-Pkg 110 Stage Equip / Rigging	0	0	02JUL10		3	261	110	◆ Mobilize-Pkg 110 Stage Equip / Rigging																																								
<b>Theatre Lighting</b>																																																	
110-500	100% CD's Issued for Pkg 110 Theatre Lighting	0	0		01FEB10	7	63	110	◆ 100% CD's Issued for Pkg 110 Theatre Lighting																																								
110-502	Prep Scope Pkg 110 Theatre Lighting	5	1	30NOV09A	15JAN10	3	-23	110	■ Prep Scope Pkg 110 Theatre Lighting																																								
110-504	Bid Period - 110 Theatre Lighting	15	15	18JAN10	05FEB10	3	-31	110	■ Bid Period - 110 Theatre Lighting																																								
110-506	Rec. Award - 110 Theatre Lighting	7	7	06FEB10	18FEB10	3	-31	110	■ Rec. Award - 110 Theatre Lighting																																								
110-508	RevApp Award - 110 Theatre Lighting	3	3	17FEB10	19FEB10	3	21	110	■ RevApp Award - 110 Theatre Lighting																																								
110-510	Award Contract - 110 Theatre Lighting	3	3	22FEB10	24FEB10	3	-21	110	■ Award Contract - 110 Theatre Lighting																																								
110-512	Submit SD's Submittals - Theatre Lighting	16	15	29FEB10	17MAR10	3	-21	110	■ Submit SD's Submittals - Theatre Lighting																																								
110-514	RevApp SD's Submittals - Theatre Lighting	25	25	18MAR10	21APR10	3	-21	110	■ RevApp SD's Submittals - Theatre Lighting																																								
110-516	Fab/Del Materials - Theatre Lighting	60	60	22APR10	04JUL10	3	21	110	■ Fab/Del Materials - Theatre Lighting																																								
110-518	Mobilize-Pkg 110 Theatre Lighting	0	0	02JUL10		3	251	110	◆ Mobilize-Pkg 110 Theatre Lighting																																								
<b>THEATRE SEATING</b>																																																	
12A-500	100% CD's Issued for Pkg 12A Theater Seating	0	0		01FEB10	105	-63	12A	◆ 100% CD's Issued for Pkg 12A Theater Seating																																								
12A-502	Re Write - Scope Pkg 12A Theater Seating	5	5	02FEB10	08FEB10	105	0	12A	■ Re Write - Scope Pkg 12A Theater Seating																																								
12A-504	Bid Period - Pkg 12A Theater Seating	15	15	05FEB10	07MAR10	105	-17	12A	■ Bid Period - Pkg 12A Theater Seating																																								
12A-506	Rec. Award - Pkg 12A Theater Seating	7	7	02MAR10	10MAR10	105	-47	12A	■ Rec. Award - Pkg 12A Theater Seating																																								
12A-508	RevApp Award - Pkg 12A Theater Seating	3	3	11MAR10	15MAR10	105	-47	12A	■ RevApp Award - Pkg 12A Theater Seating																																								
12A-510	Award Contract - Pkg 12A Theater Seating	3	3	16MAR10	19MAR10	105	47	12A	■ Award Contract - Pkg 12A Theater Seating																																								
12A-512	Submit SD's Sample Pkg 12A Theater Seating Bldg C	20	20	16MAR10	15APR10	105	-47	12A	■ Submit SD's Sample Pkg 12A Theater Seating Bldg C																																								
12A-514	RevApp SD's Sample Pkg 12A Theater Seating Bldg C	20	20	16APR10	13MAY10	105	-47	12A	■ RevApp SD's Sample Pkg 12A Theater Seating Bldg C																																								
12A-516	Fab/Del Materials Pkg 12A Theater Seating Bldg C	60	60	14MAY10	06AUG10	105	-47	12A	■ Fab/Del Materials Pkg 12A Theater Seating Bldg C																																								
12A-518	Mobilize-Pkg 12A Theater Seating	0	0	05JAN11		3	19	12A	◆ Mobilize-Pkg 12A Theater Seating																																								
4450C	Seating - Auditorium	15	15	05JAN11	25JAN11	3	-10	12A	■ Seating - Auditorium																																								
12A-COST	Cost Summary: Theater Seating 12A	16	15	05JAN11	25JAN11	3	-10	12A	■ Cost Summary: Theater Seating 12A																																								
<b>D-ELEVATORS (FSE)</b>																																																	
1772C	RevApp SD Elevator C	20	8	08NOV09A	22JAN10	79	-20	14A	■ RevApp SD Elevator C																																								
14A-13A	PropHc-Sub SD+Data 14A-Elev. A	20	5	01DEC09A	21JAN10	130	0	14A	■ PropHc-Sub SD+Data 14A-Elev. A																																								
1773A	RevApp SD Elevator A	20	20	22JAN10	18FEB10	130	49	14A	■ RevApp SD Elevator A																																								
14A-516	Fab/Del v. Elevator A	60	60	22JUN10	31AUG10	44	0	14A	■ Fab/Del v. Elevator A																																								
1750C	Fab/Del v. Elevator C	60	60	22JUN10	31AUG10	44	0	14A	■ Fab/Del v. Elevator C																																								
<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:15%;">Start Date</td> <td style="width:15%;">01APR10</td> <td style="width:15%;"></td> <td style="width:15%;"></td> <td style="width:15%;"></td> <td style="width:15%;"></td> <td style="width:15%;"></td> <td style="width:15%;"></td> <td style="width:15%;"></td> <td style="width:15%;"></td> </tr> <tr> <td>Finish Date</td> <td>15SEP11</td> <td>■</td> <td>■</td> <td>■</td> <td>■</td> <td>■</td> <td>■</td> <td>■</td> <td>■</td> </tr> <tr> <td>Del. Date</td> <td>15JAN10</td> <td>■</td> <td>■</td> <td>■</td> <td>■</td> <td>■</td> <td>■</td> <td>■</td> <td>■</td> </tr> <tr> <td>Run Date</td> <td>22JAN11:123</td> <td>■</td> <td>■</td> <td>■</td> <td>■</td> <td>■</td> <td>■</td> <td>■</td> <td>■</td> </tr> </table>										Start Date	01APR10									Finish Date	15SEP11	■	■	■	■	■	■	■	■	Del. Date	15JAN10	■	■	■	■	■	■	■	■	Run Date	22JAN11:123	■	■	■	■	■	■	■	■
Start Date	01APR10																																																
Finish Date	15SEP11	■	■	■	■	■	■	■	■																																								
Del. Date	15JAN10	■	■	■	■	■	■	■	■																																								
Run Date	22JAN11:123	■	■	■	■	■	■	■	■																																								
<p><b>GILBANE BUILDING COMPANY</b></p> <p><b>WORCESTER NORTH HIGH SCHOOL (W116)</b></p> <p><b>BID PACKAGE - CURRENT WORK</b></p>																																																	
© Primavera Systems, Inc.																																																	

Activity ID	Activity Name	Start	End	Activity	Start	End	Activity	Start	End	Activity	Start	End	Activity	Start	End	Activity	Start	End	Activity							
14A-035	Fab/Del Wheel Chair Lift C	40	40	07JUL10	31AUG10	84	0	14A																		
1760	Mobile Elevators	0	0	18SEP10			37	-7	4A																	
8075A	Instal Elevator A	30	50	18SEP10	22OCT10	37	-7	4A																		
4056A	Final Inspect Elevator A	10	10	26OCT10	05NOV10	87	-7	4A																		
5116C	Install Elevator C	20	20	25OCT10	19NOV10	37	-7	4A																		
8180C	Instal WheelChair Lift C	10	10	22NOV10	02DEC10	27	-7	4A																		
4188C	Final Inspect Elevator C	10	10	22NOV10	02DEC10	77	-7	4A																		
14A-COST	Cost Summary: Elevators 14A	60	60	18SEP10	02DEC10	37	-7	4A																		
<b>D-ELEVATOR PROTECTION</b>																										
4716K	R.O.H. Sprinkler - Kitchen/Caf	6	6	09NOV09A	18FEB10	204	-42	16A																		
2-5315AB	R.O.H. Sprinkler 2nd Flr	20	10	30NOV09A	20FEB10	38	-29	16A																		
3-5316AB	R.O.H. Sprinkler 3rd Flr	20	20	15MAR10	09APR10	24	-40	16A																		
4-5315AB	R.O.H. Sprinkler 4th Flr	20	20	19APR10	07MAY10	24	-40	16A																		
5316C	R.O.H. Sprinkler - Bldg C	20	20	17MAY10	14JUN10	46	-44	16A																		
1-5395AB	Spk Heads - 1st Flr	7	7	07JUN10	15JUN10	100	-32	16A																		
2-5395AB	Spk Heads - 2nd Flr	10	10	07JUN10	16JUN10	80	-17	16A																		
4428C	Adjust Ceiling Sprinkler Heads - Auditorium	5	5	21JUN10	25JUN10	22	0	16A																		
3-5396AB	Spk Heads - 3rd Flr	10	10	06JUL10	19JUL10	45	-17	16A																		
5475C	R.I. Sprinkler in Roof Framing @ High Area	10	10	21JUL10	09AUG10	79	-41	16A																		
4-5396AB	Spk Heads - 4th Flr	10	10	09AUG10	16AUG10	10	-17	16A																		
4538C	Ceiling Sprinkler Heads - Locker Area	7	7	31AUG10	09SEP10	20	+33	16A																		
5389C	Spk Heads - Bldg C	10	10	29SEP10	12OCT10	20	-33	16A																		
4754K	Spk Heads - Kitchen/Caf	3	3	03OCT10	19OCT10	26	-17	16A																		
6445	City Inspection Fire Alarm/Life Safety	6	5	29DEC10	30DEC10	142	-33	16A																		
15A-COST	Cost Summary: Fire Protection 15A	250*	160*	12OCT09A	12OCT10	20	-33	16A																		
<b>D-PLUMBING (P&amp;S)</b>																										
15B-036	Fab/Del Acid Neutralizer	40	40	10MAY09A	11MAR10	160	-41	16B																		
15A-000	Fab/Del Plumbing Fixtures	20	20	11JUNY09A	11FEB10	220	-45	16B																		
15A-518C	Fab/Del Plumbing Materials - Bldg C	10	10	15JUN10	01FEB10	115	-5	16B																		
1-5322AB	R.O.H. Plumbing - 1st Flr	15	15	29SEP09A	04FEB10	25	-48	16B																		
4712K	R.O.H. Plumbing - Kitchen/Caf	5	5	09NOV09A	11FEB10	204	-42	16B																		
4714K	R.I. Plumb in Walls - Kitchen/Caf	10	10	04JAN10A	16FEB10	136	-40	16B																		
1-5335AB	R.I. Plumb in Walls - 1st Flr	8	5	27JAN10	02FEB10	29	-47	16B																		
2-5335AB	R.I. Plumb in Walls - 2nd Flr	15	15	11FEB10	13FEB10	24	-30	16B																		
1-5336AB	Test & Inspect in Wall MEP -1st Flr	8	3	03FEB10	05FEB10	29	-12	16B																		
2-5325AB	R.O.H. Plumbing 2nd Flr	20	20	09FEB10	04MAR10	26	-39	16B																		
4725K	Test & Inspect in Wall MEP - Kitchen/Caf	2	2	17FEB10	15FEB10	166	-40	16B																		
2-5352AB	Test & Inspect in Wall MEP -2nd Flr	8	5	22FEB10	25FEB10	24	-15	16B																		
Start Date	15MAY09	End Date	15MAY10	Run Date	12MAY10	<b>GILBANE BUILDING COMPANY</b> <b>WORCESTER NORTH HIGH SCHOOL (WNHS)</b> <b>BID PACKAGE - CURRENT WORK</b>				<table border="1"> <tr> <th>Task</th> <th>Start</th> <th>End</th> <th>Actual</th> <th>Open</th> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>		Task	Start	End	Actual	Open										
Task	Start	End	Actual	Open																						

3-5335AB	R.O.H. Plumb n Walls - 3rd Flr	15	15	23FEB10	18MAR10	25	-28	15B	R.O.H. Plumb n Walls - 3rd Flr
3-5335AR	R.O.H. Plumbing 3rd Flr	20	20	05MAR10	31APR10	25	-38	15B	R.O.H. Plumbing 3rd Flr
3-5335AB	Test & Inspect In Wall MEP - 3rd Flr	5	5	18MAR10	23MAR10	25	-28	15B	Test & Inspect In Wall MEP - 3rd Flr
4-5335AB	R.O.H. Plumb n Walls - 4th Flr	15	15	02APR10	22APR10	20	-34	15B	R.O.H. Plumb n Walls - 4th Flr
4-5325AB	R.O.H. Plumbing 4th Flr	20	20	02APR10	29APR10	25	-33	15B	R.O.H. Plumbing 4th Flr
4-5335AB	Test & Inspect In Wall MEP - 4th Flr	5	5	23APR10	29APR10	20	-34	15B	Test & Inspect In Wall MEP - 4th Flr
5325C	R.O.H. Plumbing - Reg C	20	20	10MAY10	07JUN10	48	-44	15B	R.O.H. Plumbing - Bldg C
4742K	Instal Rctng Lines - Kitchen/Caf	10	10	02JUN10	15JUN10	50	-3	15B	Instal Rctng Lines - Kitchen/Caf
5335C	R.O.H. Plumb n Walls - Bldg C	15	15	07JUN10	25JUN10	10	-33	15B	R.O.H. Plumb n Walls - Bldg C
4812C	Instal Acid Neutralizer - Locker Area	5	5	21JUN10	26JUN10	50	33	15B	Instal Acid Neutralizer - Locker Area
4520C	In-wall Plumbing Rough - Locker Area	20	20	21JUN10	19JUL10	60	-33	15B	In-wall Plumbing Rough - Locker Area
5335C	Test & Inspect In Wall MEP - Bldg C	5	5	15JUL10	19JUL10	10	-32	15B	Test & Inspect In Wall MEP - Bldg C
4542C	Plumbing Fixtures - Locker Area	10	10	19OCT10	26OCT10	50	-33	15B	Plumbing Fixtures - Locker Area
4-5415AB	Complete Pmp @ Millwork - 4th Flr	10	10	20OCT10	02NOV10	20	-7	15B	Complete Pmp @ Millwork - 4th Flr
3-5415AB	Complete Pmp @ Millwork - 3rd Flr	10	10	17NOV10	30DEC10	10	-17	15B	Complete Pmp @ Millwork - 3rd Flr
3-5415AB	Complete Pmp @ Millwork - 2nd Flr	10	10	02DEC10	20DEC10	5	-11	15B	Complete Pmp @ Millwork - 2nd Flr
1-5415AB	Complete Pmp @ Millwork - 1st Flr	10	10	23DEC10	07JAN11	5	-17	15B	Complete Pmp @ Millwork - 1st Flr
5415C	Complete Pmp @ Millwork - Bldg C	10	10	10JAN11	21JAN11	5	-17	15B	Complete Pmp @ Millwork - Bldg C
10B-COST	Cost Summary: Plumbing 15B	356*	260*	28SEP09A	21JAN11	5	-17	15B	Cost Summary: Plumbing 15B
<b>DW-HVAC (75315)</b>									
15C-546	Fab/Deliver MEP - Bldg A/B Flr 4	16	16	02OCT09A	28FEB10	20	-36	18C	Fab/Deliver MEP - Bldg A/B Flr 4
15C-546	Fab/Deliver Roof Equipment - 15C - HVAC	50	45	12OCT09A	13MAR10	30	-53	15C	Fab/Deliver Roof Equipment - 15C - HVAC
15C-576	Fab/Deliver VAV's / FCU - 15C - HVAC	47	26	19DEC09A	19FEB10	34	0	15C	Fab/Deliver VAV's / FCU - 15C - HVAC
15C-576	Fab/Deliver Cooling Tower - HVAC	50	50	15DEC09A	25MAR10	37	0	15C	Fab/Deliver Cooling Tower - HVAC
10C-622	Re-sub SD Chiller - 15C - HVAC	20	20	04JAN10A	11FEB10	32	0	15C	Re-sub SD Chiller - 15C - HVAC
15C-10-C1	MEP Coordination Dwg Bldg C - 15C-HVAC	40	2	15JAN10	18JAN10	53	15	15C	MEP Coordination Dwg Bldg C - 15C-HVAC
15C-260	Fab/Deliver MEP - Bldg A/B Flr 3	15	15	15JAN10	04FEB10	20	45	15C	Fab/Deliver MEP - Bldg A/B Flr 3
15C-554	Fab/Deliver Gas Fired Boilers	20	20	15JAN10	11FEB10	43	0	15C	Fab/Deliver Gas Fired Boilers
15C-555	Fab/Deliver Baseboard Heat	20	20	15JAN10	11FEB10	40	0	15C	Fab/Deliver Baseboard Heat
15C-555	Fab/Deliver Fin Tube Radiation	50	30	15JAN10	25FEB10	38	0	15C	Fab/Deliver Fin Tube Radiation
15C-550	Fab/Deliver RTU #1	70	70	18JAN10	22APR10	35	0	18C	Fab/Deliver RTU #1
15C-552	Fab/Deliver RTU - for Cafe/Aud Lib	70	70	15JAN10	22APR10	35	0	18C	Fab/Deliver RTU - for Cafe/Aud Lib
15C-526	Fab/Deliver Roof Equipment - 15C - HVAC	80	80	15JAN10	06MAY10	5	-31	15C	Fab/Deliver Roof Equipment - 15C - HVAC
15C-550	Fab/Deliver H.V. Unit - Gym	50	50	15JAN10	06MAY10	34	0	15C	Fab/Deliver H.V. Unit - Gym
15C-526	Fab/Deliver Roof Equipment - 15C - HVAC	50	50	15JAN10	06MAY10	34	0	15C	Fab/Deliver Roof Equipment - 15C - HVAC
15C-259	Fab/Deliver Mech Pipe / Duct - Bldg C	20	20	18JAN10	16FEB10	63	-6	18C	Fab/Deliver Mech Pipe / Duct - Bldg C
15C-623	A/E Re-sub Re-sub SD Chiller - 15C - HVAC	20	20	12FEB10	11MAR10	32	0	15C	A/E Re-sub Re-sub SD Chiller - 15C - HVAC
15C-625	Fab & del Chiller - 15C - HVAC	60	60	12MAR10	04JUN10	32	0	16C	Fab & del Chiller - 15C - HVAC
Send Form	15APR09	Early Bar	GILBANE BUILDING COMPANY		Sheet 17 of 31				
Print Date	10/2/10	Progress Bar	WORCESTER NORTH HIGH SCHOOL (W116)						
Print Time	11:22:10 AM	Critical Activity	BID PACKAGE - CURRENT WORK						
© Primavera Systems, Inc.				<b>Gilbane</b>					

ACTIVITY	FROM	TO	ACTIVITY	FROM	TO	ACTIVITY	FROM	TO	ACTIVITY	FROM	TO	ACTIVITY	FROM	TO	ACTIVITY	FROM	TO
2-9320AB	R.I.O.H. Mechanical Piping - 2nd Flr	20	8	14DEC05A	21JAN10	-18	16C	R.I.O.H. Mechanical Piping - 2nd Flr									
2-9325AB	R.I.O.H. HVAC - 3rd Flr	20	8	29DEC05A	11FEB10	25	-24	16C	R.I.O.H. HVAC - 3rd Flr								
4794K	R.I.O.H. Mechanical Piping - Kitchen/Caf	5	5	15JAN10	21JAN10	21	-32	15C	R.I.O.H. Mechanical Piping - Kitchen/Caf								
3-9320AB	R.I.O.H. Mechanical Piping - 3rd Flr	20	16	05FEB10	26FEB10	35	-25	15C	R.I.O.H. Mechanical Piping - 3rd Flr								
4602C	R.I.O.H. Mechanical Piping - Locker Area	15	15	16FEB10	08MAR10	63	-5	15C	R.I.O.H. Mechanical Piping - Locker Area								
1-9336AB	Instal VAV's / FCU's / CUH - 1st Flr	6	6	22FEB10	28FEB10	24	-70	16C	Instal VAV's / FCU's / CUH - 1st Flr								
4740K	Set RTU - Kitchen/Caf	2	2	28FEB10	01MAR10	207	-42	18C	Set RTU - Kitchen/Caf								
4-9305AB	R.I.O.H. HVAC - 4th Flr	20	20	28FEB10	25MAR10	28	-94	15C	R.I.O.H. HVAC - 4th Flr								
4720K	Instal VAV's / FCU's / CUH - Kitchen/Caf	5	5	01MAR10	07MAR10	27	-70	15C	Instal VAV's / FCU's / CUH - Kitchen/Caf								
1-9306AB	Duct Tie In To VAV's - 1st Flr	9	9	01MAR10	10MAR10	24	-70	15C	Duct Tie In To VAV's - 1st Flr								
1-9307AB	Piping Tie In To VAV's - 1st Flr	9	9	01MAR10	11MAR10	18	-70	15C	Piping Tie In To VAV's - 1st Flr								
2-9306AB	Instal VAV's / FCU's / CUH - 2nd Flr	10	10	01MAR10	12MAR10	24	-50	16C	Instal VAV's / FCU's / CUH - 2nd Flr								
4724K	Duct Tie In To VAV's - Kitchen/Caf	2	2	11MAR10	12MAR10	24	-70	15C	Duct Tie In To VAV's - Kitchen/Caf								
4-9320AB	R.I.O.H. Mechanical Piping - 4th Flr	20	20	12MAR10	02APR10	30	-34	15C	R.I.O.H. Mechanical Piping - 4th Flr								
4722K	Piping Tie In To VAV's - Kitchen/Caf	1	1	15MAR10	15MAR10	187	-70	15C	Piping Tie In To VAV's - Kitchen/Caf								
2-9308AB	Duct Tie In To VAV's - 2nd Flr	10	10	15MAR10	28MAR10	24	60	16C	Duct Tie In To VAV's - 2nd Flr								
3-9306AB	Instal VAV's / FCU's / CUH - 3rd Flr	10	10	15MAR10	22MAR10	24	-40	15C	Instal VAV's / FCU's / CUH - 3rd Flr								
2-9307AB	Piping Tie In To VAV's - 2nd Flr	10	10	15MAR10	29MAR10	44	-50	15C	Piping Tie In To VAV's - 2nd Flr								
3-9307AB	Piping Tie In To VAV's - 3rd Flr	10	10	29MAR10	30APR10	24	-40	16C	Piping Tie In To VAV's - 3rd Flr								
3-9308AB	Duct Tie In To VAV's - 3rd Flr	10	10	29MAR10	30APR10	24	-40	16C	Duct Tie In To VAV's - 3rd Flr								
1-9175AB	Firestop Duct Penetrations - 1st Flr	3	3	02APR10	30APR10	121	-17	15C	Firestop Duct Penetrations - 1st Flr								
4-9306AB	Instal VAV's / FCU's / CUH - 4th Flr	10	10	02APR10	22APR10	26	-39	16C	Instal VAV's / FCU's / CUH - 4th Flr								
4402C	R.I.O.H. Mechanical - Auditorium	30	30	05APR10	01MAY10	22	0	16C	R.I.O.H. Mechanical - Auditorium								
9905C	R.I.O.H. HVAC - Bldg C	20	20	12APR10	07MAY10	24	-44	15C	R.I.O.H. HVAC - Bldg C								
4-9307AB	Piping Tie In To VAV's - 4th Flr	10	10	23APR10	08MAY10	25	-38	15C	Piping Tie In To VAV's - 4th Flr								
4-9308AB	Duct Tie In To VAV's - 4th Flr	10	10	23APR10	08MAY10	25	-38	16C	Duct Tie In To VAV's - 4th Flr								
9970C	R.I.O.H. Mechanical Piping - Bldg C	20	20	26APR10	21MAY10	49	-44	16C	R.I.O.H. Mechanical Piping - Bldg C								
4734K	Firestopping - Kitchen/Caf	2	2	30APR10	02MAY10	158	-7	15C	Firestopping - Kitchen/Caf								
2-6416AB	Firestop Duct Penetrations - 2nd Flr	5	5	30APR10	08MAY10	80	-7	15C	Firestop Duct Penetrations - 2nd Flr								
4303AB	Set Mechanical Roof Equipment - Classroom Bldg	10	10	07MAY10	23MAY10	6	31	16C	Set Mechanical Roof Equipment - Classroom Bldg								
4301C	Set Mechanical Equipment Gym	13	13	07MAY10	29MAY10	162	-31	15C	Set Mechanical Equipment Gym								
9906C	Instal VAV's / FCU's / CUH - 1st Flr Bldg C	10	10	17MAY10	29MAY10	59	-44	15C	Instal VAV's / FCU's / CUH - 1st Flr Bldg C								
3-6415AB	Firestop Duct Penetrations - 3rd Flr	5	5	29MAY10	04JUN10	45	-17	15C	Firestop Duct Penetrations - 3rd Flr								
9907C	Piping Tie In To VAV's - Bldg C	10	10	01JUN10	14JUN10	58	-41	15C	Piping Tie In To VAV's - Bldg C								
9908C	Duct Tie In To VAV's - Bldg C	10	10	01JUN10	14JUN10	58	-41	15C	Duct Tie In To VAV's - Bldg C								
1-6400AB	Instal RGD - 1st Flr	8	8	01JUN10	15JUN10	99	-22	16C	Instal RGD - 1st Flr								
2-6400AB	Instal RGD - 2nd Flr	15	15	01JUN10	25JUN10	78	17	15C	Instal RGD - 2nd Flr								
4-6416AB	Firestop Duct Penetrations - 4th Flr	5	5	26JUN10	02JUL10	10	-17	15C	Firestop Duct Penetrations - 4th Flr								

Start Date 1/15/10 Data Date 1/15/10 Run Date	31APR10 15SEP10 15JAN10 31JAN10	<input type="checkbox"/> Early Bar <input type="checkbox"/> Progress Bar <input type="checkbox"/> Critical Activity	W/C GILBANE BUILDING COMPANY WORCESTER NORTH HIGH SCHOOL (W115) BID PACKAGE - CURRENT WORK	Gilbane	Project Status Manager
---	--	---	---	---------	------------------------------



Activity	Start	End	Start	End	Duration	ES	EF	LS	LF	Activity
4432C	01	10	23JUN10	12JUL10	22	0	150			GH Ceiling RGDs - Auditorium
3-5400AB	16	16	06JUL10	26JUL10	10	-17	150			Install RGD - 3rd Flr
4-5400AB	15	15	03AUG10	23AUG10	5	-17	150			Install RGD - 4th Flr
3415C	5	5	17AUG10	23AUG10	2/2	-50	150			Firestop Duct Penetrations - Bldg C
4504C	7	7	3AUG10	08SEP10	50	88	150			Ceiling RGDs - Locker Area
0425	50	60	22SEP10	01DEC10	80	-93	150			Final General Equipment Start-Up & Commissioning
5400C	15	15	29SEP10	16OCT10	15	-93	150			Install RGD - Bldg C
4-5422AB	10	10	23OCT10	02NOV10	10	-17	150			Test & Balance HVAC - 4th Flr
3-5422AB	10	10	10NOV10	23NOV10	10	-17	150			Test & Balance HVAC - 3rd Flr
2-5422AB	10	10	30DEC10	19DEC10	5	-17	150			Test & Balance HVAC - 2nd Flr
4752K	7	7	30DEC10	17DEC10	22	-7	150			Install RGD - Kitchen Caf
1-5422AB	10	10	22DEC10	07JAN11	0	-7	150			Test & Balance HVAC - 1st Flr
5422C	15	15	10JAN11	28JAN11	0	-17	150			Test & Balance HVAC - 1st Flr Bldg C
15C-COST	250*	225*	19OCT09A	31DEC10	80	-23	150			Cost Summary: HVAC 15B
<b>3-UNDER SLAB PILING (FEB)</b>										
16B2B-COST	60	60	31APR10*	24JUN10	313	D	150			Cost Summary: UG Electric 16B2B Spring 2010
<b>04- ELECTRICAL (FEB)</b>										
16A-527	45	1E	07AUG09A	04FEB10	40	-53	15A			Prep/Sub SD+Data 16A-Light Fixtures
16A-532	10	5	29OCT09A	21JAN10	387	0	19A			Prep/Sub SD+Data 16A-Panel Boxes
D12-600	10	10	14JAN10A	23JAN10	188	0	18A			Price Add # 30 Revised Electrical (Add)
D12-602	10	10	14JAN10A	12FEB10	159	0	18A			Owner App Price Add # 30 Revised Electrical (Add)
D12-601	1	1	16JAN10	15JAN10	159	0	18A			Mtg to Clarify # 30 Revised Electrical/subs
16A-634	15	15	22JAN10	11FEB10	387	0	18A			Rev App SD- Panel Boxes
16A-624	15	15	05FEB10	28FEB10	40	-53	18A			Rev App Light Fixtures
16A-636	20	20	12FEB10	11MARCH10	387	0	18A			Fab/Del Panel Boxes
D12-612	10	10	15FEB10	26FEB10	169	0	18A			Prep & Resub # 30 - Switchgear
16A-617	20	20	28FEB10	04JUN10	40	-113	18A			Fab/Del Light Fixtures
16A-614	15	15	01MARCH10	18MARCH10	169	-48	18A			Rev App SD- Switchgear
16A-616	50	50	22MARCH10	23MARCH10	169	108	18A			Fab/Del Switchgear
2-5340AB	20	10	23DEC09A	28JAN10	40	0	10A			RJ Electric In Walls - 2nd Flr
2-5310AB	20	10	23DEC09A	25FEB10	65	-15	16A			R.L.O.H. Electric, Fire Alarm + AV 2nd Flr
1-5310AB	10	10	15JAN10	26JAN10	37	-15	16A			RJ Electric In Walls - 1st Flr
1-5310AB	10	10	15JAN10	22JAN10	78	-34	16A			R.L.O.H. Electric, Fire Alarm + AV - 1st Flr
4710K	10	10	08FEB10	16FEB10	150	-40	16A			RJ Electric In Walls - Kitchen Caf
4924C	15	15	18FEB10	03MARCH10	53	-5	16A			R.L.O.H. Electrical - Locker Area
4725K	10	0	18FEB10	04MARCH10	204	-42	15A			R.L.O.H. Electric, Fire Alarm + AV - Kitchen Caf
3-5310AB	20	20	19FEB10	18MARCH10	25	-20	15A			RJ Electric In Walls - 3rd Flr
4112C	17	7	22FEB10	07MARCH10	54	-21	19A			R.L. In-wall Electrical - Auditorium

1-5220AB	R.I.O.H. Controls - 1st Flr	7	7	22MAR10	22MAR10	48	-64	16A	
4744K	R.I.O.H. Controls - Kitchen/Caf	3	3	16MAR10	19MAR10	197	-48	16A	
4-5310AB	R.I.E. in Wall - 4th Flr	20	20	28MAR10	22APR10	20	-24	16A	
2-5320AB	R.I.O.H. Controls 2nd Flr	10	10	28MAR10	08APR10	44	-26	16A	
3-5310AB	R.I.O.H. Electric, Fire Alarm + AV 3rd Flr	20	20	25MAR10	23APR10	34	-40	16A	
4406C	Temp Lighting (above + below AWP) - Auditorium	5	5	02APR10	02APR10	22	0	15A	
4406C	R.I. Sprinklers - Auditorium	30	30	08APR10	20MAY10	27	0	15A	
4410C	R.I. Electrical - Auditorium	30	30	08APR10	20MAY10	27	0	15A	
3-5320AB	R.I.O.H. Controls 2nd Flr	10	10	28APR10	07MAY10	34	-10	16A	
4-5310AB	R.I.O.H. Electric, Fire Alarm + AV 4th Flr	20	20	25APR10	21MAY10	24	-40	16A	
4-5320AB	R.I.O.H. Controls 4th Flr	10	10	24MAY10	07JUN10	24	-40	16A	
5310C	R.I.O.H. Electric, Fire Alarm + AV - Bldg C	20	20	01JUN10	28JUN10	45	-44	16A	
4420C	House Lighting - Auditorium	10	10	07JUN10	18JUN10	23	0	15A	
1-5390AB	Lighting - 1st Flr	13	13	02JUN10	25JUN10	94	-32	16A	
2-5390AB	Lighting - 2nd Flr	20	20	02JUN10	02JUL10	70	-17	16A	
5340C	R. Electric In Walls - Bldg C	20	20	14JUN10	12JUL10	10	83	16A	
4420C	Suspend AV/ Speakers etc - Auditorium	5	5	27JUN10	25JUN10	22	3	16A	
4510C	In-wall Electrical Rough - Locker Area	20	20	21JUN10	12JUL10	50	-33	16A	
4514C	In-wall Electr. Rm Equipment - Locker Area	16	16	28JUN10	19JUL10	50	-33	16A	
5320C	R.I.O.H. Controls - Bldg C	10	10	25JUN10	13JUL10	45	-44	16A	
4420C	Aud Area Theater Seating & Lights - Auditorium	5	5	02JUL10	08JUL10	3	-6	16A	
3-5390AB	Lighting - 3rd Flr	20	20	08JUL10	02AUG10	25	-7	16A	
5470C	R.I. Elect In Roof Framing @ High Area	10	10	21JUL10	03AUG10	79	-14	16A	
4490C	OH Ceiling Lighting - Auditorium	10	10	26JUL10	02AUG10	3	-18	16A	
4-5300AB	Lighting - 4th Flr	20	20	03AUG10	30AUG10	0	-17	16A	
4450C	Activate House/Stagerwork Lights - Auditorium	10	10	03AUG10	20AUG10	3	19	16A	
4532C	Ceiling Lighting - Locker Area	7	7	31AUG10	08SEP10	50	+33	15A	
5390C	Lighting - Bldg C	20	20	28SEP10	29OCT10	10	35	15A	
4758K	Lighting - Kitchen/Caf	7	7	06DEC10	17DEC10	27	-17	15A	
5435	Fire Alarm In House Test	6	6	16DEC10	22DEC10	142	-33	16A	
5430C	Install Electrical Finishes - Bldg C	10	10	17JAN11	23JAN11	0	-17	16A	
16A-COST	Cost Summary: Electrical 16A	215	215	23MAR10	23JAN11	0	17	16A	
<b>ELECTRICAL FINISHES (PSE)</b>									
16A-COST	Cost Summary: UIC Electric 16A2A Fall 2009	40	40	15JAN10	11MAR10	387	-53	16B	
<b>GENERAL OCCUPANCY &amp; PUNCH LIST</b>									
4-5427	Complete for Final Clean/Punch List - 4th Flr	3	0		30NOV10	80	-17	16D	
4-5428	Final Clean - 4th Flr	5	0	10NOV10	16NOV10	68	-17	16D	
4-5430	AVE & Citrus Issue Punch List - 4th Flr	13	10	17NOV10	01DEC10	60	-17	16D	
<div style="display: flex; justify-content: space-between;"> <div style="width: 20%;"> <p>Start Date: 15APR10 Finish Date: 10JUN11 Cost Date: 15APR10 Run Date: 22MAY10 14:28</p> </div> <div style="width: 40%; text-align: center;"> <p>Early Bar Progress Bar Critical Activity</p> <p><b>GILBANE BUILDING COMPANY</b> WORCESTER NORTH HIGH SCHOOL (W116) BID PACKAGE - CURRENT WORK</p> </div> <div style="width: 30%; text-align: right;"> <p>100% 90% 80% 70% 60% 50% 40% 30% 20% 10% 0%</p> <p><b>Gilbane</b></p> </div> </div>									
<p>© Primavera Systems, Inc.</p>									

- R.I.O.H. Controls - 1st Flr
  - R.I.O.H. Controls - Kitchen/Caf
  - R.I. Electric In Walls - 4th Flr
  - R.I.O.H. Controls 2nd Flr
  - R.I.O.H. Electric, Fire Alarm + AV 3rd Flr
  - Temp Lighting (above + below AWP) - Auditorium
  - R.I. Sprinklers - Auditorium
  - R.I. Electrical - Auditorium
  - R.I.O.H. Controls 2nd Flr
  - R.I.O.H. Electric, Fire Alarm + AV 4th Flr
  - R.I.O.H. Controls 4th Flr
  - R.I.O.H. Electric, Fire Alarm + AV - Bldg C
  - House Lighting - Auditorium
  - Lighting - 1st Flr
  - Lighting - 2nd Flr
  - R.I. Electric In Walls - Bldg C
  - Suspend AV/ Speakers etc - Auditorium
  - In-wall Electrical Rough - Locker Area
  - Install Electr. Rm Equipment - Locker Area
  - R.I.O.H. Controls - Bldg C
  - Aud Area Theater Seating & Lights - Auditorium
  - Lighting - 3rd Flr
  - R.I. Electric In Roof Framing @ High Area
  - OH Ceiling Lighting - Auditorium
  - Lighting - 4th Flr
  - Activate House/Stagerwork Lights - Auditorium
  - Ceiling Lighting - Locker Area
  - Lighting - Bldg C
  - Lighting - Kitchen/Caf
  - Fire Alarm in House Test
  - Install Electrical Finishes - Bldg C
- Cost Summary: Electrical 16A

- Cost Summary: UIC Electric 16A2A Fall 2009
- ◆ Complete for Final Clean/Punch List - 4th Flr
  - Final Clean - 4th Flr
  - AVE & Citrus Issue Punch List - 4th Flr

3-5427	Complete for Final Clean/Punch List - 3rd Flr	0	0		31DEC10	45	-17	93R	◆ Complete for Final Clean/Punch List
3-5428	Final Clean - 3rd Flr	5	5	09DEC10	08DEC10	45	-17	93D	■ Final Clean - 3rd Flr
4-5435	Implement Punch List - 4th Flr	20	20	02DEC10	30DEC10	60	-17	99D	■ Implement Punch List - 4th Flr
3-5430	A/E & Owner Issue Punch List - 3rd Flr	10	10	09DEC10	22DEC10	45	-17	98D	■ A/E & Owner Issue Punch List - 3rd Flr
2-5427	Complete for Final Clean/Punch List - 2nd Flr	3	0		22DEC10	30	-17	95D	◆ Complete for Final Clean/Punch List
2-5428	Final Clean - 2nd Flr	5	5	23DEC10	20DEC10	20	-17	99D	■ Final Clean - 2nd Flr
3-5435	Implement Punch List - 3rd Flr	20	20	23DEC10	21JAN11	45	-17	95D	■ Implement Punch List - 3rd Flr
R-5430AB	A/E & Owner Issue Punch List - Roof A/B	10	10	30DEC10	15JAN11	31	-22	95D	■ A/E & Owner Issue Punch List - Roof A/B
R-5430C	A/E & Owner Issue Punch List - Roof C	10	10	30DEC10	15JAN11	31	-22	95D	■ A/E & Owner Issue Punch List - Roof C
2-5430	A/E & Owner Issue Punch List - 2nd Flr	10	10	06JAN11	14JAN11	30	-17	95D	■ A/E & Owner Issue Punch List - 2nd Flr
1-5427	Complete for Final Clean/Punch List - 1st Flr	0	0		11JAN11	18	-17	95D	◆ Complete for Final Clean/Punch List
1-5428	Final Clean - 1st Flr	5	5	12JAN11	18JAN11	18	-17	95D	■ Final Clean - 1st Flr
R-5430AB	Implement Punch List - Roof A/B	20	20	14JAN11	10FEB11	51	-22	95D	■ Implement Punch List - Roof A/B
R-5430C	Implement Punch List - Roof C	20	20	14JAN11	10FEB11	51	-22	95D	■ Implement Punch List - Roof C
2-5435	Implement Punch List - 2nd Flr	20	20	17JAN11	11FEB11	30	-17	95D	■ Implement Punch List - 2nd Flr
1-5430	A/E & Owner Issue Punch List - 1st Flr	10	10	19JAN11	01FEB11	18	-17	95D	■ A/E & Owner Issue Punch List - 1st Flr
5440AB	A/E & Owner Punch List - Exterior	10	10	21JAN11	03FEB11	16	-22	95D	■ A/E & Owner Punch List - Exterior
5440C	Final Clean - 1st Flr Bldg C	10	10	31JAN11	11FEB11	0	-17	95D	■ Final Clean - 1st Flr Bldg C
1-5435	Implement Punch List - 1st Flr	20	20	02FEB11	01MAR11	18	-17	95D	■ Implement Punch List - 1st Flr
5445AB	Implement Punch List - Exterior	20	20	04FEB11	03MAR11	18	-22	95D	■ Implement Punch List - Exterior
3-5435	A/E & Owner Issue Punch List @ Bldg C	0	10	14FEB11	25FEB11	0	-17	95D	■ A/E & Owner Issue Punch List @ Bldg C
6-5435	Implement Punch List @ Bldg C	20	20	23FEB11	25MAR11	0	-17	95D	■ Implement Punch List @ Bldg C
<b>INSPECTION</b>									
1-5000AB	OH Inspection - 1st Flr	3	3	24JUN10	28JUN10	04	-32	INS	■ OH Inspection - 1st Flr
2-5000AB	OH Inspections - 2nd Flr	5	5	06JUL10	12JUL10	07	-17	INS	■ OH Inspections - 2nd Flr
3-5000AB	OH Inspections - 3rd Flr	5	5	05AUG10	06AUG10	05	-17	INS	■ OH Inspections - 3rd Flr
4-5000AB	OH Inspection - 4th Flr	5	5	31AUG10	01SEP10	01	-17	INS	■ OH Inspection - 4th Flr
9000U	OH Inspection - Bldg C	0	5	27OCT10	02NOV10	10	-33	INS	■ OH Inspection - Bldg C
4763K	OH Inspection - Kitchen/Caf	2	2	20DEC10	21DEC10	22	-17	INS	■ OH Inspection - Kitchen/Caf
Start Date	2/15/09	Early Bar		WHIR		Sheet 2 of 21		Job No. 0000	
Finish Date	18FEB11	Progress Bar		GILBANE BUILDING COMPANY		C/1/P/2 - 1/10/10		Project Name	
Draw Date	15/01/10	Critical Activity		WORCESTER NORTH HIGH SCHOOL (W116)		C/1/P/2 - 1/10/10		Contract No.	
Rev. Date	22/01/10 1428			BID PACKAGE - CURRENT WORK		C/1/P/2 - 1/10/10		Contract Value	
© Gilbane Systems, Inc.				Gilbane		C/1/P/2 - 1/10/10		Contract Value	

# Appendix C: Bid Package Cost vs. Budget Estimate

Worcester North High School - GRCO, Project No. 4637

Bid Package Cost vs. Budget Estimate

10/29/2009


Bid Package # & Name (Trade Contractor Bid Packages - In Bold)	Contractor	RF Est Budget (4-13-09)	Estimated Contract Value	Actual Award Amount	CR Amount	Total Drafts to Date	Variance \$	Variance %	Comments
<b>C24 - Landscaping</b>		\$183,225	\$183,225	\$0		\$183,225	\$0	0.00%	
<b>D4A - Masonry</b>		\$4,008,839	\$4,008,839	\$0		\$4,008,839	\$0	0.00%	
<b>D5B - Miscellaneous Metals</b>		\$29,638	\$0	\$669,000		\$669,000	(\$29,638)	+27.25%	
<b>D6A - Millwork</b>		\$873,144	\$873,422	\$0		\$873,422	\$0	0.03%	
<b>D7C - Waterproofing &amp; Joint Sealants</b>		\$348,777	\$0	\$369,000		\$369,000	(\$218,225)	61.99%	
<b>D7E - Metal Panels</b>		\$352,791	\$352,791	\$0		\$352,791	\$0	0.00%	
<b>D9B - Glass &amp; Glazing</b>		\$113,730	\$113,730	\$0		\$113,730	\$0	0.00%	
<b>D9C - Spaced Doors</b>		\$127,500	\$127,500	\$0		\$127,500	\$0	0.00%	
<b>D9E - Ceramic Tile</b>		\$423,327	\$0	\$0		\$0	(\$423,327)	-100.00%	
<b>D9C - Acoustical Ceilings</b>		\$863,220	\$863,220	\$0		\$863,220	\$0	0.00%	
<b>D9D - Carpentry</b>		\$86,175	\$86,175	\$0		\$86,175	\$0	0.00%	
<b>D9E - Resilient Flooring</b>		\$728,235	\$728,235	\$0		\$728,235	\$0	0.00%	
<b>D9F - Wood (Athletic) Flooring</b>		\$284,040	\$284,040	\$0		\$284,040	\$0	0.00%	
<b>D9G - Epoxy Flooring</b>		\$37,339	\$37,339	\$0		\$37,339	\$0	0.00%	
<b>D9H - Painting &amp; Wallcovering</b>		\$459,488	\$459,488	\$0		\$459,488	\$0	0.00%	
<b>D9J - General Trades</b>		\$575,241	\$575,241	\$0		\$575,241	\$0	0.00%	
<b>D9A - Lockers</b>		\$348,840	\$348,840	\$0		\$348,840	\$0	0.00%	

## Appendix D: Retaining Wall Design

			①
		<u>Design of Retaining wall with counterforts - M&amp;P</u>	
		Current retaining wall tallest portion is 14.5' and the tallest portion of cliff is around 60-65' at the highest point. The driveway is intended as a firelane and typically live loads for a firelane are approx. 250 psf.	
		→ Use counterforts because they add tremendous strength without making the slab of the heel very long	
		Soil properties → glacial till (very dense, fine sandy silt)	
		— footing designs can be used with an allowable bearing pressure of <u>5 tons/sqft</u> , value of 0.6 for coefficient between concrete and bearing soil for sliding resistance.	

②

### General pressures on retaining walls



① Determine DL and LL for the wall

We need to design the wall for the driveway that is intended as a firelane. Typically for firelanes, LL = 250 psf

$$U = 1.4D + 1.7L$$

There is no DL on the wall, so


$$U = 1.7L = 1.7(250 \text{ psf}) = \underline{425 \text{ psf}}$$

Design for  $f'_c = 4000 \text{ psi}$   $f_y = 60,000 \text{ psi}$


Need to assume wall dimensions

Assume wall = 10' high

we used this general association for the dimensions



Our wall



Our problem

Design a cantilever wall to retain a bank of 65' whose horizontal surface is subjected to a live load surcharge of 250 psf. The soil is glacial till, very dense, fine sandy silt.

④


Properties of soil can be classified as  
Soil numbers

$$\text{unit wt/pcf} = 110-120 \text{ pcf} \quad \phi = 25-30'$$

$$f = 0.6 \text{ / per vito from } \underline{\text{Collinay}}$$

$$q_c = 5 \text{ tons/sqft} = \underline{10,000 \text{ psf}}$$

a general look to our wall





(5)


Find  $h'$  due to the surcharge of the LL

$$h' = \frac{S}{w} \quad \text{assume } w = 120 \text{ pcf}$$

$$S = 425 \text{ psf}$$

$$h' = \frac{425 \text{ psf}}{120 \text{ pcf}} = \underline{\underline{3.27'}}$$

Assumed pressures



our estimated base thickness = 1.50  
if  $h = 10'$  our free arm distance will be 9'

$$C_m = \frac{1 - \sin \phi}{1 + \sin \phi} = \frac{1 - \sin 30^\circ}{1 + \sin 30^\circ} = \underline{\underline{0.333}}$$

Assume  $\phi = 30^\circ$

(6)

Pressure  $P$

$$P = \frac{1}{2} C_a h w h (h + 2h')$$

$$= \frac{1}{2} (0.333) (120) (9') (9' + 2(3.27'))$$

Total  $P$  from surcharge =  $2974.22 \approx \underline{2799 \text{ lbs}}$

$$y = \frac{h^2 + 3hh'}{3(h + 2h')} = \frac{(9')^2 + 3(9)(3.27)}{3(15.54)} = \frac{169.29}{46.62}$$

$$y = 3.63'$$

$$M_0 = 1.7 (2799) (3.63') = \underline{17246 \text{ ft}\cdot\text{lbs}}$$

Find the size of steel

$$P_b = \frac{0.85(4000)}{60,000} (0.85) \left( \frac{87,000}{87,000 + 60,000} \right) =$$

$$P_b = 0.0284 \quad \leftarrow \text{shear}$$

$$P_{all} = \left( \frac{P_b}{2} \right) (0.75)$$

$$P_{all} = 0.01066 \approx 0.011$$

Look in appendix e for  $\frac{M_0}{bd^2}$  value

⑦

From the book → appendix A Graph A.1b

$$\frac{M_u}{\phi b d^2} = 590$$

unit length of wall ( $b=12''$ ) with  $\phi=0.90$

$$d = \sqrt{\frac{M_u \times 12}{0.90 \times 12 \times 590}} =$$

$$d = \sqrt{\frac{17216 \times 12}{0.90 \times 12 \times 590}} = \sqrt{\frac{206952}{6372}} = \sqrt{32.42}$$

$$d = 5.69'' \approx 5.70''$$

Assume  $\frac{1}{2}''$  diameter of rebar

also, 2'' cover over steel

$$d = 5.70'' + 2.0'' + .5'' = 8.2'' \text{ make}$$

10'' = d at base of arm

check arm for shear at distance  $d$  above the

base  $d = \frac{10''}{12''} = 0.833' = \text{distance} = 9' - 0.833' = 8.1667'$



Check shear away from base

$$P = \frac{1}{2} \times 0.333 \times 120 \times 8.1667 \times 15.54 = 2535 \text{ lbs}$$

$$V_u = 1.7 \times 2535 = 4310.6 \text{ lbs}$$

$$\phi V_c = 2 \phi \sqrt{f'_c} b d$$

$$= 2 (.85) (\sqrt{4000}) (12) (10)$$

$$= 2 (.85) (63.24) (12) (10) = 12902 \text{ lbs}$$

$$4310 \text{ lbs} < 12902 \text{ lbs}$$

Passes shear test ✓

Design for a 12' wall

Soil numbers remain the same

• unit wt = 110-120 pcf  $\phi = 25-30'$



$f = 0.6$  / per vito from Collinon

$q = 5 \text{ tons/sq ft} = 10,000 \text{ psf}$

Find  $h'$  due to the surcharge - will be the same

$h' = \frac{S}{w}$  assume  $w = 120 \text{ pcf}$

$S = 425 \text{ psf}$

$h' = 3.27'$

$C_{ah}$  will be the same as well = 0.333

Pressure  $P = \frac{1}{2} C_{ah} w h (h + 2h')$

estimated footing thickness = 1.5' / effective height = 10.5'

$P = \frac{1}{2} (0.333)(120)(10.5')(10.5 + 2(3.27'))$   
 $= 3574.82 \text{ lbs}$

$y = \frac{h^2 + 3hh'}{3(h + 2h')} = \frac{10.5^2 + 3(10.5)(3.27)}{3(17.01)} = \underline{\underline{4.17'}}$

9

$$M_u = 1.7(3574.82)(4.17) = \underline{25341.88 \text{ ft}\cdot\text{lbs}}$$

$P_{all}$  is the same as the previous wall

$$\underline{P_{all} = 0.011}$$

look in appendix for  $\frac{M_u}{bd^2}$  value

$$\frac{M_u}{bd^2} = 590 \text{ from chart} \quad f_y = 60 \text{ ksi} \quad f'_c = 4000 \text{ psi}$$

$$d = \sqrt{\frac{M_u \times 12}{0.90 \times 12 \times 590}} = \sqrt{\frac{25342 \times 12}{0.90(12)(590)}} = \underline{\underline{6.9''}}$$

Assume  $\frac{1}{2}$ " diameter for Rebar

also, 2" cover for steel

$$d = 6.9'' + 2'' + .5'' = 9.4'' \approx \underline{\underline{10''}}$$

check arm for shear distance above base

$$d = \frac{10''}{12''} = 0.833' \text{ distance} = 10.5' - .833' = \underline{\underline{9.667'}}$$

Check shear away from base

$$P = \frac{1}{2} \times 0.333 \times 120 \times 9.667 \times 17.04 = 3291.2 \text{ lbs}$$

$$1.7(3291.2) = \underline{5594.7 \text{ lbs}}$$

$$\phi V_c = 2\phi \sqrt{f_c} b d = \underline{\underline{12902 \text{ lbs}}}$$


$$5594.7 \text{ lbs} < 12902 \text{ lbs}$$

passes shear



b) stability investigation


Drawing of Retaining wall right now (10' wall)





b) Stability investigation

Drawing of retaining wall as it looks now



Component weight table

Distance From Center of  $w$  to Front of wall

C.W	$W$ lbs	$K_{ft}$	$MR$ ft-lbs
$W_1 = \left(\frac{5}{6}\right)(9')(150)$	1125	1.92'	2160
$W_2 = (1')(7.833)(150)$	1175	3.92'	4606
$W_3 = \left(\frac{5}{6}\right)\left(\frac{5}{6}\right)(150)$	104	1.92'	199.68
$W_4 = (9')(5.5')(120)$	5940	5.083'	30193
$W_5 = (2')(1.5')(120)$	360	0.75'	270
$W_6 = \frac{1}{2}(9')(5.5')(150)$	3713	4.16'	15446
Totals!	12,417		52,875

(12)

Total soil pressure

$$P = 0.5 (c + \gamma h) (w) (h) (h + 2h')$$

$$P = 0.5 (0.333) (120) (10') (10' + 6.54)$$

$$P = \underline{\underline{3305 \text{ lbs}}}$$

$$y = \frac{h^2 + 3hh'}{3(h + 2h')}$$

$$= \frac{(100) + 3(10)(3.27)}{3(10 + 6.54)} = 3.99 \approx 4.00'$$

$$M_o = 3305 \text{ lbs} \times 4.00' = \underline{\underline{13,220 \text{ Ft. lbs}}}$$

distance of resultant from front edge

$$a = \frac{52,875 - 13,220}{12,417} = \underline{\underline{3.19'}}$$

Resultant is inside middle 3rd

Using the formula  $\rightarrow$  max bearing pressure =

$$q_1 = (4L - 6a) \frac{R_v}{L^2}$$

$$q_1 = \frac{(31.32 - 19.14)}{61.36}$$

Surcharge

$$W_{Tot.} = 12,417 + 425 \text{ psf} \times 5.5$$

$$= \underline{14,754.5 \text{ lbs}}$$

$$M_c = 52875 + 425 (5.37) (5.5)$$

$$= \underline{65,427.4 \text{ lbs}\cdot\text{ft}}$$

$$New a = \frac{65,427.4 - 13,220}{14,754.5} = 3.54'$$

Inside middle 3<sup>rd</sup>

Surcharge to a


$$q_1 = \frac{(31.32 - 21.24)(14,754.5)}{61.36}$$

$$F.O.S = \frac{52875}{13,220} = \underline{3.99}$$

$$q_1 = \underline{2423.8 \text{ psf}}$$

$$\underline{\text{Friction Force}} = 0.5 \times 12,417 = \underline{6,208.5 \text{ lbs}}$$

Fricion at the toe



$$\frac{7.83}{5.5} = \frac{2423.8}{x}$$

$$x = 1702$$

Fricion toe :  $(2423.8 + 1702) \times 5 \times 1.5 \times 0.577$   
 $= 1785.5 \text{ lbs}$

Fricion heel, key :  $1702 \times 5 \times 6.333 \times 0.5$   
 $= 2695 \text{ lbs}$

Passive Earth Pressure =  $0.5 \times 120 \times 3.0 \times 1.833^3$   
 $= 329 \text{ lbs}$

Total Resistance to sliding =  $\frac{4809.5 \text{ lbs}}{P = 3305 \text{ lbs}}$

FS = 1.45 = adequate

External stability is ascertained

(15)

Steel for the arm and key

10" arm - 2" cover  
+ .5"

$M_o = 17,246 \text{ ft-lbs}$  from before

$$\frac{M_o}{bd^2} = \frac{17,246 (12)}{0.9 (12) (7.5)^2} = \underline{\underline{340.6}}$$

#6 @ 24  
.22

$f_y = 60,000 \quad f'_c = 4000$

Steel ratio from chart = 0.006

$$A_s = 0.006 \times 12 \times 7.5 = 0.54 \text{ in}^2/\text{ft}$$

Use #7 bars @ 12" on center ( $A_s = 0.60 \text{ in}^2/\text{ft}$ )

From 4.5' #7 bars @ 24" on center

Control temperature and cracking

Not less than 0.0012 times the gross  
Concrete area must be provided

$$\text{Gross Area} = 12" \times 7.5" = \underline{\underline{90 \text{ in}^2}}$$

$$(0.0012)(90 \text{ in}^2) = 0.108$$

Vertical Bars exposed face

$$\frac{1}{2} (0.108) \text{ Bars} > 0.054 \text{ in}^2/\text{ft}$$


#4 Bars @ 24" O.C ( $A_s = 0.10 \text{ in}^2/\text{ft}$ )

Non exposed face

use #4 Bars @ 16 in O.C  
( $A_s = 0.145 \text{ in}^2/\text{ft}$ )

horizontal steel

$$0.0020 (12" \times 7.5") = \frac{0.18 \text{ in}^2/\text{ft}}{2} = 0.09 \text{ in}^2/\text{ft}$$
$$= \#4 @ 20 \text{ in O.C}^2$$



Design Steel for Toe Slab

2710

load factor of 1.7

Find moment =  $\swarrow$  to point C

$$M_0 = 1.7 \left( \frac{2423.8}{2} \times 1.5^2 \times \frac{2}{3} \right)$$

Find w from a to C  $M_0 = \text{the same}$

$$a = \frac{52,875 - 13,220}{12,417} = 3.19'$$

Bigger  $\frac{12,417}{7.833}$  inside middle 3rd

$$q_1 = (4L - 6a) \frac{P_v}{L^2}$$

$$q_1 = (7.833(4) - 6(3.19)) \left( \frac{12,417}{7.833^2} \right)$$



$$(31.32 - 19.14)(202.37) =$$

$$q_1 = 2465 \text{ lbs}$$

$$q_2 = (6a - 2L) \frac{P_v}{L^2}$$

$$= (19.14 - 15.66)(202.37)$$

$$q_2 = 704.28 \text{ lbs}$$



$$\text{Surcharge to b} = \frac{1761}{7.83} = \frac{x}{6.33}$$

$$\text{Surcharge at b} = \underline{\underline{1723}}$$

Toe slab

(18)

Find moment

$$M_u = 1.7 \left( \frac{2423.8}{2} \times 1.5^2 \times \frac{2}{3} + \frac{1423}{2} \times 1.5^2 \times \frac{1}{3} \right) - 0.9 \left( 150 \times 1.5^2 \times \frac{1}{2} \right)$$

$$= 1.7(1818 + 533.1) - 0.9(168.75)$$

$$M_u = 3996.87 - 151.875 =$$

$$M_u = 3845 \text{ ft-lbs}$$

For concrete case exposed to earth,  
protective cover of 3 in is required bar  $\phi = 1''$   
effective depth =  $12'' - 3.0'' - 0.5'' = \underline{8.5''}$

$$\frac{M_u}{\phi b d^2} = \frac{3845 \times 12}{0.9 \times 12 \times 72.25} = 59.13 \leftarrow \text{Graph is less}$$

$$\text{Minimum required } \rho_b = \frac{200}{60,000} = \underline{0.0033} \leftarrow \text{use}$$

$$A_s = 0.0033 \times 12 \times 8.5 = \underline{0.3366 \text{ in}^2/\text{ft}}$$

$$\underline{\# 6 \text{ bars @ } 12'' \text{ O.C. } (A_s = 0.44 \text{ in}^2/\text{ft})}$$



Reflecting 12 in lateral spacing,  
the bars will be continued 21" past the  
face of the wall.

Check Shear

Shear will be checked 167733 (1'6")  
from edge of toe = 1' from edge of toe

$$\frac{2710}{9.75} = \frac{x}{2465}$$

$$V_u = 1.7 \left( 2465 \times \frac{1}{2} \times 1 + 1536 \times \frac{1}{2} \times 1 \right) - 0.9(150 \times 1)$$
$$= 3400.85 - 135 =$$

$V_u = 3266 \text{ lbs}$

$$\frac{1761}{7.83} = \frac{x}{6.83}$$

Design Shear strength =

$$\phi V_c = 2 \times 0.85 \sqrt{4000} \times 12 \times 8.5$$

$\phi V_c = 10966.7 \text{ lbs}$  ✓ passes shear test

$$\phi V_c > V_u$$

use #3 bars at 12" o.c for  
Cracking Control

(20)

Design for Heel slab total length = 5.5'

L.L. surcharge = 250 psf

$$M_u = 1.7 \left( 250 \times 5.5^2 \times \frac{1}{2} \right) + 1.4 \left( 1423 + 5.5^2 \times \frac{1}{2} + 150 \times 5.5^2 \times \frac{1}{2} \right)$$

$$M_u = 6428.2 + 33308$$

$$= \underline{39736.5 \text{ ft}\cdot\text{lbs}}$$

$$\frac{M_u}{\phi b d^2} = \frac{39736.5 \times 12}{0.9 \times 12 \times 72.25} = \underline{611.1}$$

$P_o = 0.0155$  from graph A.1b

$$A_s = 0.0155 \times 12 \times 8.5 = \underline{1.58 \text{ in}^2/\text{ft}}$$

use #9 bars at 7" O.C  $A_s = \underline{1.70 \text{ in}^2/\text{ft}}$

$$\frac{1761}{7.83} \times \frac{5.5}{5.5} \quad V_u = 1.7(250 \times 5.5) + 1.4(1236.9 \times 5.5)$$

$$V_u = \underline{11861.5 \text{ lbs}} > \underline{10966.7}$$

increase effective depth to 9.5" Does not pass

So, height of toe and slab will be 13"

(21)

with height = 13" effective depth will be 9.5"

$$\phi V_c = 2 \times 0.85 \sqrt{4000} \times 12 \times 9.5 = 12256.98 \text{ lbs}$$

$\phi V_c > V_u = 11861.5 \text{ lbs}$  passes shear ✓



increase bars to #10 bars @ 8" O.C

$$A_s = 1.80 \text{ in}^2/\text{ft}$$

USE #6 bars @ 9" O.C for Crack Control

increase the same, 21" past the stem


### Diagram of the wall



23

### Design of Counterforts


Total wall length = 84'



M = total pressure @ bottom of wall  
P

$$M = \frac{P l^2}{10} \text{ or } \frac{P l^2}{12}$$

Since the total wall length is approx 84' and the drop off is less we will only make wall 42' long. The after, the wall height can decrease significantly.



Counterfort steel design

Mu = p l^2 / 10      p = pressure at bottom of wall

p = 3305 lbs from previous calculations

Mu = 3305 (9.5 x 12)^2 / 10

Mu = 4,295,178 in^2 lb

jd = typically .875d

Ah = Mu / (phi Fy jd) = 4,295,178 / (0.9 (60,000) (.875) (9.5) (12))

Ah = 0.797 in^2/ft

use #9 bars @ 12 in O.C

Mu = p l^2 / 12      p = 3305 lbs

l = 9.5 (12)

Mu = 3305 (9.5 x 12)^2 / 12

Mu = 3,579,315 lb in^2

Ah = Mu / (phi Fy jd)

Ah = 3,579,315 / (0.9 (60,000) (.875) (9.5) (12)) = 0.665 in^2/ft

use #8 bars @ 12" O.C

(25)

$$A_v = \frac{V_u}{\phi F_y d}$$

0.85  
shear

$$V_i = V + \frac{M}{d} (\tan \theta + \tan \phi)$$

0 30°

$V_i =$

Shrinkage steel =  
0.0035 b x d

$$V_i = 11861 \text{ lbs} + \frac{3,579,315}{8''} (0.577)$$

$$A_v = \frac{11861}{\phi 60000 (8)} = 0.027 \text{ in}^2/\text{ft}$$

Use #3 bars @ 24" O.C

$$A_s = 0.055$$

Shrinkage steel

$$0.0035 b \times d =$$

$$0.0035 \times 1 \times 10' = 0.035 \text{ in}^2/\text{ft}$$


Use #3 bars @ 30" O.C

No. 4, No 5 V

No. 6, No. 18 bottom  
top


Counter fort Design

GRID






### Collinan Typical Retaining Wall



### Total Area of Section

- ①  $1.667' \times 14.5' = 24.17'²$
- ②  $2.083' \times 12.5' \times \frac{1}{2} = 13.02'²$
- ③  $1' \times 2' = 2'²$
- ④  $2.083' \times 2' = 4.167'²$
- ⑤  $1.25' \times 2' = 2.5'²$

Total = 45.857 sq.ft for Collinan wall at highest point



Total Area of Section

$$\begin{aligned} \textcircled{1} &= 10.83 \times .83 = 8.98' \\ \textcircled{2} &= 1.5' \times 1.0833' = 1.624' \\ \textcircled{3} &= 5.5' \times 1.0833' = 5.95' \end{aligned}$$

Totals = 16.56<sup>2</sup> w/o counter fits

$$\textcircled{4} = 5.5 \times 8.9 \times \frac{1}{2} = 24.475$$

Totals = 41.03 ft<sup>2</sup> w/ counter fits

Lower

Volume

Cullinan


$$42' (45857 \text{ sq ft}) = 1925 \text{ ft}^3$$

Ours

$$38665' (16.56 \text{ sq ft}) = 640.3 \text{ ft}^3$$

Ours with Counterbore

$$\begin{aligned}
& 640.3 \text{ ft}^3 + 38665' (5) (41.03) \text{ ft}^2 \\
& = 640.3 \text{ ft}^3 + 136.8 \text{ ft}^3 \\
& = \underline{777.1 \text{ ft}^3}
\end{aligned}$$



GRAPH A.1B  
Moment capacity of rectangular sections.

Table A.2 Arcus of groups of standard bars, in<sup>2</sup>

Bar No.	Number of bars											
	1	2	3	4	5	6	7	8	9	10	11	12
4	0.20	0.39	0.58	0.78	0.98	1.18	1.37	1.57	1.77	1.98	2.16	2.36
5	0.31	0.61	0.91	1.22	1.53	1.84	2.15	2.45	2.76	3.07	3.37	3.68
6	0.44	0.88	1.32	1.77	2.21	2.65	3.09	3.53	3.98	4.42	4.85	5.30
7	0.60	1.20	1.80	2.41	3.01	3.61	4.21	4.81	5.41	6.01	6.61	7.22
8	0.79	1.57	2.35	3.14	3.93	4.71	5.50	6.28	7.07	7.85	8.64	9.43
9	1.03	2.06	3.09	4.00	4.90	5.80	6.60	7.40	8.20	9.00	9.80	10.60
10	1.27	2.53	3.79	5.06	6.33	7.59	8.86	10.12	11.39	12.66	13.92	15.19
11	1.56	3.12	4.68	6.25	7.81	9.37	10.94	12.50	14.06	15.62	17.19	18.75
14	2.25	4.50	6.75	9.00	11.25	13.50	15.75	18.00	20.25	22.50	24.75	27.00
15	4.30	8.60	13.00	16.00	20.00	24.00	28.00	32.00	36.00	40.00	44.00	48.00

Table A.3 Perimeters of groups of standard bars, in.

Bar No.	Number of bars											
	1	2	3	4	5	6	7	8	9	10	11	12
4	1.6	3.1	4.7	6.2	7.8	9.4	11.0	12.6	14.1	15.7	17.2	18.8
5	2.0	3.5	5.0	7.5	9.8	11.8	13.7	15.7	17.7	19.5	21.6	23.6
6	2.4	4.7	7.1	9.4	11.3	14.1	16.5	18.8	21.2	23.6	25.9	28.2
7	2.8	5.5	8.2	11.0	13.7	16.5	19.1	21.0	24.7	27.5	30.2	33.0
8	3.1	6.5	9.4	12.6	15.7	18.9	22.0	25.1	28.2	31.4	34.5	37.7
9	3.5	7.1	10.6	14.2	17.7	21.2	24.8	28.4	31.9	35.4	39.0	42.5
10	4.0	8.0	12.0	16.0	20.0	23.9	27.9	31.9	35.9	39.9	43.9	47.9
11	4.4	8.9	13.3	17.7	22.2	26.6	31.0	35.4	39.9	44.3	48.7	53.2
14	5.3	10.6	16.0	21.3	26.6	31.9	37.2	43.6	47.9	52.2	58.5	63.8
15	7.1	14.2	21.3	28.4	35.5	42.5	49.6	56.7	63.8	70.9	78.0	85.1

Table A.4 Areas of bars in slabs, in<sup>2</sup>/ft


Spacing in.	Bar No.										
	3	4	5	6	7	8	9	10	11		
3	0.44	0.78	1.23	1.77	2.40	3.14	4.00	5.06	6.25		
3½	0.38	0.67	1.05	1.51	2.06	2.69	3.43	4.34	5.36		
4	0.33	0.59	0.92	1.32	1.80	2.36	3.00	3.80	4.68		
4½	0.29	0.52	0.82	1.18	1.60	2.09	2.67	3.37	4.19		
5	0.26	0.47	0.71	1.06	1.44	1.88	2.40	3.04	3.75		
5½	0.24	0.42	0.67	0.96	1.31	1.71	2.18	2.76	3.41		
6	0.22	0.39	0.51	0.88	1.20	1.57	2.00	2.53	3.12		
6½	0.20	0.36	0.57	0.82	1.11	1.45	1.85	2.34	2.89		
7	0.19	0.34	0.53	0.76	1.03	1.35	1.71	2.17	2.68		
7½	0.18	0.31	0.49	0.71	0.96	1.26	1.60	2.02	2.50		
8	0.17	0.29	0.46	0.66	0.90	1.18	1.50	1.89	2.34		
9	0.15	0.26	0.41	0.59	0.80	1.05	1.33	1.69	2.08		
10	0.13	0.24	0.37	0.53	0.72	0.94	1.20	1.52	1.87		
12	0.11	0.20	0.31	0.44	0.60	0.78	1.00	1.27	1.56		

Table A.5 Limiting steel

$f_t$	$f_c$	$\rho_s$	$\rho_c$
40,000	3000	0.85	0.027
	4000	0.85	0.030
	5000	0.80	0.038
	6000	0.75	0.065
	8000	0.70	0.071
50,000	3000	0.85	0.0275
	4000	0.85	0.0307
	5000	0.80	0.0322
	6000	0.75	0.0486
	8000	0.70	0.0520
60,000	3000	0.85	0.0281
	4000	0.85	0.0305
	5000	0.80	0.0325
	6000	0.75	0.0377
	8000	0.70	0.0411
80,000	3000	0.85	0.0141
	4000	0.85	0.0158
	5000	0.80	0.0221
	6000	0.75	0.0229
	8000	0.70	0.0251
80,000	8000	0.65	0.0288

$$\rho_s = 0.258 \frac{f_c}{f_t} \frac{M_u}{V_u} - \rho_c$$


# Appendix E: Cullinan's Retaining Wall Design



# Appendix F: Monthly Man Hour Totals

Winnipeg North High School  
 Gilbena Building Company Contract # 4847  
 Man-Hour Summary

Month	Manhours		Deliverables		Visitors		Orientation		Onup Tests		Inclusions		Logn Time		Project S.V.A.	
	Days	Monthly	Monthly	To Date	Monthly	To Date	Monthly	To Date	Monthly	To Date	Monthly	To Date	Monthly	To Date	Monthly	To Date
Dec 08	22	5780	0758													
Jan 09	20	5872	11840													
Feb 09	20	2672	15732													
Mar 09	22	3484	18616													
Apr 09	22	4160	22776													
May 09	20	2868	25644													
Jun 09	22	4808	30452													
Jul 09	22	3200	33652													
Aug 09	21	3193	36845													
Sept 09	21	2717	39562													
Oct 09	21	2968	42530													
Nov 09	20	3887	46417													
Dec 09	22	3801	50218													
Jan 10	24															



Y:\Manhour Rep - Cert Psychics etc\Monthly Man-Hour Graph.xls

2/1/2010

## Appendix G: Capstone Design Proposal

11/21/2009

Scott MacDonald

Matt Moreau

Ryan Marques

### North High Capstone Design

The original design for the banking on the southeast corner of the building was to cover the banking in rip-rap. As construction began, Gilbane wanted to keep the access road open. This original design of rip-rap could not allow this to happen; as there needed to be more room and Gilbane was concerned about the forces from the construction vehicles so close to the banking. The height of the banking is 62' with a steep drop off, this was an additional concern for the movement of

The solution was to build a cantilevered retaining wall around the banking to accommodate the space for the construction vehicles and the load associated with them. Pictures can be seen on the next page. The design portion of this project will be developing an alternate solution for this problem.

Our retaining wall design will be driven by several factors; ground water and soil conditions, cost and required wall height. The first step in designing the retaining wall will be to get information on the earth's lateral pressure in the area. The basic soil parameters include:

- Soil unit weight
- Angle of internal friction (for sands)
- Cohesion and plasticity indices (for clays)
- The water table location.
- Ledge location

This information should be relatively easy to get since the retaining wall is already constructed on-site.

From here we will be able to size the wall and check for stability; this will include checks for wall overturning, base sliding, and soil bearing capacity failures. After the wall is sized, each wall member will be checked for adequate strength and steel reinforcing can be determined. One area that also needs to be looked at is the necessity to drain the backfill of rainwater and/or groundwater.

Our Solution:



Our group decided to look at a counterfort retaining wall design. A counterfort retaining wall is very similar to a cantilever wall, except that it has one additional feature. This wall has a triangular shaped wall which connects the top of the wall to the back of the footer. This added support wall is hidden within the earthen or gravel backfill of the wall. The footer, retaining wall and support wall must be tied to one another with reinforcing steel. The support walls add a great deal of strength to the retaining wall. The supports make it virtually impossible for the wall to become detached from the footer. Counterforts are usually used for high walls with heights greater than 8 to 12 m. In this case, the wall is only 10' high but this type of design is also used for situations where high lateral pressures occur; where the backfill is heavily surcharged, in this case like North High where there will be a lot of heavy construction vehicles making their way through.

The first step in our design was to size the members, since we already had drawings of the current retaining wall it was relatively easy to realize what the height would need to be. We used the height of the current retaining wall to gather all of our dimensions, such as footing size, wall thickness and support sizes. These dimensions were based on a function of the retaining wall height from equations found in the foundation engineering handbook.

### **Dimensions of Retaining Wall**



Height: 10'

Footer: 4' x 1'

Wall Thickness: 13"

Counterforts: 8" thick; spaced every 3'

### **Counterfort Retaining Wall**



### Design Analysis:

There are three pressures acting on a retaining wall:

**Active earth pressure:** The pressure exerted on the back of the wall

**Bearing pressure:** The vertical bearing pressure of the soil or rock supports the footing

**Passive earth pressure:** Lateral movement of the wall is resisted by passive earth pressure

## Current Retaining Wall



Appendix H: Pictures – North High





















**Appendix I: Tank Replacement Project Pictures**























## Appendix J: Revit Takeoff Sheets

### Structural Foundation Schedule

Family and Type	Volume	Unit	Width
Footing-Rectangular: 5x5x2	46.88	CF	5' - 0"
Footing-Rectangular: 5x5x2	46.88	CF	5' - 0"
Footing-Rectangular: 5x5x2	43.75	CF	5' - 0"
Footing-Rectangular: 6x6x2	63.00	CF	6' - 0"
Footing-Rectangular: 6x6x2	63.00	CF	6' - 0"
Footing-Rectangular: 5x5x2	43.75	CF	5' - 0"
Footing-Rectangular: 9x9x2	131.63	CF	9' - 0"
Footing-Rectangular: 4x4x2	30.00	CF	4' - 0"
Footing-Rectangular: 4x4x2	28.00	CF	4' - 0"
Footing-Rectangular: 4x4x2	26.00	CF	4' - 0"
Footing-Rectangular: 4x4x2	30.00	CF	4' - 0"
Footing-Rectangular: 4x4x2	28.00	CF	4' - 0"
Footing-Rectangular: 4x4x2	28.00	CF	4' - 0"
Footing-Rectangular: 4x4x2	30.00	CF	4' - 0"
Footing-Rectangular: 5x5x2	40.63	CF	5' - 0"
Footing-Rectangular: 5x5x2	43.75	CF	5' - 0"
Footing-Rectangular: 5x5x2	43.75	CF	5' - 0"
Footing-Rectangular: 5x5x2	43.75	CF	5' - 0"
Footing-Rectangular: 5x5x2	40.63	CF	5' - 0"
Footing-Rectangular: 4x4x2	28.33	CF	4' - 0"
Footing-Rectangular: 4x4x2	28.00	CF	4' - 0"
Footing-Rectangular: 4x4x2	28.00	CF	4' - 0"
Footing-Rectangular: 7x7x2	85.75	CF	7' - 0"
Footing-Rectangular: 7x7x2	85.75	CF	7' - 0"
Footing-Rectangular: 9x9x2	141.75	CF	9' - 0"
Footing-Rectangular: 9x9x2	141.75	CF	9' - 0"
Footing-Rectangular: 7x7x2	85.75	CF	7' - 0"
Footing-Rectangular: 8x8x2	112.00	CF	8' - 0"
Footing-Rectangular: 9x9x2	141.75	CF	9' - 0"
Footing-Rectangular: 9x9x2	141.75	CF	9' - 0"
Footing-Rectangular: 4x4x2	28.00	CF	4' - 0"
Footing-Rectangular: 7x7x2	85.75	CF	7' - 0"
Footing-Rectangular: 7x7x2	85.75	CF	7' - 0"
Footing-Rectangular: 7x7x2	85.75	CF	7' - 0"
Footing-Rectangular: 7x7x2	85.75	CF	7' - 0"
Footing-Rectangular: 7x7x2	85.75	CF	7' - 0"





Footing-Rectangular: 8x8x2.5	128.00	CF	8' - 0"
Foundation Slab: 6" Foundation Slab	17497.11	CF	
Footing-Rectangular: 7x7x2	91.88	CF	7' - 0"
Footing-Rectangular: 8x8x2.5	128.00	CF	8' - 0"
Footing-Rectangular: 4x4x2	28.00	CF	4' - 0"
Footing-Rectangular: 7x7x2	85.75	CF	7' - 0"
Footing-Rectangular: 7x7x2	85.75	CF	7' - 0"
Footing-Rectangular: 9x9x2	141.75	CF	9' - 0"
Footing-Rectangular: 9x9x2	141.75	CF	9' - 0"
Footing-Rectangular: 5x5x2	46.88	CF	5' - 0"
Footing-Rectangular: 10x10x3'11"	341.67	CF	10' - 0"
Footing-Rectangular: 10x10x3'11"	341.67	CF	10' - 0"
Footing-Rectangular: 10x10x3'11"	341.67	CF	10' - 0"
Footing-Rectangular: 10x10x3'11"	341.67	CF	10' - 0"
Footing-Rectangular: 6x6x2	63.00	CF	6' - 0"
Footing-Rectangular: 5x5x2	43.75	CF	5' - 0"
Footing-Rectangular: 10x10x3'11"	341.67	CF	10' - 0"
Footing-Rectangular: 10x10x3'11"	341.67	CF	10' - 0"
Footing-Rectangular: 10x10x3'11"	341.67	CF	10' - 0"
Footing-Rectangular: 10x10x3'11"	341.67	CF	10' - 0"
Footing-Rectangular: 7x7x2	85.75	CF	7' - 0"
Footing-Rectangular: 7x7x2	80.50	CF	7' - 0"
Footing-Rectangular: 8x8x2	96.00	CF	8' - 0"
Foundation Slab: 6" Foundation Slab	4711.00	CF	
Foundation Slab: 6" Foundation Slab	18208.19	CF	
Foundation Slab: 6" Foundation Slab	16694.44	CF	
Foundation Slab: 6" Foundation Slab	16694.44	CF	
Foundation Slab: 6" Foundation Slab	12872.40	CF	
Footing-Rectangular: 5x5x2	43.75	CF	5' - 0"
Footing-Rectangular: 6x6x2	54.00	CF	6' - 0"
Footing-Rectangular: 6x6x2	54.00	CF	6' - 0"
Footing-Rectangular: 6x6x2	54.00	CF	6' - 0"
Footing-Rectangular: 6x6x2	54.00	CF	6' - 0"
Footing-Rectangular: 6x6x2	54.00	CF	6' - 0"
Footing-Rectangular: 6x6x2	54.00	CF	6' - 0"
Footing-Rectangular: 6x6x2	54.00	CF	6' - 0"
Footing-Rectangular: 6x6x2	54.00	CF	6' - 0"
Footing-Rectangular: 6x6x2	54.00	CF	6' - 0"
Footing-Rectangular: 6x6x2	54.00	CF	6' - 0"
Footing-Rectangular: 6x6x2	54.00	CF	6' - 0"
Footing-Rectangular: 5x5x2	37.50	CF	5' - 0"

Footing-Rectangular: 5x5x2	43.75	CF	5' - 0"
Footing-Rectangular: 6x6x2	54.00	CF	6' - 0"
Footing-Rectangular: 6x6x2	54.00	CF	6' - 0"
Footing-Rectangular: 6x6x2	54.00	CF	6' - 0"
Footing-Rectangular: 6x6x2	54.00	CF	6' - 0"
Footing-Rectangular: 6x6x2	54.00	CF	6' - 0"
Footing-Rectangular: 6x6x2	54.00	CF	6' - 0"
Footing-Rectangular: 6x6x2	54.00	CF	6' - 0"
Footing-Rectangular: 6x6x2	54.00	CF	6' - 0"
Footing-Rectangular: 6x6x2	54.00	CF	6' - 0"
Footing-Rectangular: 5x5x2	37.50	CF	5' - 0"
Footing-Rectangular: 7x7x2	73.50	CF	7' - 0"
Footing-Rectangular: 7x7x2	73.50	CF	7' - 0"
Footing-Rectangular: 7x7x2	73.50	CF	7' - 0"
Footing-Rectangular: 7x7x2	73.50	CF	7' - 0"
Footing-Rectangular: 7x7x2	73.50	CF	7' - 0"
Footing-Rectangular: 9x9x3'11"	276.75	CF	9' - 0"
Footing-Rectangular: 5x5x2	43.75	CF	5' - 0"
Wall Foundation: Bearing Footing - 36" x 12"	55.06	CF	3' - 0"
Wall Foundation: Bearing Footing - 36" x 12"	40.89	CF	3' - 0"
Wall Foundation: Bearing Footing - 36" x 12"	83.64	CF	3' - 0"
Wall Foundation: Bearing Footing - 36" x 12"	83.64	CF	3' - 0"
Wall Foundation: Bearing Footing - 36" x 12"	46.32	CF	3' - 0"
Wall Foundation: Bearing Footing - 36" x 12"	80.58	CF	3' - 0"
Wall Foundation: Bearing Footing - 36" x 12"	170.25	CF	3' - 0"
Wall Foundation: Bearing Footing - 36" x 12"	37.13	CF	3' - 0"
Wall Foundation: Bearing Footing - 36" x 12"	144.62	CF	
Foundation Slab: 6" Foundation Slab	5931.37	CF	
<b>Total</b>	<b>113385.03</b>	<b>CF</b>	
<b>Total</b>	<b>4200</b>	<b>CY</b>	









HSS-Hollow Structural Section: HSS5X5X5/16	0.62	CF	17' - 4"
HSS-Hollow Structural Section: HSS5X5X5/16	0.62	CF	17' - 4"
HSS-Hollow Structural Section: HSS5X5X5/16	0.62	CF	17' - 4"
HSS-Hollow Structural Section: HSS5X5X5/16	0.65	CF	17' - 4"
HSS-Hollow Structural Section: HSS5X5X5/16	0.39	CF	18' - 3"
HSS-Hollow Structural Section: HSS5X5X5/16	0.62	CF	11' - 4"
HSS-Hollow Structural Section: HSS5X5X5/16	0.63	CF	17' - 4"
HSS-Hollow Structural Section: HSS5X5X5/16	0.63	CF	17' - 4"
HSS-Hollow Structural Section: HSS5X5X5/16	0.62	CF	17' - 4"
HSS-Hollow Structural Section: HSS5X5X5/16	0.62	CF	17' - 4"
HSS-Hollow Structural Section: HSS5X5X5/16	0.63	CF	17' - 4"
HSS-Hollow Structural Section: HSS5X5X5/16	0.63	CF	17' - 4"
HSS-Hollow Structural Section: HSS5X5X5/16	0.62	CF	17' - 4"
HSS-Hollow Structural Section: HSS5X5X5/16	0.02	CF	17' - 4"
W-Wide Flange: W8X10	0.17	CF	1' - 0"
W-Wide Flange: W8X10	0.22	CF	9' - 1 1/2"
W-Wide Flange: W8X10	0.03	CF	11' - 4"
W-Wide Flange: W8X10	0.07	CF	2' - 0"
W-Wide Flange: W8X10	0.23	CF	4' - 0"
W-Wide Flange: W8X18	0.23	CF	7' - 4"
W-Wide Flange: W8X18	0.18	CF	7' - 4"
W-Wide Flange: W8X18	0.18	CF	5' - 9 3/8"
W-Wide Flange: W8X18	0.18	CF	5' - 9 3/8"
W-Wide Flange: W8X18	0.18	CF	5' - 9 3/8"
W-Wide Flange: W8X18	0.28	CF	5' - 9 3/8"
W-Wide Flange: W8X18	0.28	CF	8' - 2 5/8"
W-Wide Flange: W8X18	0.15	CF	8' - 2 5/8"
W-Wide Flange: W10X12	0.15	CF	7' - 0"
W-Wide Flange: W10X12	0.15	CF	7' - 0"
W-Wide Flange: W10X12	0.15	CF	7' - 0"
W-Wide Flange: W10X12	0.15	CF	7' - 0"
W-Wide Flange: W10X12	0.2	CF	7' - 0"
W-Wide Flange: W10X12	0.15	CF	9' - 0"
W-Wide Flange: W10X12	0.2	CF	7' - 0"
W-Wide Flange: W10X12	0.15	CF	9' - 0"
W-Wide Flange: W10X12	0.2	CF	7' - 0"
W-Wide Flange: W10X12	0.15	CF	9' - 0"
W-Wide Flange: W10X12	0.2	CF	7' - 0"
W-Wide Flange: W10X12	0.09	CF	9' - 0"
W-Wide Flange: W10X12	0.14	CF	4' - 4"

W-Wide Flange: W10X12	0.07	CF	6' - 7"
W-Wide Flange: W10X12	0.1	CF	3' - 8"
W-Wide Flange: W10X12	0.09	CF	4' - 6 1/8"
W-Wide Flange: W10X12	0.09	CF	4' - 3 3/8"
W-Wide Flange: W10X12	0.09	CF	4' - 4"
W-Wide Flange: W10X12	0.09	CF	4' - 4"
W-Wide Flange: W10X12	0.1	CF	4' - 4"
W-Wide Flange: W10X12	0.09	CF	4' - 4 5/8"
W-Wide Flange: W10X12	0.09	CF	4' - 4"
W-Wide Flange: W10X12	0.09	CF	4' - 4"
W-Wide Flange: W10X12	0.09	CF	4' - 4"
W-Wide Flange: W10X12	0.09	CF	4' - 4"
W-Wide Flange: W10X12	0.09	CF	4' - 4"
W-Wide Flange: W10X12	0.09	CF	4' - 4"
W-Wide Flange: W10X12	0.09	CF	4' - 4"
W-Wide Flange: W10X12	0.09	CF	4' - 4"
W-Wide Flange: W10X12	0.1	CF	4' - 4"
W-Wide Flange: W10X12	2.66	CF	4' - 6 1/2"
W-Wide Flange: W10X12	2.66	CF	111' - 11 3/4"
W-Wide Flange: W10X12	0.22	CF	111' - 11 3/4"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"







W-Wide Flange: W10X12	0.23	CF	11' - 0 3/8"
W-Wide Flange: W10X12	2.66	CF	11' - 0 3/8"
W-Wide Flange: W10X12	2.66	CF	111' - 11 3/4"
W-Wide Flange: W10X12	0.22	CF	111' - 11 3/4"
W-Wide Flange: W10X12	0.03	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.21	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.22	CF	10' - 0"
W-Wide Flange: W10X12	0.23	CF	10' - 0"
W-Wide Flange: W10X12	0.2	CF	11' - 0 3/8"
W-Wide Flange: W10X12	0.23	CF	11' - 0 3/8"
W-Wide Flange: W10X12	0.23	CF	11' - 0 3/8"
W-Wide Flange: W10X12	0.23	CF	11' - 0 3/8"
W-Wide Flange: W10X12	0.2	CF	11' - 0 3/8"
W-Wide Flange: W10X12	0.23	CF	11' - 0 3/8"
W-Wide Flange: W10X12	0.23	CF	11' - 0 3/8"
W-Wide Flange: W10X12	0.23	CF	11' - 0 3/8"
W-Wide Flange: W10X12	0.23	CF	11' - 0 3/8"
W-Wide Flange: W10X12	0.23	CF	11' - 0 3/8"
W-Wide Flange: W10X12	0.23	CF	11' - 0 3/8"
W-Wide Flange: W10X12	0.23	CF	11' - 0 3/8"
W-Wide Flange: W10X12	0.23	CF	11' - 0 3/8"









W-Wide Flange: W10X15	0.54	CF	18' - 8"
W-Wide Flange: W10X15	0.55	CF	18' - 8"
W-Wide Flange: W10X15	0.54	CF	18' - 10"
W-Wide Flange: W10X15	0.54	CF	18' - 7 3/4"
W-Wide Flange: W10X15	0.54	CF	18' - 8"
W-Wide Flange: W10X15	0.54	CF	18' - 8"
W-Wide Flange: W10X15	0.55	CF	18' - 8"
W-Wide Flange: W10X15	0.54	CF	18' - 10"
W-Wide Flange: W10X15	0.54	CF	18' - 7 3/4"
W-Wide Flange: W10X15	0.54	CF	18' - 8"
W-Wide Flange: W10X15	0.54	CF	18' - 8"
W-Wide Flange: W10X15	0.55	CF	18' - 8"
W-Wide Flange: W10X15	0.54	CF	18' - 10"
W-Wide Flange: W10X15	0.54	CF	18' - 7 3/4"
W-Wide Flange: W10X15	0.54	CF	18' - 8"
W-Wide Flange: W10X15	0.54	CF	18' - 7 3/4"
W-Wide Flange: W10X15	0.54	CF	18' - 8"
W-Wide Flange: W10X15	0.54	CF	18' - 7 3/4"
W-Wide Flange: W10X15	0.54	CF	18' - 8"
W-Wide Flange: W10X15	0.54	CF	18' - 7 3/4"
W-Wide Flange: W10X15	0.54	CF	18' - 8"
W-Wide Flange: W10X15	0.54	CF	18' - 8"
W-Wide Flange: W10X15	0.55	CF	18' - 8"
W-Wide Flange: W10X15	0.54	CF	18' - 10"
W-Wide Flange: W10X15	0.54	CF	18' - 8"
W-Wide Flange: W10X15	0.55	CF	18' - 8"
W-Wide Flange: W10X15	0.55	CF	18' - 10"
W-Wide Flange: W10X15	0.55	CF	18' - 10"
W-Wide Flange: W10X15	0.92	CF	18' - 10"
W-Wide Flange: W10X22	0.92	CF	21' - 4"
W-Wide Flange: W10X22	0.35	CF	21' - 4"
W-Wide Flange: W10X22	0.35	CF	8' - 7"
W-Wide Flange: W10X22	0.38	CF	8' - 7"
W-Wide Flange: W10X22	0.64	CF	9' - 1 1/2"
W-Wide Flange: W10X22	0.81	CF	15' - 0"
W-Wide Flange: W10X22	0.8	CF	18' - 10"
W-Wide Flange: W10X22	0.8	CF	18' - 8"
W-Wide Flange: W10X22	0.8	CF	18' - 8"
W-Wide Flange: W10X22	0.46	CF	18' - 8"
W-Wide Flange: W10X22	0.46	CF	11' - 4"



W-Wide Flange: W10X22	0.79	CF	11' - 4"
W-Wide Flange: W10X22	0.78	CF	18' - 10"
W-Wide Flange: W10X22	0.78	CF	18' - 8"
W-Wide Flange: W10X22	0.78	CF	18' - 8"
W-Wide Flange: W10X22	0.78	CF	18' - 8"
W-Wide Flange: W10X22	0.78	CF	18' - 8"
W-Wide Flange: W10X22	0.78	CF	18' - 8"
W-Wide Flange: W10X22	0.79	CF	18' - 8"
W-Wide Flange: W10X22	0.8	CF	18' - 10"
W-Wide Flange: W10X22	0.8	CF	18' - 8"
W-Wide Flange: W10X22	0.8	CF	18' - 8"
W-Wide Flange: W10X22	0.8	CF	18' - 8"
W-Wide Flange: W10X22	0.78	CF	18' - 8"
W-Wide Flange: W10X22	0.78	CF	18' - 8"
W-Wide Flange: W10X22	0.78	CF	18' - 8"
W-Wide Flange: W10X22	0.79	CF	18' - 8"
W-Wide Flange: W10X22	0.78	CF	18' - 10"
W-Wide Flange: W10X22	0.78	CF	18' - 8"
W-Wide Flange: W10X22	0.78	CF	18' - 8"
W-Wide Flange: W10X22	0.79	CF	18' - 8"
W-Wide Flange: W10X22	0.12	CF	18' - 10"
W-Wide Flange: W12X14	0.12	CF	5' - 0"
W-Wide Flange: W12X14	0.18	CF	5' - 0"
W-Wide Flange: W12X14	0.18	CF	7' - 0"
W-Wide Flange: W12X14	0.12	CF	7' - 0"
W-Wide Flange: W12X14	0.12	CF	5' - 0"
W-Wide Flange: W12X14	0.13	CF	5' - 0"
W-Wide Flange: W12X14	0.13	CF	5' - 0"
W-Wide Flange: W12X14	0.18	CF	5' - 0"
W-Wide Flange: W12X14	0.18	CF	7' - 0"
W-Wide Flange: W12X14	0.18	CF	7' - 0"
W-Wide Flange: W12X14	0.17	CF	7' - 0"
W-Wide Flange: W12X14	0.18	CF	6' - 8"
W-Wide Flange: W12X14	0.17	CF	7' - 0"
W-Wide Flange: W12X14	0.18	CF	6' - 8"
W-Wide Flange: W12X14	0.17	CF	7' - 0"
W-Wide Flange: W12X14	0.18	CF	6' - 8"
W-Wide Flange: W12X14	0.17	CF	7' - 0"
W-Wide Flange: W12X14	0.19	CF	6' - 8"
W-Wide Flange: W12X14	0.19	CF	7' - 4"

W-Wide Flange: W12X14	0.51	CF	7' - 4"
W-Wide Flange: W12X14	0.51	CF	18' - 8"
W-Wide Flange: W12X14	0.51	CF	18' - 8"
W-Wide Flange: W12X14	0.51	CF	18' - 8"
W-Wide Flange: W12X14	0.51	CF	18' - 8"
W-Wide Flange: W12X14	0.51	CF	18' - 8"
W-Wide Flange: W12X14	0.51	CF	18' - 8"
W-Wide Flange: W12X14	0.51	CF	18' - 8"
W-Wide Flange: W12X14	0.51	CF	18' - 8"
W-Wide Flange: W12X14	0.51	CF	18' - 8"
W-Wide Flange: W12X14	0.51	CF	18' - 8"
W-Wide Flange: W12X14	0.51	CF	18' - 8"
W-Wide Flange: W12X14	0.51	CF	18' - 8"
W-Wide Flange: W12X14	0.51	CF	18' - 8"
W-Wide Flange: W12X14	0.24	CF	18' - 8"
W-Wide Flange: W12X14	0.51	CF	9' - 1 1/2"
W-Wide Flange: W12X14	0.51	CF	18' - 8"
W-Wide Flange: W12X14	0.51	CF	18' - 8"
W-Wide Flange: W12X14	0.52	CF	18' - 8"
W-Wide Flange: W12X14	0.51	CF	18' - 10"
W-Wide Flange: W12X14	0.51	CF	18' - 8"
W-Wide Flange: W12X14	0.51	CF	18' - 8"
W-Wide Flange: W12X14	0.51	CF	18' - 8"
W-Wide Flange: W12X14	0.52	CF	18' - 8"
W-Wide Flange: W12X14	0.51	CF	18' - 10"
W-Wide Flange: W12X14	0.51	CF	18' - 8"
W-Wide Flange: W12X14	0.52	CF	18' - 8"
W-Wide Flange: W12X14	0.19	CF	18' - 10"
W-Wide Flange: W12X14	0.19	CF	7' - 4"
W-Wide Flange: W12X14	0.19	CF	7' - 4"
W-Wide Flange: W12X14	0.18	CF	7' - 4"
W-Wide Flange: W12X14	0.18	CF	7' - 4"
W-Wide Flange: W12X14	0.18	CF	7' - 4"
W-Wide Flange: W12X14	0.18	CF	7' - 4"
W-Wide Flange: W12X14	0.18	CF	7' - 4"
W-Wide Flange: W12X14	0.5	CF	7' - 4"
W-Wide Flange: W12X14	0.5	CF	18' - 8"
W-Wide Flange: W12X14	0.5	CF	18' - 8"
W-Wide Flange: W12X14	0.5	CF	18' - 8"
W-Wide Flange: W12X14	0.18	CF	18' - 8"



W-Wide Flange: W12X14	0.5	CF	18' - 8"
W-Wide Flange: W12X14	0.5	CF	18' - 8"
W-Wide Flange: W12X14	0.51	CF	18' - 8"
W-Wide Flange: W12X14	0.5	CF	18' - 8"
W-Wide Flange: W12X14	0.5	CF	18' - 8"
W-Wide Flange: W12X14	0.53	CF	18' - 8"
W-Wide Flange: W12X14	0.62	CF	19' - 8 1/2"
W-Wide Flange: W12X14	0.6	CF	22' - 7 3/8"
W-Wide Flange: W12X14	0.57	CF	21' - 7 3/4"
W-Wide Flange: W12X14	0.51	CF	20' - 8 1/4"
W-Wide Flange: W12X14	0.49	CF	18' - 9"
W-Wide Flange: W12X14	0.46	CF	17' - 9 3/8"
W-Wide Flange: W12X14	0.38	CF	16' - 9 7/8"
W-Wide Flange: W12X16	0.38	CF	12' - 5 3/8"
W-Wide Flange: W12X16	0.31	CF	12' - 5 3/8"
W-Wide Flange: W12X16	0.22	CF	10' - 0"
W-Wide Flange: W12X16	0.67	CF	7' - 3 3/4"
W-Wide Flange: W12X19	0.67	CF	18' - 8"
W-Wide Flange: W12X19	0.67	CF	18' - 8"
W-Wide Flange: W12X19	0.24	CF	18' - 8"
W-Wide Flange: W12X19	0.39	CF	7' - 4"
W-Wide Flange: W12X19	0.99	CF	11' - 4"
W-Wide Flange: W12X19	0.87	CF	26' - 8"
W-Wide Flange: W12X19	0.97	CF	23' - 6 7/8"
W-Wide Flange: W12X19	0.94	CF	25' - 10 3/4"
W-Wide Flange: W12X19	0.91	CF	25' - 1 1/2"
W-Wide Flange: W12X19	1.06	CF	24' - 4 1/4"
W-Wide Flange: W12X26	1.06	CF	21' - 0"
W-Wide Flange: W12X26	1.03	CF	21' - 0"
W-Wide Flange: W12X26	1.05	CF	20' - 8"
W-Wide Flange: W12X26	1.03	CF	21' - 0"
W-Wide Flange: W12X26	1.06	CF	20' - 8"
W-Wide Flange: W12X26	1.06	CF	21' - 0"
W-Wide Flange: W12X26	0.55	CF	21' - 0"
W-Wide Flange: W12X26	0.55	CF	11' - 0"
W-Wide Flange: W12X26	0.58	CF	11' - 0"
W-Wide Flange: W12X26	0.58	CF	11' - 0"
W-Wide Flange: W12X26	1.05	CF	11' - 0"
W-Wide Flange: W12X26	1.05	CF	21' - 0"

W-Wide Flange: W12X26	1.05	CF	21' - 0"
W-Wide Flange: W12X26	1.05	CF	21' - 0"
W-Wide Flange: W12X26	1.41	CF	21' - 0"
W-Wide Flange: W12X26	0.69	CF	27' - 6"
W-Wide Flange: W12X26	0.69	CF	14' - 0"
W-Wide Flange: W12X26	0.69	CF	14' - 0"
W-Wide Flange: W12X26	0.69	CF	14' - 0"
W-Wide Flange: W12X26	0.91	CF	14' - 0"
W-Wide Flange: W12X26	0.85	CF	18' - 2"
W-Wide Flange: W12X26	0.85	CF	17' - 4"
W-Wide Flange: W12X26	0.85	CF	17' - 4"
W-Wide Flange: W12X26	0.85	CF	17' - 4"
W-Wide Flange: W12X26	0.6	CF	17' - 4"
W-Wide Flange: W12X26	0.31	CF	12' - 0"
W-Wide Flange: W12X26	0.92	CF	6' - 0"
W-Wide Flange: W12X26	0.94	CF	18' - 3"
W-Wide Flange: W12X26	0.94	CF	18' - 8"
W-Wide Flange: W12X26	0.94	CF	18' - 8"
W-Wide Flange: W12X26	0.92	CF	18' - 8"
W-Wide Flange: W12X26	0.9	CF	18' - 8"
W-Wide Flange: W12X26	0.95	CF	18' - 3"
W-Wide Flange: W12X26	0.95	CF	18' - 8"
W-Wide Flange: W12X26	0.95	CF	18' - 8"
W-Wide Flange: W12X26	0.95	CF	18' - 8"
W-Wide Flange: W12X26	0.95	CF	18' - 8"
W-Wide Flange: W12X26	0.93	CF	18' - 8"
W-Wide Flange: W12X26	0.95	CF	18' - 3"
W-Wide Flange: W12X26	0.93	CF	18' - 8"
W-Wide Flange: W12X26	0.95	CF	18' - 3"
W-Wide Flange: W12X26	0.93	CF	18' - 8"
W-Wide Flange: W12X26	0.33	CF	18' - 3"
W-Wide Flange: W12X26	0.92	CF	7' - 4"
W-Wide Flange: W12X26	0.92	CF	18' - 8"
W-Wide Flange: W12X26	0.92	CF	18' - 8"
W-Wide Flange: W12X26	0.92	CF	18' - 8"
W-Wide Flange: W12X26	0.92	CF	18' - 8"
W-Wide Flange: W12X26	0.92	CF	18' - 6"
W-Wide Flange: W12X26	0.92	CF	18' - 10"
W-Wide Flange: W12X26	1.31	CF	18' - 8"
W-Wide Flange: W12X26	0.54	CF	26' - 0"

W-Wide Flange: W12X26	0.9	CF	11' - 4"
W-Wide Flange: W12X26	0.9	CF	18' - 3"
W-Wide Flange: W12X26	0.91	CF	18' - 3"
W-Wide Flange: W12X26	0.92	CF	18' - 6"
W-Wide Flange: W12X26	0.96	CF	18' - 3"
W-Wide Flange: W12X26	0.96	CF	18' - 8"
W-Wide Flange: W12X26	0.96	CF	18' - 8"
W-Wide Flange: W12X26	0.95	CF	18' - 8"
W-Wide Flange: W12X26	0.9	CF	18' - 8"
W-Wide Flange: W12X26	0.91	CF	18' - 8"
W-Wide Flange: W12X26	0.92	CF	18' - 6"
W-Wide Flange: W12X26	0.9	CF	18' - 7 3/4"
W-Wide Flange: W12X26	0.92	CF	18' - 3"
W-Wide Flange: W12X26	0.92	CF	18' - 8"
W-Wide Flange: W12X26	0.92	CF	18' - 8"
W-Wide Flange: W12X26	0.92	CF	18' - 8"
W-Wide Flange: W12X26	0.92	CF	18' - 8"
W-Wide Flange: W12X26	0.92	CF	18' - 8"
W-Wide Flange: W12X26	0.46	CF	18' - 7 3/4"
W-Wide Flange: W12X26	0.97	CF	18' - 8"
W-Wide Flange: W12X26	0.96	CF	18' - 8"
W-Wide Flange: W12X26	0.96	CF	18' - 8"
W-Wide Flange: W12X26	0.92	CF	18' - 8"
W-Wide Flange: W12X26	0.92	CF	18' - 3"
W-Wide Flange: W12X26	0.96	CF	18' - 3"
W-Wide Flange: W12X26	0.96	CF	18' - 8"
W-Wide Flange: W12X26	0.97	CF	18' - 8"
W-Wide Flange: W12X26	0.46	CF	18' - 8"
W-Wide Flange: W12X26	0.46	CF	18' - 8"
W-Wide Flange: W12X26	0.97	CF	18' - 8"
W-Wide Flange: W12X26	0.96	CF	18' - 8"
W-Wide Flange: W12X26	0.96	CF	18' - 8"
W-Wide Flange: W12X26	0.92	CF	18' - 8"
W-Wide Flange: W12X26	0.92	CF	18' - 3"
W-Wide Flange: W12X26	0.96	CF	18' - 3"
W-Wide Flange: W12X26	0.96	CF	18' - 8"
W-Wide Flange: W12X26	0.96	CF	18' - 8"
W-Wide Flange: W12X26	0.97	CF	18' - 8"
W-Wide Flange: W12X26	0.46	CF	18' - 8"
W-Wide Flange: W12X26	0.79	CF	18' - 8"

W-Wide Flange: W12X26	0.92	CF	15' - 10 3/8"
W-Wide Flange: W12X26	0.96	CF	18' - 3"
W-Wide Flange: W12X26	0.96	CF	18' - 8"
W-Wide Flange: W12X26	0.96	CF	18' - 8"
W-Wide Flange: W12X26	0.97	CF	18' - 8"
W-Wide Flange: W12X26	0.95	CF	18' - 8"
W-Wide Flange: W12X26	0.9	CF	18' - 8"
W-Wide Flange: W12X26	0.92	CF	18' - 3"
W-Wide Flange: W12X26	0.92	CF	18' - 8"
W-Wide Flange: W12X26	0.92	CF	18' - 8"
W-Wide Flange: W12X26	0.92	CF	18' - 8"
W-Wide Flange: W12X26	0.92	CF	18' - 8"
W-Wide Flange: W12X26	0.95	CF	18' - 8"
W-Wide Flange: W12X26	0.97	CF	18' - 8"
W-Wide Flange: W12X26	0.96	CF	18' - 8"
W-Wide Flange: W12X26	0.96	CF	18' - 8"
W-Wide Flange: W12X26	0.92	CF	18' - 8"
W-Wide Flange: W12X26	0.92	CF	18' - 3"
W-Wide Flange: W12X26	0.96	CF	18' - 3"
W-Wide Flange: W12X26	0.96	CF	18' - 8"
W-Wide Flange: W12X26	0.97	CF	18' - 8"
W-Wide Flange: W12X26	0.95	CF	18' - 8"
W-Wide Flange: W12X26	0.95	CF	18' - 8"
W-Wide Flange: W12X26	0.97	CF	18' - 8"
W-Wide Flange: W12X26	0.96	CF	18' - 8"
W-Wide Flange: W12X26	0.96	CF	18' - 8"
W-Wide Flange: W12X26	0.92	CF	18' - 8"
W-Wide Flange: W12X26	0.92	CF	18' - 3"
W-Wide Flange: W12X26	0.96	CF	18' - 3"
W-Wide Flange: W12X26	0.96	CF	18' - 8"
W-Wide Flange: W12X26	0.96	CF	18' - 8"
W-Wide Flange: W12X26	0.97	CF	18' - 8"
W-Wide Flange: W12X26	0.95	CF	18' - 8"
W-Wide Flange: W12X26	0.92	CF	18' - 8"
W-Wide Flange: W12X26	0.91	CF	18' - 7 3/4"
W-Wide Flange: W12X26	0.92	CF	18' - 6"
W-Wide Flange: W12X26	0.91	CF	18' - 7 3/4"
W-Wide Flange: W12X26	1.1	CF	18' - 6"
W-Wide Flange: W12X30	1.1	CF	18' - 8"
W-Wide Flange: W12X30	1.1	CF	18' - 8"

W-Wide Flange: W12X30	1.1	CF	18' - 8"
W-Wide Flange: W12X30	1.3	CF	18' - 8"
W-Wide Flange: W12X35	1.3	CF	18' - 8"
W-Wide Flange: W12X35	1.05	CF	18' - 8"
W-Wide Flange: W12X40	1.05	CF	14' - 0"
W-Wide Flange: W12X40	1.05	CF	14' - 0"
W-Wide Flange: W12X40	1.05	CF	14' - 0"
W-Wide Flange: W12X40	1.05	CF	14' - 0"
W-Wide Flange: W12X40	1.05	CF	14' - 0"
W-Wide Flange: W12X40	1.05	CF	14' - 0"
W-Wide Flange: W12X40	1.05	CF	14' - 0"
W-Wide Flange: W12X40	1.05	CF	14' - 0"
W-Wide Flange: W12X40	1.05	CF	14' - 0"
W-Wide Flange: W12X40	1.05	CF	14' - 0"
W-Wide Flange: W12X40	0.58	CF	14' - 0"
W-Wide Flange: W14X22	0.58	CF	13' - 8"
W-Wide Flange: W14X22	0.58	CF	13' - 8"
W-Wide Flange: W14X22	0.58	CF	13' - 8"
W-Wide Flange: W14X22	0.6	CF	13' - 8"
W-Wide Flange: W14X22	0.6	CF	13' - 8"
W-Wide Flange: W14X22	0.9	CF	13' - 8"
W-Wide Flange: W14X22	0.9	CF	21' - 0"
W-Wide Flange: W14X22	0.88	CF	21' - 0"
W-Wide Flange: W14X22	0.89	CF	20' - 8"
W-Wide Flange: W14X22	0.87	CF	21' - 0"
W-Wide Flange: W14X22	0.9	CF	20' - 8"
W-Wide Flange: W14X22	0.9	CF	21' - 0"
W-Wide Flange: W14X22	0.88	CF	21' - 0"
W-Wide Flange: W14X22	0.89	CF	20' - 8"
W-Wide Flange: W14X22	0.87	CF	21' - 0"
W-Wide Flange: W14X22	0.9	CF	20' - 8"
W-Wide Flange: W14X22	0.9	CF	21' - 0"
W-Wide Flange: W14X22	0.88	CF	21' - 0"
W-Wide Flange: W14X22	0.89	CF	20' - 8"
W-Wide Flange: W14X22	0.87	CF	21' - 0"
W-Wide Flange: W14X22	0.9	CF	20' - 8"
W-Wide Flange: W14X22	0.9	CF	21' - 0"
W-Wide Flange: W14X22	0.88	CF	21' - 0"
W-Wide Flange: W14X22	0.89	CF	20' - 8"
W-Wide Flange: W14X22	0.87	CF	21' - 0"
W-Wide Flange: W14X22	0.9	CF	20' - 8"
W-Wide Flange: W14X22	0.9	CF	21' - 0"
W-Wide Flange: W14X22	0.88	CF	21' - 0"
W-Wide Flange: W14X22	0.89	CF	20' - 8"



W-Wide Flange: W14X22	0.87	CF	21' - 0"
W-Wide Flange: W14X22	0.87	CF	20' - 8"
W-Wide Flange: W14X22	0.89	CF	20' - 8"
W-Wide Flange: W14X22	0.87	CF	21' - 0"
W-Wide Flange: W14X22	0.88	CF	20' - 8"
W-Wide Flange: W14X22	0.89	CF	20' - 8"
W-Wide Flange: W14X22	0.88	CF	21' - 0"
W-Wide Flange: W14X22	0.89	CF	20' - 8"
W-Wide Flange: W14X22	0.87	CF	21' - 0"
W-Wide Flange: W14X22	0.87	CF	20' - 8"
W-Wide Flange: W14X22	0.88	CF	20' - 8"
W-Wide Flange: W14X22	0.89	CF	20' - 8"
W-Wide Flange: W14X22	0.89	CF	21' - 0"
W-Wide Flange: W14X22	0.91	CF	21' - 0"
W-Wide Flange: W14X22	0.91	CF	21' - 4"
W-Wide Flange: W14X22	0.91	CF	21' - 4"
W-Wide Flange: W14X22	0.91	CF	21' - 4"
W-Wide Flange: W14X22	0.91	CF	21' - 4"
W-Wide Flange: W14X22	0.89	CF	21' - 4"
W-Wide Flange: W14X22	0.89	CF	21' - 0"
W-Wide Flange: W14X22	0.89	CF	21' - 0"
W-Wide Flange: W14X22	0.89	CF	21' - 0"
W-Wide Flange: W14X22	0.89	CF	21' - 0"
W-Wide Flange: W14X22	0.89	CF	21' - 0"
W-Wide Flange: W14X22	0.89	CF	21' - 0"
W-Wide Flange: W14X22	0.89	CF	21' - 0"
W-Wide Flange: W14X22	0.89	CF	21' - 0"
W-Wide Flange: W14X22	0.89	CF	21' - 0"
W-Wide Flange: W14X22	0.91	CF	21' - 0"
W-Wide Flange: W14X22	0.91	CF	21' - 4"
W-Wide Flange: W14X22	0.91	CF	21' - 4"
W-Wide Flange: W14X22	0.91	CF	21' - 4"
W-Wide Flange: W14X22	0.91	CF	21' - 4"
W-Wide Flange: W14X22	0.89	CF	21' - 4"
W-Wide Flange: W14X22	0.89	CF	21' - 0"
W-Wide Flange: W14X22	0.89	CF	21' - 0"
W-Wide Flange: W14X22	0.89	CF	21' - 0"
W-Wide Flange: W14X22	0.89	CF	21' - 0"
W-Wide Flange: W14X22	0.89	CF	21' - 0"





W-Wide Flange: W14X22	0.73	CF	17' - 4"
W-Wide Flange: W14X22	0.73	CF	17' - 4"
W-Wide Flange: W14X22	0.74	CF	17' - 4"
W-Wide Flange: W14X22	0.73	CF	17' - 4"
W-Wide Flange: W14X22	0.73	CF	17' - 4"
W-Wide Flange: W14X22	0.74	CF	17' - 4"
W-Wide Flange: W14X22	0.73	CF	17' - 4"
W-Wide Flange: W14X22	0.73	CF	17' - 4"
W-Wide Flange: W14X22	0.73	CF	17' - 4"
W-Wide Flange: W14X22	0.74	CF	17' - 4"
W-Wide Flange: W14X22	0.73	CF	17' - 4"
W-Wide Flange: W14X22	0.73	CF	17' - 4"
W-Wide Flange: W14X22	0.74	CF	17' - 4"
W-Wide Flange: W14X22	0.72	CF	17' - 4"
W-Wide Flange: W14X22	0.72	CF	17' - 4"
W-Wide Flange: W14X22	0.72	CF	17' - 4"
W-Wide Flange: W14X22	0.72	CF	17' - 4"
W-Wide Flange: W14X22	0.74	CF	17' - 4"
W-Wide Flange: W14X22	0.75	CF	17' - 7 1/4"
W-Wide Flange: W14X22	0.77	CF	17' - 9 5/8"
W-Wide Flange: W14X22	0.77	CF	18' - 2"
W-Wide Flange: W14X22	0.77	CF	18' - 2"
W-Wide Flange: W14X22	0.73	CF	18' - 2"
W-Wide Flange: W14X22	0.73	CF	17' - 4"
W-Wide Flange: W14X22	0.73	CF	17' - 4"
W-Wide Flange: W14X22	0.73	CF	17' - 4"
W-Wide Flange: W14X22	0.73	CF	17' - 4"
W-Wide Flange: W14X22	0.73	CF	17' - 4"
W-Wide Flange: W14X22	0.7	CF	17' - 4"
W-Wide Flange: W14X22	0.65	CF	16' - 6 1/2"
W-Wide Flange: W14X22	0.77	CF	15' - 4 1/4"
W-Wide Flange: W14X22	1.26	CF	18' - 2"
W-Wide Flange: W14X22	0.74	CF	29' - 3"
W-Wide Flange: W14X22	0.75	CF	17' - 7 1/4"
W-Wide Flange: W14X22	0.74	CF	17' - 9 5/8"
W-Wide Flange: W14X22	1.25	CF	17' - 8 1/2"
W-Wide Flange: W14X22	1.26	CF	29' - 3"
W-Wide Flange: W14X22	1.26	CF	29' - 3"
W-Wide Flange: W14X22	1.26	CF	29' - 3"

W-Wide Flange: W14X22	1.23	CF	29' - 3"
W-Wide Flange: W14X22	1.21	CF	28' - 7 1/4"
W-Wide Flange: W14X22	1.18	CF	27' - 11 1/2"
W-Wide Flange: W14X22	0.22	CF	27' - 3 3/4"
W-Wide Flange: W14X22	0.83	CF	4' - 6"
W-Wide Flange: W14X22	0.83	CF	19' - 9 7/8"
W-Wide Flange: W14X22	0.83	CF	19' - 9 7/8"
W-Wide Flange: W14X22	0.83	CF	19' - 9 7/8"
W-Wide Flange: W14X22	0.83	CF	19' - 9 7/8"
W-Wide Flange: W14X22	0.83	CF	19' - 9 7/8"
W-Wide Flange: W14X22	0.83	CF	19' - 9 7/8"
W-Wide Flange: W14X22	0.83	CF	19' - 9 7/8"
W-Wide Flange: W14X22	0.83	CF	19' - 9 7/8"
W-Wide Flange: W14X22	0.83	CF	19' - 9 7/8"
W-Wide Flange: W14X22	0.83	CF	19' - 9 7/8"
W-Wide Flange: W14X22	0.83	CF	19' - 9 7/8"
W-Wide Flange: W14X22	0.85	CF	19' - 9 7/8"
W-Wide Flange: W14X22	0.85	CF	20' - 4 1/2"
W-Wide Flange: W14X22	0.85	CF	20' - 4 1/2"
W-Wide Flange: W14X22	0.83	CF	20' - 4 1/2"
W-Wide Flange: W14X22	0.85	CF	20' - 4 1/2"
W-Wide Flange: W14X22	0.85	CF	20' - 4 1/2"
W-Wide Flange: W14X22	0.85	CF	20' - 4 1/2"
W-Wide Flange: W14X22	0.85	CF	20' - 4 1/2"
W-Wide Flange: W14X22	0.85	CF	20' - 4 1/2"
W-Wide Flange: W14X22	0.85	CF	20' - 4 1/2"
W-Wide Flange: W14X22	0.85	CF	20' - 4 1/2"
W-Wide Flange: W14X22	0.85	CF	20' - 4 1/2"
W-Wide Flange: W14X22	0.85	CF	20' - 4 1/2"
W-Wide Flange: W14X22	1.24	CF	20' - 4 1/2"
W-Wide Flange: W14X30	1.22	CF	21' - 4"
W-Wide Flange: W14X30	0.38	CF	21' - 0"
W-Wide Flange: W14X30	1.24	CF	7' - 0"
W-Wide Flange: W14X30	1.2	CF	21' - 4"
W-Wide Flange: W14X30	1.22	CF	20' - 8"

W-Wide Flange: W14X30	1.2	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	20' - 8"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.63	CF	21' - 0"
W-Wide Flange: W14X30	1.24	CF	28' - 0"
W-Wide Flange: W14X30	1.24	CF	21' - 4"
W-Wide Flange: W14X30	2.05	CF	21' - 4"
W-Wide Flange: W14X30	2.03	CF	35' - 0"
W-Wide Flange: W14X30	2.03	CF	34' - 8"
W-Wide Flange: W14X30	0.81	CF	34' - 8"
W-Wide Flange: W14X30	0.71	CF	14' - 0"
W-Wide Flange: W14X30	0.81	CF	12' - 0"
W-Wide Flange: W14X30	0.71	CF	14' - 0"
W-Wide Flange: W14X30	1.24	CF	12' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 4"
W-Wide Flange: W14X30	0.38	CF	21' - 0"
W-Wide Flange: W14X30	1.24	CF	7' - 0"
W-Wide Flange: W14X30	1.2	CF	21' - 4"
W-Wide Flange: W14X30	1.22	CF	20' - 8"
W-Wide Flange: W14X30	1.2	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	20' - 8"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	2.03	CF	21' - 0"
W-Wide Flange: W14X30	2.03	CF	34' - 8"
W-Wide Flange: W14X30	1.24	CF	34' - 8"
W-Wide Flange: W14X30	1.22	CF	21' - 4"
W-Wide Flange: W14X30	0.38	CF	21' - 0"
W-Wide Flange: W14X30	1.24	CF	7' - 0"
W-Wide Flange: W14X30	1.2	CF	21' - 4"
W-Wide Flange: W14X30	1.22	CF	20' - 8"
W-Wide Flange: W14X30	1.2	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	20' - 8"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	2.03	CF	21' - 0"

W-Wide Flange: W14X30	2.03	CF	34' - 8"
W-Wide Flange: W14X30	0.81	CF	34' - 8"
W-Wide Flange: W14X30	0.71	CF	14' - 0"
W-Wide Flange: W14X30	0.81	CF	12' - 0"
W-Wide Flange: W14X30	0.71	CF	14' - 0"
W-Wide Flange: W14X30	1.24	CF	12' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 4"
W-Wide Flange: W14X30	0.38	CF	21' - 0"
W-Wide Flange: W14X30	1.24	CF	7' - 0"
W-Wide Flange: W14X30	1.2	CF	21' - 4"
W-Wide Flange: W14X30	1.22	CF	20' - 8"
W-Wide Flange: W14X30	1.2	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	20' - 8"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	2.03	CF	21' - 0"
W-Wide Flange: W14X30	2.03	CF	34' - 8"
W-Wide Flange: W14X30	1.21	CF	34' - 8"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	0.38	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	7' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	0.8	CF	21' - 0"
W-Wide Flange: W14X30	0.81	CF	14' - 0"
W-Wide Flange: W14X30	1.21	CF	14' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	0.38	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	7' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"

W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	0.8	CF	21' - 0"
W-Wide Flange: W14X30	0.81	CF	14' - 0"
W-Wide Flange: W14X30	1.22	CF	14' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	0.38	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	7' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	1.22	CF	21' - 0"
W-Wide Flange: W14X30	0.8	CF	21' - 0"
W-Wide Flange: W14X30	0.81	CF	14' - 0"
W-Wide Flange: W14X30	1.04	CF	14' - 0"
W-Wide Flange: W14X30	0.98	CF	18' - 2"
W-Wide Flange: W14X30	1	CF	17' - 4"
W-Wide Flange: W14X30	1	CF	17' - 4"
W-Wide Flange: W14X30	1.01	CF	17' - 4"
W-Wide Flange: W14X30	0.69	CF	17' - 6 1/4"



W-Wide Flange: W16X26	0.32	CF	14' - 0"
W-Wide Flange: W16X26	1.08	CF	7' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 4"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 4"
W-Wide Flange: W16X26	1.06	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 4"
W-Wide Flange: W16X26	1.03	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"

W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 4"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.09	CF	21' - 4"
W-Wide Flange: W16X26	1.07	CF	21' - 4"
W-Wide Flange: W16X26	1.07	CF	21' - 0"
W-Wide Flange: W16X26	1.09	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.07	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	20' - 8"
W-Wide Flange: W16X26	1.07	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.07	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"

W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	20' - 8"
W-Wide Flange: W16X26	0.69	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	14' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 4"
W-Wide Flange: W16X26	1.06	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 0"

W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 4"
W-Wide Flange: W16X26	1.03	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 4"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.09	CF	21' - 4"
W-Wide Flange: W16X26	1.07	CF	21' - 4"
W-Wide Flange: W16X26	1.07	CF	21' - 0"
W-Wide Flange: W16X26	1.09	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.07	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	20' - 8"
W-Wide Flange: W16X26	1.07	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 4"

W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.07	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	20' - 8"
W-Wide Flange: W16X26	0.69	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	14' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 4"
W-Wide Flange: W16X26	1.06	CF	21' - 4"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 4"
W-Wide Flange: W16X26	1.06	CF	21' - 4"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 4"
W-Wide Flange: W16X26	1.06	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 0"

W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.04	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 4"
W-Wide Flange: W16X26	1.03	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 4"
W-Wide Flange: W16X26	1.08	CF	21' - 0"

W-Wide Flange: W16X26	1.09	CF	21' - 4"
W-Wide Flange: W16X26	1.07	CF	21' - 4"
W-Wide Flange: W16X26	1.07	CF	21' - 0"
W-Wide Flange: W16X26	1.09	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.07	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	20' - 8"
W-Wide Flange: W16X26	1.07	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.07	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 0"

W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	20' - 8"
W-Wide Flange: W16X26	0.69	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	14' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	21' - 4"
W-Wide Flange: W16X26	1.07	CF	21' - 4"
W-Wide Flange: W16X26	1.07	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 4"
W-Wide Flange: W16X26	1.06	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.03	CF	21' - 0"



W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.04	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 4"
W-Wide Flange: W16X26	1.03	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 4"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.09	CF	21' - 4"
W-Wide Flange: W16X26	1.07	CF	21' - 4"
W-Wide Flange: W16X26	1.07	CF	21' - 0"
W-Wide Flange: W16X26	1.09	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.07	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	20' - 8"
W-Wide Flange: W16X26	1.07	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 0"

W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.07	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	20' - 8"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	20' - 8"
W-Wide Flange: W16X26	1.03	CF	21' - 0"
W-Wide Flange: W16X26	1.07	CF	20' - 8"
W-Wide Flange: W16X26	0.69	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	14' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 4"
W-Wide Flange: W16X26	1.06	CF	21' - 4"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	1.08	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 4"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"



















W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.05	CF	21' - 0"
W-Wide Flange: W16X26	1.06	CF	21' - 0"
W-Wide Flange: W16X26	0.92	CF	21' - 0"
W-Wide Flange: W16X26	0.94	CF	18' - 3"
W-Wide Flange: W16X26	0.94	CF	18' - 8"
W-Wide Flange: W16X26	0.94	CF	18' - 8"
W-Wide Flange: W16X26	0.94	CF	18' - 8"
W-Wide Flange: W16X26	1.49	CF	18' - 8"
W-Wide Flange: W16X26	0.94	CF	29' - 3"
W-Wide Flange: W16X26	0.9	CF	18' - 8"
W-Wide Flange: W16X26	0.54	CF	18' - 3"
W-Wide Flange: W16X26	0.75	CF	11' - 4"
W-Wide Flange: W16X26	0.75	CF	15' - 3"
W-Wide Flange: W16X26	0.75	CF	15' - 3"
W-Wide Flange: W16X26	0.75	CF	15' - 3"
W-Wide Flange: W16X26	0.75	CF	15' - 3"
W-Wide Flange: W16X26	0.86	CF	15' - 3"
W-Wide Flange: W16X26	0.86	CF	17' - 4"
W-Wide Flange: W16X26	0.9	CF	17' - 4"
W-Wide Flange: W16X26	0.88	CF	18' - 3"
W-Wide Flange: W16X26	0.85	CF	17' - 6 1/4"
W-Wide Flange: W16X26	0.85	CF	17' - 4"
W-Wide Flange: W16X26	1.25	CF	17' - 4"
W-Wide Flange: W16X31	1.25	CF	21' - 0"
W-Wide Flange: W16X31	1.25	CF	21' - 0"
W-Wide Flange: W16X31	1.25	CF	21' - 0"
W-Wide Flange: W16X31	1.25	CF	21' - 0"

W-Wide Flange: W16X31	1.25	CF	21' - 0"
W-Wide Flange: W16X31	1.25	CF	21' - 0"
W-Wide Flange: W16X31	1.25	CF	21' - 0"
W-Wide Flange: W16X31	1.19	CF	21' - 0"
W-Wide Flange: W16X31	1.09	CF	19' - 9 1/8"
W-Wide Flange: W16X31	2.08	CF	18' - 2"
W-Wide Flange: W16X36	2.07	CF	29' - 7"
W-Wide Flange: W16X36	2.08	CF	29' - 7"
W-Wide Flange: W16X36	2.1	CF	29' - 7"
W-Wide Flange: W16X36	2.1	CF	29' - 7"
W-Wide Flange: W16X36	2.1	CF	29' - 7"
W-Wide Flange: W16X36	2.1	CF	29' - 7"
W-Wide Flange: W16X36	2.1	CF	29' - 7"
W-Wide Flange: W16X36	2.1	CF	29' - 7"
W-Wide Flange: W16X36	2.1	CF	29' - 7"
W-Wide Flange: W16X36	2.1	CF	29' - 7"
W-Wide Flange: W16X36	0.93	CF	29' - 7"
W-Wide Flange: W18X35	0.93	CF	14' - 0"
W-Wide Flange: W18X35	0.93	CF	14' - 0"
W-Wide Flange: W18X35	0.93	CF	14' - 0"
W-Wide Flange: W18X35	0.93	CF	14' - 0"
W-Wide Flange: W18X35	0.91	CF	14' - 0"
W-Wide Flange: W18X35	0.89	CF	14' - 0"
W-Wide Flange: W18X35	0.91	CF	13' - 8"
W-Wide Flange: W18X35	1.43	CF	14' - 0"
W-Wide Flange: W18X35	1.43	CF	21' - 0"
W-Wide Flange: W18X35	1.4	CF	21' - 0"
W-Wide Flange: W18X35	1.43	CF	20' - 8"
W-Wide Flange: W18X35	1.4	CF	21' - 0"
W-Wide Flange: W18X35	1.42	CF	20' - 8"
W-Wide Flange: W18X35	1.42	CF	21' - 0"
W-Wide Flange: W18X35	1.41	CF	21' - 0"
W-Wide Flange: W18X35	1.42	CF	21' - 0"
W-Wide Flange: W18X35	1.42	CF	21' - 0"
W-Wide Flange: W18X35	1.41	CF	21' - 0"
W-Wide Flange: W18X35	0.93	CF	21' - 0"
W-Wide Flange: W18X35	0.93	CF	14' - 0"
W-Wide Flange: W18X35	0.93	CF	14' - 0"
W-Wide Flange: W18X35	0.93	CF	14' - 0"
W-Wide Flange: W18X35	0.93	CF	14' - 0"

W-Wide Flange: W18X35	0.91	CF	14' - 0"
W-Wide Flange: W18X35	0.89	CF	14' - 0"
W-Wide Flange: W18X35	0.91	CF	13' - 8"
W-Wide Flange: W18X35	1.43	CF	14' - 0"
W-Wide Flange: W18X35	1.43	CF	21' - 0"
W-Wide Flange: W18X35	1.4	CF	21' - 0"
W-Wide Flange: W18X35	1.43	CF	20' - 8"
W-Wide Flange: W18X35	1.4	CF	21' - 0"
W-Wide Flange: W18X35	0.93	CF	20' - 8"
W-Wide Flange: W18X35	0.93	CF	14' - 0"
W-Wide Flange: W18X35	0.93	CF	14' - 0"
W-Wide Flange: W18X35	0.93	CF	14' - 0"
W-Wide Flange: W18X35	0.93	CF	14' - 0"
W-Wide Flange: W18X35	0.91	CF	14' - 0"
W-Wide Flange: W18X35	0.89	CF	14' - 0"
W-Wide Flange: W18X35	0.91	CF	13' - 8"
W-Wide Flange: W18X35	1.43	CF	14' - 0"
W-Wide Flange: W18X35	1.43	CF	21' - 0"
W-Wide Flange: W18X35	1.4	CF	21' - 0"
W-Wide Flange: W18X35	1.43	CF	20' - 8"
W-Wide Flange: W18X35	1.43	CF	21' - 0"
W-Wide Flange: W18X35	1.42	CF	20' - 8"
W-Wide Flange: W18X35	1.42	CF	21' - 0"
W-Wide Flange: W18X35	1.41	CF	21' - 0"
W-Wide Flange: W18X35	1.42	CF	21' - 0"
W-Wide Flange: W18X35	1.42	CF	21' - 0"
W-Wide Flange: W18X35	1.41	CF	21' - 0"
W-Wide Flange: W18X35	0.93	CF	21' - 0"
W-Wide Flange: W18X35	0.93	CF	14' - 0"
W-Wide Flange: W18X35	0.93	CF	14' - 0"
W-Wide Flange: W18X35	0.93	CF	14' - 0"
W-Wide Flange: W18X35	0.93	CF	14' - 0"
W-Wide Flange: W18X35	0.91	CF	14' - 0"
W-Wide Flange: W18X35	0.89	CF	14' - 0"
W-Wide Flange: W18X35	0.91	CF	13' - 8"
W-Wide Flange: W18X35	1.43	CF	14' - 0"
W-Wide Flange: W18X35	1.43	CF	21' - 0"
W-Wide Flange: W18X35	1.4	CF	21' - 0"
W-Wide Flange: W18X35	1.43	CF	20' - 8"
W-Wide Flange: W18X35	1.43	CF	21' - 0"

W-Wide Flange: W18X35	0.91	CF	20' - 8"
W-Wide Flange: W18X35	1.42	CF	14' - 0"
W-Wide Flange: W18X35	1.43	CF	21' - 0"
W-Wide Flange: W18X35	0.93	CF	21' - 0"
W-Wide Flange: W18X35	0.93	CF	14' - 0"
W-Wide Flange: W18X35	0.93	CF	14' - 0"
W-Wide Flange: W18X35	0.93	CF	14' - 0"
W-Wide Flange: W18X35	0.92	CF	14' - 0"
W-Wide Flange: W18X35	0.89	CF	14' - 0"
W-Wide Flange: W18X35	1.42	CF	13' - 8"
W-Wide Flange: W18X35	1.42	CF	21' - 0"
W-Wide Flange: W18X35	1.41	CF	21' - 0"
W-Wide Flange: W18X35	1.43	CF	21' - 0"
W-Wide Flange: W18X35	1.43	CF	21' - 0"
W-Wide Flange: W18X35	1.43	CF	21' - 0"
W-Wide Flange: W18X35	0.91	CF	21' - 0"
W-Wide Flange: W18X35	1.42	CF	14' - 0"
W-Wide Flange: W18X35	1.43	CF	21' - 0"
W-Wide Flange: W18X35	0.93	CF	21' - 0"
W-Wide Flange: W18X35	0.93	CF	14' - 0"
W-Wide Flange: W18X35	0.93	CF	14' - 0"
W-Wide Flange: W18X35	0.93	CF	14' - 0"
W-Wide Flange: W18X35	0.92	CF	14' - 0"
W-Wide Flange: W18X35	0.89	CF	14' - 0"
W-Wide Flange: W18X35	1.42	CF	13' - 8"
W-Wide Flange: W18X35	1.42	CF	21' - 0"
W-Wide Flange: W18X35	1.41	CF	21' - 0"
W-Wide Flange: W18X35	1.43	CF	21' - 0"
W-Wide Flange: W18X35	1.43	CF	21' - 0"
W-Wide Flange: W18X35	1.43	CF	21' - 0"
W-Wide Flange: W18X35	0.95	CF	21' - 0"
W-Wide Flange: W18X35	1.43	CF	14' - 0"
W-Wide Flange: W18X35	1.43	CF	21' - 0"
W-Wide Flange: W18X35	0.93	CF	21' - 0"
W-Wide Flange: W18X35	0.93	CF	14' - 0"
W-Wide Flange: W18X35	0.93	CF	14' - 0"
W-Wide Flange: W18X35	0.93	CF	14' - 0"
W-Wide Flange: W18X35	0.92	CF	14' - 0"
W-Wide Flange: W18X35	0.9	CF	14' - 0"
W-Wide Flange: W18X35	1.42	CF	13' - 8"

W-Wide Flange: W18X35	1.42	CF	21' - 0"
W-Wide Flange: W18X35	1.41	CF	21' - 0"
W-Wide Flange: W18X35	1.43	CF	21' - 0"
W-Wide Flange: W18X35	1.43	CF	21' - 0"
W-Wide Flange: W18X35	1.43	CF	21' - 0"
W-Wide Flange: W18X35	0.95	CF	21' - 0"
W-Wide Flange: W18X35	1.43	CF	14' - 0"
W-Wide Flange: W18X35	1.43	CF	21' - 0"
W-Wide Flange: W18X35	0.93	CF	21' - 0"
W-Wide Flange: W18X35	0.93	CF	14' - 0"
W-Wide Flange: W18X35	0.93	CF	14' - 0"
W-Wide Flange: W18X35	0.93	CF	14' - 0"
W-Wide Flange: W18X35	0.92	CF	14' - 0"
W-Wide Flange: W18X35	0.9	CF	14' - 0"
W-Wide Flange: W18X35	1.42	CF	13' - 8"
W-Wide Flange: W18X35	1.42	CF	21' - 0"
W-Wide Flange: W18X35	1.41	CF	21' - 0"
W-Wide Flange: W18X35	1.43	CF	21' - 0"
W-Wide Flange: W18X35	1.43	CF	21' - 0"
W-Wide Flange: W18X35	1.43	CF	21' - 0"
W-Wide Flange: W18X35	0.72	CF	21' - 0"
W-Wide Flange: W18X35	1.15	CF	11' - 4"
W-Wide Flange: W18X35	1.24	CF	17' - 4"
W-Wide Flange: W18X35	1.24	CF	18' - 8"
W-Wide Flange: W18X35	1.22	CF	18' - 8"
W-Wide Flange: W18X35	1.22	CF	18' - 2"
W-Wide Flange: W18X35	1.22	CF	18' - 2"
W-Wide Flange: W18X35	1.22	CF	18' - 2"
W-Wide Flange: W18X35	1.22	CF	18' - 2"
W-Wide Flange: W18X35	1.22	CF	18' - 2"
W-Wide Flange: W18X35	1.22	CF	18' - 2"
W-Wide Flange: W18X35	1.16	CF	18' - 2"
W-Wide Flange: W18X35	1.17	CF	17' - 4"
W-Wide Flange: W18X35	1.17	CF	17' - 4"
W-Wide Flange: W18X35	1.16	CF	17' - 4"
W-Wide Flange: W18X35	1.14	CF	17' - 4"
W-Wide Flange: W18X35	1.15	CF	17' - 4"
W-Wide Flange: W18X35	1.15	CF	17' - 4"
W-Wide Flange: W18X35	1.15	CF	17' - 4"
W-Wide Flange: W18X35	1.15	CF	17' - 4"

W-Wide Flange: W18X35	1.15	CF	17' - 4"
W-Wide Flange: W18X35	0.91	CF	17' - 4"
W-Wide Flange: W18X35	0.91	CF	13' - 0"
W-Wide Flange: W18X35	0.89	CF	13' - 0"
W-Wide Flange: W18X35	0.89	CF	12' - 8"
W-Wide Flange: W18X35	1.6	CF	12' - 8"
W-Wide Flange: W18X40	1.62	CF	20' - 8"
W-Wide Flange: W18X40	1.6	CF	21' - 0"
W-Wide Flange: W18X40	1.62	CF	20' - 8"
W-Wide Flange: W18X40	1.6	CF	21' - 0"
W-Wide Flange: W18X40	1.62	CF	20' - 8"
W-Wide Flange: W18X40	1.6	CF	21' - 0"
W-Wide Flange: W18X40	1.62	CF	20' - 8"
W-Wide Flange: W18X40	1.62	CF	21' - 0"
W-Wide Flange: W18X40	1.61	CF	21' - 0"
W-Wide Flange: W18X40	1.62	CF	20' - 8"
W-Wide Flange: W18X40	1.61	CF	21' - 0"
W-Wide Flange: W18X40	1.64	CF	20' - 8"
W-Wide Flange: W18X40	1.61	CF	21' - 0"
W-Wide Flange: W18X40	1.64	CF	20' - 8"
W-Wide Flange: W18X40	1.61	CF	21' - 0"
W-Wide Flange: W18X40	1.36	CF	20' - 8"
W-Wide Flange: W18X40	1.36	CF	17' - 4"
W-Wide Flange: W18X40	1.66	CF	17' - 4"
W-Wide Flange: W18X50	1.66	CF	17' - 4"
W-Wide Flange: W18X50	1.77	CF	17' - 4"
W-Wide Flange: W18X50	1.77	CF	18' - 8"
W-Wide Flange: W18X50	1.79	CF	18' - 8"
W-Wide Flange: W18X50	1.81	CF	18' - 8"
W-Wide Flange: W18X50	1.79	CF	18' - 8"
W-Wide Flange: W18X50	1.81	CF	18' - 8"
W-Wide Flange: W18X50	1.79	CF	18' - 8"
W-Wide Flange: W18X50	1.81	CF	18' - 8"
W-Wide Flange: W18X50	1.66	CF	18' - 8"
W-Wide Flange: W18X50	1.66	CF	17' - 4"
W-Wide Flange: W18X50	4.12	CF	17' - 4"
W-Wide Flange: W18X60	4.12	CF	35' - 0"
W-Wide Flange: W18X60	4.12	CF	35' - 0"
W-Wide Flange: W18X60	4.12	CF	35' - 0"
W-Wide Flange: W18X60	2.66	CF	35' - 0"



W-Wide Flange: W18X76	5.64	CF	18' - 3"
W-Wide Flange: W18X97	5.64	CF	29' - 7"
W-Wide Flange: W18X97	1.83	CF	29' - 7"
W-Wide Flange: W21X44	1.79	CF	21' - 4"
W-Wide Flange: W21X44	1.79	CF	21' - 0"
W-Wide Flange: W21X44	1.83	CF	21' - 0"
W-Wide Flange: W21X44	2.11	CF	21' - 4"
W-Wide Flange: W21X44	1.18	CF	24' - 6"
W-Wide Flange: W21X44	1.18	CF	14' - 0"
W-Wide Flange: W21X44	1.18	CF	14' - 0"
W-Wide Flange: W21X44	1.18	CF	14' - 0"
W-Wide Flange: W21X44	1.96	CF	14' - 0"
W-Wide Flange: W21X48	1.96	CF	21' - 0"
W-Wide Flange: W21X48	1.92	CF	21' - 0"
W-Wide Flange: W21X48	1.94	CF	20' - 8"
W-Wide Flange: W21X48	1.91	CF	21' - 0"
W-Wide Flange: W21X48	1.94	CF	20' - 8"
W-Wide Flange: W21X48	1.94	CF	21' - 0"
W-Wide Flange: W21X48	1.94	CF	21' - 0"
W-Wide Flange: W21X48	1.95	CF	21' - 0"
W-Wide Flange: W21X48	2.19	CF	21' - 0"
W-Wide Flange: W21X48	1.63	CF	23' - 6 7/8"
W-Wide Flange: W21X48	1.63	CF	17' - 4"
W-Wide Flange: W21X48	2.99	CF	17' - 4"
W-Wide Flange: W24X55	2.23	CF	28' - 0"
W-Wide Flange: W24X55	2.18	CF	21' - 0"
W-Wide Flange: W24X55	2.21	CF	20' - 8"
W-Wide Flange: W24X55	2.18	CF	21' - 0"
W-Wide Flange: W24X55	2.25	CF	20' - 8"
W-Wide Flange: W24X55	2.23	CF	21' - 4"
W-Wide Flange: W24X55	2.23	CF	21' - 0"
W-Wide Flange: W24X55	2.18	CF	21' - 0"
W-Wide Flange: W24X55	2.21	CF	20' - 8"
W-Wide Flange: W24X55	2.18	CF	21' - 0"
W-Wide Flange: W24X55	2.25	CF	20' - 8"
W-Wide Flange: W24X55	2.21	CF	21' - 4"
W-Wide Flange: W24X55	2.23	CF	21' - 0"
W-Wide Flange: W24X55	2.18	CF	21' - 0"
W-Wide Flange: W24X55	2.21	CF	20' - 8"
W-Wide Flange: W24X55	2.18	CF	21' - 0"

W-Wide Flange: W24X55	2.25	CF	20' - 8"
W-Wide Flange: W24X55	2.23	CF	21' - 4"
W-Wide Flange: W24X55	2.23	CF	21' - 0"
W-Wide Flange: W24X55	2.18	CF	21' - 0"
W-Wide Flange: W24X55	2.21	CF	20' - 8"
W-Wide Flange: W24X55	2.18	CF	21' - 0"
W-Wide Flange: W24X55	2.25	CF	20' - 8"
W-Wide Flange: W24X55	2.21	CF	21' - 4"
W-Wide Flange: W24X55	2.27	CF	21' - 0"
W-Wide Flange: W24X55	2.18	CF	21' - 0"
W-Wide Flange: W24X55	2.21	CF	20' - 8"
W-Wide Flange: W24X55	2.18	CF	21' - 0"
W-Wide Flange: W24X55	2.25	CF	20' - 8"
W-Wide Flange: W24X55	2.23	CF	21' - 4"
W-Wide Flange: W24X55	2.23	CF	21' - 0"
W-Wide Flange: W24X55	2.18	CF	21' - 0"
W-Wide Flange: W24X55	2.21	CF	20' - 8"
W-Wide Flange: W24X55	2.18	CF	21' - 0"
W-Wide Flange: W24X55	2.25	CF	20' - 8"
W-Wide Flange: W24X55	2.21	CF	21' - 4"
W-Wide Flange: W24X55	3.77	CF	21' - 0"
W-Wide Flange: W24X55	3.77	CF	35' - 0"
W-Wide Flange: W24X55	2.27	CF	35' - 0"
W-Wide Flange: W24X55	2.18	CF	21' - 0"
W-Wide Flange: W24X55	2.21	CF	20' - 8"
W-Wide Flange: W24X55	2.18	CF	21' - 0"
W-Wide Flange: W24X55	2.25	CF	20' - 8"
W-Wide Flange: W24X55	2.23	CF	21' - 4"
W-Wide Flange: W24X55	2.23	CF	21' - 0"
W-Wide Flange: W24X55	2.18	CF	21' - 0"
W-Wide Flange: W24X55	2.21	CF	20' - 8"
W-Wide Flange: W24X55	2.18	CF	21' - 0"
W-Wide Flange: W24X55	2.25	CF	20' - 8"
W-Wide Flange: W24X55	2.21	CF	21' - 4"
W-Wide Flange: W24X55	2.6	CF	21' - 0"
W-Wide Flange: W24X55	2.23	CF	24' - 6"
W-Wide Flange: W24X55	2.23	CF	21' - 0"
W-Wide Flange: W24X55	2.21	CF	21' - 0"
W-Wide Flange: W24X55	2.21	CF	21' - 0"
W-Wide Flange: W24X55	2.21	CF	21' - 0"

W-Wide Flange: W24X55	2.23	CF	21' - 0"
W-Wide Flange: W24X55	2.21	CF	21' - 0"
W-Wide Flange: W24X55	2.21	CF	21' - 0"
W-Wide Flange: W24X55	2.21	CF	21' - 0"
W-Wide Flange: W24X55	2.23	CF	21' - 0"
W-Wide Flange: W24X55	2.25	CF	21' - 0"
W-Wide Flange: W24X55	2.23	CF	21' - 0"
W-Wide Flange: W24X55	2.23	CF	21' - 0"
W-Wide Flange: W24X55	2.21	CF	21' - 0"
W-Wide Flange: W24X55	2.21	CF	21' - 0"
W-Wide Flange: W24X55	2.21	CF	21' - 0"
W-Wide Flange: W24X55	2.23	CF	21' - 0"
W-Wide Flange: W24X55	2.21	CF	21' - 0"
W-Wide Flange: W24X55	2.21	CF	21' - 0"
W-Wide Flange: W24X55	2.21	CF	21' - 0"
W-Wide Flange: W24X55	2.23	CF	21' - 0"
W-Wide Flange: W24X55	2.25	CF	21' - 0"
W-Wide Flange: W24X55	2.23	CF	21' - 0"
W-Wide Flange: W24X55	2.23	CF	21' - 0"
W-Wide Flange: W24X55	2.21	CF	21' - 0"
W-Wide Flange: W24X55	2.21	CF	21' - 0"
W-Wide Flange: W24X55	2.21	CF	21' - 0"
W-Wide Flange: W24X55	2.23	CF	21' - 0"
W-Wide Flange: W24X55	2.21	CF	21' - 0"
W-Wide Flange: W24X55	2.21	CF	21' - 0"
W-Wide Flange: W24X55	2.21	CF	21' - 0"
W-Wide Flange: W24X55	2.23	CF	21' - 0"
W-Wide Flange: W24X55	2.21	CF	21' - 0"
W-Wide Flange: W24X55	2.21	CF	21' - 0"
W-Wide Flange: W24X55	2.23	CF	21' - 0"
W-Wide Flange: W24X55	2.21	CF	21' - 0"
W-Wide Flange: W24X55	2.21	CF	21' - 0"
W-Wide Flange: W24X55	2.23	CF	21' - 0"
W-Wide Flange: W24X55	2.25	CF	21' - 0"
W-Wide Flange: W24X55	1.91	CF	21' - 0"

W-Wide Flange: W24X55	1.95	CF	18' - 3"
W-Wide Flange: W24X55	1.95	CF	18' - 8"
W-Wide Flange: W24X55	3.77	CF	18' - 8"
W-Wide Flange: W24X55	3.77	CF	34' - 8"
W-Wide Flange: W24X55	3.75	CF	34' - 8"
W-Wide Flange: W24X55	3.78	CF	34' - 8"
W-Wide Flange: W24X55	3.78	CF	34' - 8"
W-Wide Flange: W24X55	3.75	CF	34' - 8"
W-Wide Flange: W24X55	3.75	CF	34' - 8"
W-Wide Flange: W24X55	3.78	CF	34' - 8"
W-Wide Flange: W24X55	3.78	CF	34' - 8"
W-Wide Flange: W24X55	3.75	CF	34' - 8"
W-Wide Flange: W24X55	1.95	CF	34' - 8"
W-Wide Flange: W24X55	1.95	CF	18' - 8"
W-Wide Flange: W24X55	2.86	CF	18' - 8"
W-Wide Flange: W24X55	1.61	CF	26' - 8"
W-Wide Flange: W24X62	1.61	CF	14' - 0"
W-Wide Flange: W24X62	1.63	CF	14' - 0"
W-Wide Flange: W24X62	1.61	CF	14' - 0"
W-Wide Flange: W24X62	3.36	CF	14' - 0"
W-Wide Flange: W24X62	1.61	CF	28' - 0"
W-Wide Flange: W24X62	1.61	CF	14' - 0"
W-Wide Flange: W24X62	1.63	CF	14' - 0"
W-Wide Flange: W24X62	1.61	CF	14' - 0"
W-Wide Flange: W24X62	1.61	CF	14' - 0"
W-Wide Flange: W24X62	1.61	CF	14' - 0"
W-Wide Flange: W24X62	1.63	CF	14' - 0"
W-Wide Flange: W24X62	1.61	CF	14' - 0"
W-Wide Flange: W24X62	1.61	CF	14' - 0"
W-Wide Flange: W24X62	1.61	CF	14' - 0"
W-Wide Flange: W24X62	1.61	CF	14' - 0"
W-Wide Flange: W24X62	1.63	CF	14' - 0"
W-Wide Flange: W24X62	1.61	CF	14' - 0"
W-Wide Flange: W24X62	1.61	CF	14' - 0"
W-Wide Flange: W24X62	3.36	CF	14' - 0"
W-Wide Flange: W24X62	1.61	CF	27' - 6"
W-Wide Flange: W24X62	1.61	CF	14' - 0"
W-Wide Flange: W24X62	1.61	CF	14' - 0"
W-Wide Flange: W24X62	1.61	CF	14' - 0"
W-Wide Flange: W24X62	1.61	CF	14' - 0"
W-Wide Flange: W24X62	1.61	CF	14' - 0"
W-Wide Flange: W24X62	1.61	CF	14' - 0"

W-Wide Flange: W24X62	1.61	CF	14' - 0"
W-Wide Flange: W24X62	1.61	CF	14' - 0"
W-Wide Flange: W24X62	1.61	CF	14' - 0"
W-Wide Flange: W24X62	1.61	CF	14' - 0"
W-Wide Flange: W24X62	1.61	CF	14' - 0"
W-Wide Flange: W24X62	1.61	CF	14' - 0"
W-Wide Flange: W24X62	1.61	CF	14' - 0"
W-Wide Flange: W24X62	1.61	CF	14' - 0"
W-Wide Flange: W24X62	2.24	CF	14' - 0"
W-Wide Flange: W24X62	2.24	CF	18' - 8"
W-Wide Flange: W24X62	2.47	CF	18' - 8"
W-Wide Flange: W24X68	4.67	CF	18' - 8"
W-Wide Flange: W24X68	3.9	CF	34' - 8"
W-Wide Flange: W24X68	5.16	CF	29' - 3"
W-Wide Flange: W24X76	5.16	CF	34' - 8"
W-Wide Flange: W24X76	5.16	CF	34' - 8"
W-Wide Flange: W24X76	5.16	CF	34' - 8"
W-Wide Flange: W24X76	5.24	CF	34' - 8"
W-Wide Flange: W24X76	5.24	CF	34' - 8"
W-Wide Flange: W24X76	5.24	CF	34' - 8"
W-Wide Flange: W24X76	5.24	CF	34' - 8"
W-Wide Flange: W24X76	5.22	CF	34' - 8"
W-Wide Flange: W24X76	5.22	CF	34' - 8"
W-Wide Flange: W24X76	6.99	CF	34' - 8"
W-Wide Flange: W27X84	6.99	CF	42' - 0"
W-Wide Flange: W27X84	5.77	CF	42' - 0"
W-Wide Flange: W27X84	6.99	CF	35' - 0"
W-Wide Flange: W27X84	6.99	CF	42' - 0"
W-Wide Flange: W27X84	6.99	CF	42' - 0"
W-Wide Flange: W27X84	6.99	CF	42' - 0"
W-Wide Flange: W27X84	5.77	CF	42' - 0"
W-Wide Flange: W27X84	6.72	CF	35' - 0"
W-Wide Flange: W30X99	6.72	CF	34' - 8"
W-Wide Flange: W30X99	6.72	CF	34' - 8"
W-Wide Flange: W30X99	6.72	CF	34' - 8"
W-Wide Flange: W30X99	6.75	CF	34' - 8"
W-Wide Flange: W30X99	6.75	CF	34' - 8"
W-Wide Flange: W30X99	6.75	CF	34' - 8"
W-Wide Flange: W30X99	6.75	CF	34' - 8"









W-Wide Flange: W30X99	6.75	CF	34' - 8"
W-Wide Flange: W30X99	6.75	CF	34' - 8"
W-Wide Flange: W30X99	6.75	CF	34' - 8"
W-Wide Flange: W30X99	6.75	CF	34' - 8"
W-Wide Flange: W30X99	6.75	CF	34' - 8"
W-Wide Flange: W30X99	6.72	CF	34' - 8"
W-Wide Flange: W30X99	6.72	CF	34' - 8"
W-Wide Flange: W30X99	6.72	CF	34' - 8"
W-Wide Flange: W30X99	6.72	CF	34' - 8"
W-Wide Flange: W30X99	7.97	CF	34' - 8"
W-Wide Flange: W30X116	7.97	CF	35' - 0"
W-Wide Flange: W30X116	7.97	CF	35' - 0"
W-Wide Flange: W30X116	16.31	CF	35' - 0"
W-Wide Flange: W33X118	16.26	CF	69' - 4"
W-Wide Flange: W33X118	16.26	CF	69' - 4"
W-Wide Flange: W33X118	16.26	CF	69' - 4"
W-Wide Flange: W33X118	16.26	CF	69' - 4"
<b>Totals</b>	<b>3358.52</b>	<b>CF</b>	

## **Appendix K: Development of the WPI Recreational Center**

Over the past couple years WPI has tried to modernize the buildings and facilities on campus, with the construction of the Bartlett Center, East hall and alumni field; this year the plan was to build a brand new athletic facility. Last spring, when our MQP was assembled, WPI was going through the process of evaluating a conceptual design of the facility. Construction was slated to start in the summer of 2009 and was our initial project for completing our MQP, unfortunately, due to the economy at the time, WPI decided to hold off on the project for at least another year; resulting in us needing to find another MQP.

To get a good understanding of how the different parties worked together we attended the design meetings and watched the interactions between the different groups. WPI is the owner and Gilbane Building Co was hired as the construction manager. Many different people within the WPI community attended these meetings, from the president down to the equipment manager. All parties worked together to develop a conceptual design that looked good and fit in with the surrounding buildings and a facility that would fall within budget. The budget for the project was roughly 60 million and Gilbane's part of the project at that point was to help WPI decide what parts of the facility were wants vs. needs. We attended roughly 4 meetings and saw the conceptual design change quite a bit from the 1<sup>st</sup> meeting to the last meeting. Overall, although the project didn't go through, it was a good experience to see how a CM can assist an owner in the early stages of a project. Through this experience, our group has learned the hard way on how quickly a project can change because of the economy.